Annexure-A

NOC FROM IRRIGATION DEPARTMENT



Office of the

Superintending Engineer, Link Circle Canal Bank Dharampura Lahore. Phone # +92 42 99250310 Email: se!ink_canal@yahoo.com

Page 536

IRRIGATION DEPARTMENT

6-699

Τo

The Managing Director, WASA, LDA, Lahore.

No. 5224/124-G Dated 05-12-2977

Subject:

Reference

WASA LDA LAHORE

2

Diary No

Date <u>h-</u>

DMD (FA'& R)

LIMD (O & M)

DMD (Engg)L

D (P & E)

MD

443X

(A)

 (\mathbf{B})

NOC REGARDING SURFACE WATER INDUCTION AND CONSTRUCTION OF WATER TREATMENT PLANT.

Chief Engineer, Irrigation Lahore Zone, Lahore letter Nos.
i. 2383/WII/2017/18076-77/57/2016, dated 22-08-2017 (Annexed with minutes of the meeting dated 26-07-2017).
ii. 2835/WII/LHR/2017/22022/3/2017, dated 13-10-2017 (Annexed with minutes of the meeting dated 19-09-2017).
iii. 3429/WII/LHR/2017/26757-58 / 57/2016, dated 30-11-2017 (Annexed with minutes of the meeting dated 23-11-2017).
Director Planning and Design, WASA, LDA, Lahore letter No. P&D/1212-17, dated 04-10-2017.

All the above reference letters of worthy Chief Engineer, Irrigation The Labore Zone, Labore on the above cited subject along with annexures were endorsed to concerned Executive Engineer, Chakbandi Division, Labore, for immediate compliance. In this regards, Executive Engineer, Chakbandi Division, Labore has reported vide letter No. # 380/43-WB, dated 04-12-2017 (copy attached) wherein he has described the prevailing situation regarding capacity and safety of BRBD Link Canal.

Anyhow, this committed 100 Cs from BRBD Link Canal for drinking water to Lahore city vide minutes of the meeting dated 27-07-2017 can be managed and can be provided by Punjab Irrigation Department.

In this context of foregoing, undersigned as Superintending Engineer, Link Circle, Lahore has no objection in providing 100 Cs to WASA from R.D. 279+500/R (Escape structure) as phase-01. You are requested to sign an agreement

For Record



Office of the

Superintending Engineer, Link Circle Canal Bank Dharampura Lahore. Phone # +92 42 99250310 Email: selink_canal@yahoo.com

with the Executive Engineer, Chakbandi Division, Lahore for provision of this 100 Cs at the disposal of WASA.

D.A/As above

1.

2.

3.

Superint ngineer, "Etnk Circle, Lahore

C.C.

Secretary to Govt. of the Punjab, Irrigation Department, Lahore.

Chief Engineer, Irrigation Lahore Zone, Lahore, for information, guidance and with the request to direct the Consultants (G3) to give an immediate appropriate solution for enhancing capacity of BRBD Link so as to supply this 100 Cs and future supplies without stress over the BRBD Link Canal.

Executive Engineer, Chakbandi Division, Lahore, for necessary action as per rules and regulation.



Annexure-B

CONSTRUCTION ACTIVITIES AND MATERIALS

PC-1 of LWWMP, Construction of SWTP-June2019 Prepared by: MM Pakistan (Pvt.) Ltd.

Annexure - B

Construction Activities and Materials Cost Estimates Breakup - Capital Cost

	Capital Cost - Summary	1	. US\$ = 150 PKR
Sr. No.	Description	Amount (PKR in Million)	Amount (USD in Million)
	New Ravi Syphon, Intake Structure and Raw Water Channel (as		
1	per feasibility level estimate provided by Punjab Irrigation		
	Department - Breakup is attached at Annexure-11)	4 6 6 4 0 4	24.00
2	I Otal Cost A	4,661.94	31.08
2	Surface water Treatment Plant (SWTP) - Civil and E&W Works		
2.1	Civil Works	22.17	0.15
2.1.1	Naw Water Talik and Kaw Water Pullip House	127.11	0.15
2.1.2		127.41	0.85
2.1.3		2.34	0.02
2.1.4	Flocculation & Clarifiers	408.70	2.72
2.1.5	Sludge Enickener	16.07	0.11
2.1.6	Sludge Drying Beds with Shades	39.13	0.26
2.1.7	Rapid Gravity Filtration Unit	168.60	1.12
2.1.8	Clear Water Tank, Pump House and Disinfection Room	348.23	2.32
2.1.9	Chemical Storage Building and Alum Dozing Station	44.77	0.30
2.1.10	Admin Building	5.81	0.04
2.1.11	Staff Quarters	19.35	0.13
2.1.12	Internal Roads, H.I & Transformers Room	73.97	0.49
	Sub Total (2.1)	1,276.55	8.51
2.2	Electrical & Mechanical Works including SCADA System		
2.2.1	Supplying and Installation of Mechanical Equipment including Pumping Machinery etc.	2,942.09	19.61
2.2.2	Supplying and Installation of Electrical Equipment etc.	2,042.84	13.62
2.2.3	SCADA and Instrumentation	228.87	1.53
	Sub Total (2.2)	5,213.80	34.76
	Total (2.1 + 2.2)	6,490.35	43.27
3	Transmission Main (HDPE Pipe)		
3.1	Transmission Main including Valves, Fittings etc. (HDPE Pipe - Length 3.5 km)	642.25	4.28
	Total (3)	642.25	4.28
4	Feeding Main for 04 Serving Areas (HDPE Pipe)		
4.1	Feeding Main including Valves, Fittings etc. (HDPE Pipe)	2,732.59	18.22
	Total (4)	2,732.59	18.22
5	Construction and Rehabilitation of Distribution Network including Water Meters		
5.1	Distribution Network including Valves, Fittings etc. (HDPE Pipe)	470.46	3.14
5.2	Supply and Fixing Leakage Detection Equipment (NRW)	150.00	1.00
5.3	Domestic & Bulk Water Meters and Water Flow Meters	1,352.01	9.01
	Total (5)	1,972.47	13.15
6	Miscellaneous Works		

	Capital Cost - Summary	1	US\$ = 150 PKR
Sr. No.	Description	Amount (PKR in Million)	Amount (USD in Million)
6.1	Substation for External Electrification by LESCO	450.00	3.00
6.2	Shifting of Services of Electricity, SuiGas, PTCL Cable and Electric Poles	150.00	1.00
6.3	Restoration of Roads	50.00	0.33
6.4	General Items with Allied Works	60.00	0.40
	Total (6)	710.00	4.73
	Total B (2+3+4+5+6)	12,547.66	83.65
	Additional cost for Mega Projects @ 4.16% on Civil Works	53.10	0.35
	PRA @ 5 %	627.38	4.18
	Cost for Owner's Engineer Consultancy Services	206.18	1.37
	PMU-LWASA Establishment	211.21	1.41
	Plantation Cost (L.S)	10.00	0.07
	Total Cost	13,655.54	91.04
	Contingencies @ 2 %	273.11	1.82
	Total Cost B	13,928.65	92.86
	Capital Cost (A+B)	18,590.59	123.94
	O&M Cost for 02 years	1,360.75	9.07
	Total Cost	19,951.34	133.01

2.1.1.	2.1.1. Raw Water Tank and Raw Water Pump House						
	MRS, 1st BI-Annual-2019 (1st January-2019 to 30th June-2019) District Lahore						
Sr. No.	Sr. No.DescriptionQuantityUnitRate					Amount(PKR)	
Α	Raw Water Tank						
1	Chapter 3 Item 21-b						
	Earthwork excavation in irrigation channels, drains, etc. to designed section, grades and profiles, excavated material disposed-off and dressed within 50 ft. (15 m) lead: i) In ordinary Soil.	1854.169	Cu:m	1.00	233.65	433,227.00	
2	Chapter 6 Item 5-h						

2.1.1.	2.1.1. Raw Water Tank and Raw Water Pump House						
	MRS, 1st BI-Annual-2019 (1st January-	2019 to 30th Ju	ne-2019)	District	Lahore		
Sr. No.	Description	Quanti	ty	Unit	Rate	Amount(PKR)	
	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone						
	Apron Ratio 1: 3: 6	192.953	Cu:m	1.00	6967.65	1,344,425.00	
	Apron Ratio 1: 2: 4	16.37	Cu:m	1.00	7,964.85	130,345.00	
3	Chapter 6 Item 6-i-ii		A			· · · ·	
	Providing and laying reinforced cement concrete (including pre-stressed concrete), using coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete (but excluding the cost of steel reinforcement, its fabrication and placing in position, etc.):- (a)(ii) Reinforced cement concrete in slab of rafts / strip foundation, base slab of column and retaining walls; etc. and other structural members other than those mentioned in 5(a) (i) above not requiring form work (i.e. horizontal shuttering) complete in all respects: (2) Type B (nominal mix 1: 1½: 3) RCC Base Slab	176.588	Cum	1.00	10401.75	1,836,819.00	
	(a) (i) Reinforced cement concrete in roof slab	170.500	cum	1.00	10401.75	1,030,013.00	
	beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or pre-stressed members cast in situ, complete in all respects:	182 448	Curm	1.00	13818 95	2 521 240 00	
	Cantilever BCC ton Slabs Batio (1·2·4)	13 530	Curm	1.00	9324 50	126 160 00	
4	Chanter 6 Item 9-c	13.550	cu.iii	1.00	5524.50	120,100.00	
<u></u> τ	Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):-('c) Deformed bars (Grade-60) Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):-('c) Deformed bars (Grade-60)	73,160.10	Kg	100	13,646.00	9,983,427.00	
5	Chapter 1 item 1						
	carriage of 100 Cft. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cft. (4.25 cu.m) of timber, by truck or by any other means owned by the contractor.(Lead Up to 400 KM)	503.00	Cu:m	1.0	2090.56	1,051,561.00	
6	Chapter 21 Item 13		1	1			

2.1.1.	2.1.1. Raw Water Tank and Raw Water Pump House						
	MRS, 1st BI-Annual-2019 (1st January-	2019 to 30th Ju	ne-2019)	District	Lahore		
Sr. No.	Description	Quantii	ty	Unit	Rate	Amount(PKR)	
	Providing and fixing 1¼"x1¼"x3/16" (31x31x5 mm) angle iron step, in manhole chambers, including carriage and setting the same in work to correct lines and levels	154	No	1.0	284.25	43,775.00	
7	Chapter 6 Item 28						
	Providing embedding 10" (250 mm) wide ¼" (6 mm) thick rubber water stopper in expansion joints of R.C.C. roof slab complete in all respects.	2644.800	m	1.0	230.55	609,759.00	
8	Chapter 18 Item 13						
	Providing and fixing G.I. pipe railing, as per	93.750	m	1.0	3031.70	284,222.00	
	standard drawing.						
9	Rehandling of earthwork: a) Lead up to a single throw of Kassi, phaorah or shovel	368.213	Cu:m	1.0	55.30	20,362.00	
10	Chapter 3 Item 17.a.b.c						
	Iransportation of earth all types when the total distance, including the lead covered in the item of work, is more than 1000 ft. (300 m) a) up to ¼ mile (400 m). b) for every 330 ft. (100 m) additional lead or part thereof, beyond ¼ mile (400 m) up to one mile. (1.6 Km.) c) for every ¼ mile (400 m) additional lead or part thereof, beyond one mile (1.6 Km.) up to 5 miles (8 Km). d) for every ½ mile (800 m) additional lead or part thereof, beyond 5 miles (8 Km).(Lead up to 8 Km)	1337.361	Cu:m	1.0	250.75	335,343.00	
					Sub-Total(A)	18,720,665.00	
В	Raw Water Pump House						
1	Chapter-7,ltem 5-i						
	Pacca brick work in ground floor: i) cement, sand mortar:	145.259	Cu:m	1.00	7821.30	1,136,112.00	
2	Chapter-6,Item6-a-iii						
3	Providing and laying reinforced cement concrete (including pre-stressed concrete), using coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete (but excluding the cost of steel reinforcement, its fabrication and placing in position, etc.): a). Reinforced cement concrete in roof slab, beams, columns, lintels, girders and other structural members laid in situ or pre-cast laid in position, or pre-stressed members cast in situ, complete in all respect, Type C (nominal mix 1:2:4) Ch-6,Item-9(b)	53.172	Cu:m	1.00	6967.65	370,484.00	
<u> </u>	Fabrication of mild steel reinforcement for						
	cement concrete, including cutting, bending, laying in position, making joints and fastenings, including cost of binding wire and labour charges	5,317.20	Kg	100	13,646.00	725,585.00	

2.1.1.	2.1.1. Raw Water Tank and Raw Water Pump House						
	MRS, 1st BI-Annual-2019 (1st January	-2019 to 30th Ju	ne-2019)	District I	ahore		
Sr. No.	Description	Quanti	ty	Unit	Rate	Amount(PKR)	
Δ	for binding of steel reinforcement (also includes removal of rust from bars):- ('c) Deformed bars (Grade40)						
	Carriage of 100 Cft. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cft. (4.25 cu.m) of timber, by truck or by any other means owned by the contractor.(Lead Up to 400 KM)	126.54	Cu:m	1.0	2090.56	264,542.00	
5	Ch-11,Item-10(b) Cement plaster 3/8" (10 mm) thick under soffit of R.C.C. roof slabs only, up to 20' height. b) 1:3	220.00	Sq.m	1.00	228.10	50,182.00	
6	Ch-11,Item-9(b) Cement plaster 1/2" thick in 1:4 up to 20 ft height	372.300	Sq.m	1.00	201.30	74,944.00	
7	Ch-11,Item-25(a-iii) White washing 3 coats on new surface.	412.300	Sq.m	1.00	30.75	12,678.00	
0	Cement pointing 1:2 struck joints, on wall up to 20' height, i/c extra cost of labour and material for red oxide pigment in cement pointing to match with the colour of bricks (i) Ratio 1:5	370.600	Sq.m	1.00	216.70	80,309.00	
9	Ch-6,Item-3(b) Cement concrete brick or stone ballast 1½ " to 2" (40 mm to 50 mm) gauge, in foundation and plinth: (b) Ratio 1: 4: 8	33.00	Cu:m	1.00	4738.15	156,359.00	
10	Ch-10,Item-15(i) Providing and laying topping of cement concrete 1:2:4, including surface finishing and dividing in panels:-3"Thick	220.00	Sq.m	1.00	715.25	157,355.00	
11	Ch-10,Item-42 Providing and fixing marble strip of any shade for dividing the mosaic flooring into panels a) Size 1 ¹ / ₂ " x 3/8" (40 x 10 mm)	132.00	m	1.00	21.65	2,858.00	
12	Ch-9,Item-5 Single layer of tiles 9"x4½"x1½" (225x113x40 mm) laid over 4"(100 mm) earth and 1" (25 mm) mud plaster without Bhoosa, grouted with cement sand 1:3 on top of RCC roof slab, provided with 34 lbs. per %Sft. or 1.72 Kg/Sq.m bitumen coating sandblinded.	231.44	Sq.m	1.00	732.85	169,609.00	
13	Ch-9,Item-14 Khassi pernalas in cement sand mortar 1:2, 12" outside width finished smooth with a floating coat of neat cement	18.0	m	1.00	338.50	6,093.00	
14	Ch-9, Item-15 Khurra on roof 2' x 2' x 6" (600 x 600 x 150 mm)	4.000	No	1.00	499.65	1,999.00	
15	Ch-9,Item-16						

2.1.1.	2.1.1. Raw Water Tank and Raw Water Pump House					
	MRS, 1st BI-Annual-2019 (1st January-	2019 to 30th Ju	ne-2019)	District	Lahore	
Sr. No.	Description	Quantii	ty	Unit	Rate	Amount(PKR)
	BottomKhurasofbrick masonry in cement mortar 1:6, 4'x2'x4½" (1200x600x113 mm) over 3" (75 mm) cement concrete 1:4:8.	4.000	No	1.00	887.25	3,549.00
16	Ch-25,Item-41(b-v)					
	Providing and fixing steel windows with openable glazed panels, using beam section for frame 1½"x1"x5/8"x1/8" (40x25x16x3 mm), Z-section for leaves ¾"x1"x¾"x1/8" (20x25x20x3 mm), T-section sashes 1"x1"x1/8" (25x25x3 mm), glass panes, wooden screed for glazing embedded over a thin layer of putty duly screwed with leaves, brass fittings, holdfast, duly painted, complete in all respects, including all cost of material and labour, etc. as per approved design and as directed by the Engineer-in-charge:-b) fixed with wire gauze, 22 SWG v) glass pane 5 mmthick	21.60	Sq.m	1.00	5070.80	109,529.00
17	Ch-25,Item-31					
	Making and fixing steel grated door with 1/16" thick (1.5mm) sheeting, including angle iron frame 2"x2"x3/8" (50x50x10 mm) and ¾" (20 mm) square bars 4" (100 mm) centre to centre, with lockingarrangement.	6.45	Sq.m	1.00	11121.40	71,733.00
18	Ch-12,Item-31					
	Providing and fixing M.S. flat ½"x1/8" (13mm x 3mm) grill including ¾" x 1/8" (20 mmx3 mm) M.S. flat frame, in windows of approved design, including painting three coats, complete in all respects.	21.60	Sq.m	1.00	2360.75	50,992.00
19	Ch-13, Item-5(c-i & ii)					
	Painting new surface: c) Preparing surface and painting of doors and windows any type (includingedges):					
	i) priming coat.	12.90	Sq.m	1.00	82.45	1,064.00
	ii) each subsequent coat of paint. (Two Coats)	25.800	Sq.m	1.00	44.30	1,142.00
					Sub-Total(B)	3,447,118.00
					Total (A+B)	22,167,783.00
				Rupe	es in Million	22.168

2.1.2.1	2.1.2. Pre-SedimentationTanks						
	MRS, 1st BI-Annual-2019 (1st January-2019 to 30th June-2019) District Lahore						
Sr. No.	Description	Quantit	Unit	Rate	Amount(PKR)		
1	Chapter 3 Item 21-b						
	Earthwork excavation in irrigation channels, drains, etc. to designed section, grades and profiles, excavated material disposed-off and	114,37.34	Cu:m	1.00	233.65	2,672,333.00	

2.1.2.1	2.1.2.Pre-SedimentationTanks					
	MRS, 1st BI-Annual-2019 (1st January-	2019 to 30th Ju	ne-2019)	District	Lahore	
Sr. No.	Description	Quantit	:y	Unit	Rate	Amount(PKR)
	dressed within 50 ft. (15 m) lead: i) In ordinary Soil.					
2	Chapter 6 Item 5-h					
	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate):					
	Apron Ratio 1: 3: 6	2,068.30	Cu:m	1.00	6,947.65	14,369,859.00
	Apron Ratio 1: 2: 4	434.40	Cu:m	1.00	7,964.85	3,459,931.00
3	Chapter 6 Item 6-i-ii					
	Providing and laying reinforced cement concrete (including pre-stressed concrete), using coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete (but excluding the cost of steel reinforcement, its fabrication and placing in position, etc.):-					
	(a)(ii) Reinforced cement concrete in slab of rafts / strip foundation, base slab of column and retaining walls; etc. and other structural members other than those mentioned in 5(a) (i) above not requiring form work (i.e. horizontal shuttering) complete in all respects:					
	(2) Type B (nominal mix 1: 1½: 3)	1 (22 01	Cuura	1.00	10 401 75	10 005 471 00
	(a) (i) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or pre-stressed members cast in situ, complete in all respects:	1,033.91	cuim	1.00	10,401.75	16,995,471.00
	RCC Walls (1:1 1/2:3)	719.33	Cu:m	1.00	13,818.95	9,940,441.00
	Cantilever RCC top Slabs Ratio (1:2:4)	129.44	Cu:m	1.00	9,324.50	1,206,987.00
4	Chapter 6 Item 9-c Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):-('c) Deformed bars (Grade-60) Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):-('c) Deformed bars (Grade 50)	483,592.05	Kg	100	13,646.00	65,990,971.00
5	Chapter 1 Item 1					
	Carriage of 100 Cft. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cft. (4.25 cu.m) of timber, by	2,472.90	Cu:m	1.0	2,090.56	5,169,750.00

2.1.2.	2.1.2.Pre-SedimentationTanks					
	MRS, 1st BI-Annual-2019 (1st January-	2019 to 30th Ju	ne-2019)	District	Lahore	
Sr. No.	Description	Quanti	ty	Unit	Rate	Amount(PKR)
	truck or by any other means owned by the contractor (Lead Lin to 400 KM)					
6	Chapter 21 Item 13					
	Providing and fixing 1¼"x1¼"x3/16" (31x31x5 mm) angle iron step, in manhole chambers, including carriage and setting the same in work to correct lines and levels.	208	No.	1.0	284.25	59,124.00
7	Chapter 6 Item 28					
	Providing embedding 10" (250 mm) wide ¼" (6 mm) thick rubber water stopper in expansion joints of R.C.C. roof slab complete in all respects.	7,099.56	m	1.0	230.55	1,636,804.00
8	Chapter 13 Item 9-ii					
	Bitumen coating to plastered or cement concrete surface: ii) 14 lbs. per 100 Sft. (6.35 Kg per Sq.m)	1,209.60	Sm	1.0	76.75	92,837.00
9	Chapter 18 Item 13					
	Providing and fixing G.I. pipe railing, as per standard drawing.	1137.000	m	1.0	3031.70	3,447,043.00
10	Chapter 3 Item 13.i					
	Rehandling of earthwork: a) Lead up to a single throw of Kassi, phaorah or shovel	1233.468	Cu:m	1.0	55.30	68,211.00
11	Chapter 3 Item 17.a.b.c					
	Transportation of earth all types when the total distance, including the lead covered in the item of work, is more than 1000 ft. (300 m) a) up to ¼ mile (400 m). b) for every 330 ft. (100 m) additional lead or part thereof, beyond ¼ mile (400 m) up to one mile. (1.6 Km.) c) for every ¼ mile (400 m) additional lead or part thereof, beyond one mile (1.6 Km.) up to 5 miles (8 Km). d) for every ½ mile (800 m) additional lead or part thereof, beyond 5 miles (8 Km).(Lead up to 8 Km)	9183.480	Cu:m	1.0	250.75	2,302,758.00
					Total	127,412,520.00
				Rupe	es in Million	127.413

2.1.3.	Coagulation Chambers					
	MRS, 1st BI-Annual-2019 (1st January-	2019 to 30th Ju	ne-2019)	District	Lahore	
Sr. No.	Description Quantity Unit Rat				Rate	Amount(PKR)
1	Chapter 3 Item 21-b					
	Earthwork excavation in irrigation channels, drains, etc. to designed section, grades and profiles, excavated material disposed-off and dressed within 50 ft. (15 m) lead: i) In ordinary Soil.	80.725	Cu:m	1.00	233.65	18,861.00
2	Chapter 6 Item 5-h					
	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate):					
	Apron Ratio 1: 3: 6	13.91	Cu:m	1.00	6,947.65	96,635.00

2.1.3.	2.1.3. Coagulation Chambers					
	MRS, 1st BI-Annual-2019 (1st January-	2019 to 30th Ju	ne-2019)	District	Lahore	
Sr. No.	Description	Quantii	ty	Unit	Rate	Amount(PKR)
	Apron Ratio 1: 2: 4	2.59	Cu:m	1.00	7.964.85	20.647.00
3	Chapter 6 Item 6-i-ii					
	Providing and laying reinforced cement concrete					
	(including pre-stressed concrete), using coarse					
	sand and screened graded and washed aggregate,					
	in required shape and design, including forms,					
	moulds, shuttering, lifting, compacting, curing,					
	rendering and finishing exposed surface,					
	complete (but excluding the cost of steel					
	reinforcement, its fabrication and placing in					
	position, etc.):-					
	(a)(II) Reinforced cement concrete in stab of raits					
	retaining walls: etc. and other structural members					
	other than those mentioned in 5(a) (i) above not					
	requiring form work (i.e. horizontal shuttering)					
	complete in all respects:					
	(2) Type B (nominal mix 1: 1½: 3)					
	RCC Base Slab	13.30	Cu:m	1.00	10,401.75	138,320.00
	(a) (i) Reinforced cement concrete in roof slab,					
	beams, columns lintels, girders and other					
	structural members laid in situ or precast laid in					
	position, or pre-stressed members cast in situ,					
	complete in all respects:					
	RCC Walls (1:11/2:3)	26.28	Cu:m	1.00	13,818.95	363,181.00
	Cantilever RCC top Slabs Ratio (1:2:4)	10.00	Cu:m	1.00	9,324.50	93,266.00
4	Chapter 6 Item 9-c		-	1		
	Fabrication of mild steel reinforcement for					
	cement concrete, including cutting, bending,					
	laying in position, and fastenings, including cost of					
	binding wire and labour charges for binding of					
	steel reinforcement (also includes removal of rust					
	From bars):-(c) Deformed bars (Grade-60)	0 707 22	Ka	100	12 646 00	1 100 119 00
	cament concrete including cutting bending	0,707.32	кg	100	13,040.00	1,199,118.00
	laving in position and fastenings including cost of					
	hinding wire and labour charges for hinding of					
	steel reinforcement (also includes removal of rust					
	from bars): ('c) Deformed bars (Grade-60)					
5	Chapter 1 Item 1					
	Carriage of 100 Cft. (2.83 cu.m) of all materials like					
	stone aggregate, spawl, kankar lime (unslaked),					
	surkhi, etc. or 150 Cft. (4.25 cu.m) of timber, by	49.96	Cu:m	1.00	2,090.00	104,422.00
	truck or by any other means owned by the					
	contractor.(Lead Up to 400 KM)					
6	Chapter 21 Item 13					
	Providing and fixing 1¼"x1¼"x3/16" (31x31x5					
	mm) angle iron step, in manhole chambers,	64.00	No	1.00	284.25	18,192.00
	including carriage and setting the same in work					
7	Chanter 6 Item 28					
/			1	1		

2.1.3.Coagulation Chambers							
MRS, 1st BI-Annual-2019 (1st January-2019 to 30th June-2019) District Lahore							
Sr. No.	Description	Quantit	ty	Unit	Rate	Amount(PKR)	
	Providing embedding 10" (250 mm) wide ¼" (6 mm) thick rubber water stopper in expansion joints of R C C roof slab complete in all respects	103.06	m	1.00	230.55	23,760.00	
8	Chapter 13 Item 9-ii						
	Bitumen coating to plastered or cement concrete surface: ii) 14 lbs. per 100 Sft. (6.35 Kg per Sq.m)	144.22	Sm	1.00	76.75	11,069.00	
9	Chapter 18 Item 13						
	Providing and fixing G.I. pipe railing, as per standard drawing.	76.56	m	1.00	3,031.70	232,095.00	
10	Chapter 3 Item 13.i						
	Rehandling of earthwork: a) Lead up to a single throw of Kassi, phaorah or shovel	14.37	m	1.00	55.30	795.00	
11	Chapter 3 Item 17.a.b.c						
	Transportation of earth all types when the total distance, including the lead covered in the item of work, is more than 1000 ft. (300 m) a) up to ¼ mile (400 m). b) for every 330 ft. (100 m) additional lead or part thereof, beyond ¼ mile (400 m) up to one mile. (1.6 Km.) c) for every ¼ mile (400 m) additional lead or part thereof, beyond one mile (1.6 Km.) up to 5 miles (8 Km). d) for every ½ mile (800 m) additional lead or part thereof, beyond 5 miles (8 Km).(Lead up to 8 Km)	67.79	Cum	1.00	250.75	16,998.00	
					Total	2,337,359.00	
				Rupe	es in Million	2.337	

2.1.4.	2.1.4. Baffled Flocculators and Horizontal Clarifiers							
	MRS, 1st BI-Annual-2019 (1st January-	2019 to 30th Ju	ne-2019)	District	Lahore			
Sr. No.	Description	Quantit	ţy	Unit	Rate	Amount(PKR)		
1	Chapter 3 Item 21-b							
	Earthwork excavation in irrigation channels, drains, etc. to designed section, grades and profiles, excavated material disposed-off and dressed within 50 ft. (15 m) lead: i) In ordinary Soil.	42,984.69	Cu:m	1.00	233.65	10,043,374.00		
2	Chapter 6 Item 5-h							
	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate):							
	Apron Ratio 1: 3: 6	5,129.56	Cu:m	1.00	6,947.65	35,638,410.00		
	Apron Ratio 1: 2: 4	110.32	Cu m	1.00	7,964.85	878,746.00		
3	Chapter 6 Item 6-i-ii		_					
	Providing and laying reinforced cement concrete (including pre-stressed concrete), using coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface,							

2.1.4.	2.1.4. Baffled Flocculators and Horizontal Clarifiers							
	MRS, 1st BI-Annual-2019 (1st January-	2019 to 30th Ju	ne- 20 19)	District	Lahore			
Sr. No.	Description	Quantit	:y	Unit	Rate	Amount(PKR)		
	complete (but excluding the cost of steel reinforcement, its fabrication and placing in position, etc.):-							
	(a)(ii) Reinforced cement concrete in slab of rafts / strip foundation, base slab of column and retaining walls; etc. and other structural members other than those mentioned in 5(a) (i) above not requiring form work (i.e. horizontal shuttering) complete in all respects:							
	(2) Type B (nominal mix 1: 1½: 3)		_					
	RCC Base Slab	5,019.23	Cum	1.00	10,401.75	52,208,830.00		
	(a) (I) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or pre-stressed members cast in situ, complete in all respects:							
	RCC Walls (1:11/2:3)	3,049.54	Cu:m	1.00	13,818.95	42,141,551.00		
	Cantilever RCC top Slabs Ratio (1:2:4)	392.86	Cu:m	1.00	9,324.50	3,663,242.00		
	Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):-('c) Deformed bars (Grade-60) Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):('c) Deformed bars (Grade-60)	1,653,043	Kg	100	13,646.0	225,574,226.00		
5	Chapter 1 Item 1							
	Carriage of 100 Cft. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cft. (4.25 cu.m) of timber, by truck or by any other means owned by the contractor.(Lead Up to 400 KM)	11,960.30	Cu:m	1.0	2,090.56	25,003,728.00		
6	Chapter 21 Item 13							
	Providing and fixing 1¼"x1¼"x3/16" (31x31x5 mm) angle iron step, in manhole chambers, including carriage and setting the same in work to correct lines and levels.	240	No	1.0	284.25	68,220.00		
	Providing embedding 10" (250 mm) wide ¼" (6 mm) thick rubber water stopper in expansion joints of R.C.C. roof slab complete in all respects.	10,888.48	m	1.0	230.55	2,510,339.00		
8	Chapter 13 Item 9-ii Bitumen coating to plastered or cement concrete surface: ii) 14 lbs. per 100 Sft. (6.35 Kg per Sq.m)	23,15.52	Sm	1.0	76.75	177,716.00		

2.1.4. Baffled Flocculators and Horizontal Clarifiers								
	MRS, 1st BI-Annual-2019 (1st January-2019 to 30th June-2019) District Lahore							
Sr. No.	Description	Quanti	ty	Unit	Rate	Amount(PKR)		
9	Chapter 18 Item 13							
	Providing and fixing G.I. pipe railing, as per standard drawing.	3,409.44	m	1.0	3031.70	10,336,399.00		
10	Chapter 3 Item 13.i							
	Rehandling of earthwork: a) Lead up to a single throw of Kassi, phaorah or shovel	1,628.03	Cu:m	1.0	55.30	90,030.00		
11	Chapter 3 Item 17.a.b.c							
	Transportation of earth all types when the total distance, including the lead covered in the item of work, is more than 1000 ft. (300 m) a) up to ¼ mile (400 m). b) for every 330 ft. (100 m) additional lead or part thereof, beyond ¼ mile (400 m) up to one mile. (1.6 Km.) c) for every ¼ mile (400 m) additional lead or part thereof, beyond one mile (1.6 Km.) up to 5 miles (8 Km). d) for every ½ mile (800 m) additional lead or part thereof, beyond 5 miles (8 Km).(Lead up to 8 Km)	1,472.20	Cu:m	1.0	250.75	369,153.00		
	· · · · · · ·		•	•	Total	408,703,964.00		
				Rupe	es in Million	408.704		

2.1.5.SludgeThickeners							
	MRS, 1st BI-Annual-2019 (1st January-	2019 to 30th Ju	ne-2019)	District	Lahore		
Sr. No.	Description	Quanti	ty	Unit	Rate	Amount(PKR)	
1	Chapter 3 Item 21-b						
	Earthwork excavation in irrigation channels, drains, etc. to designed section, grades and profiles, excavated material disposed-off and dressed within 50 ft. (15 m) lead: i) In ordinary Soil.	2316.031	Cu:m	1.00	233.65	541,141.00	
2	Chapter 6 Item 5-h						
	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate):						
	Apron Ratio 1: 3: 6	212.850	Cu:m	1.00	6947.65	1,478,809.00	
	Apron Ratio 1: 2: 4	3.570	Cu:m	1.00	7964.85	28,437.00	
3	Chapter 6 Item 6-i-ii						
	Providing and laying reinforced cement concrete (including pre-stressed concrete), using coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete (but excluding the cost of steel reinforcement, its fabrication and placing in position, etc.):-						

2.1.5.	2.1.5. Sludge Thickeners							
	MRS, 1st BI-Annual-2019 (1st January-	2019 to 30th Ju	ne-2019)	District	Lahore			
Sr. No.	Description	Quantit	ty	Unit	Rate	Amount(PKR)		
	(a)(ii) Reinforced cement concrete in slab of rafts / strip foundation, base slab of column and retaining walls; etc. and other structural members other than those mentioned in 5(a) (i) above not requiring form work (i.e. horizontal shuttering) complete in all respects:							
	(2) Type B (nominal mix 1: 1½: 3)	200.200	6	1.00	10401 75	2 476 070 00		
	(a) (i) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or pre-stressed members cast in situ, complete in all respects: RCC Walls (1:11/2:3)	98.753	Cu:m	1.00	10401.75 13818.95	1,364,664.00		
4	Chanter 6 Item 9-c	0.897	cu.m	1.00	9524.50	8,500.00		
	Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):-('c) Deformed bars (Grade-60) Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):('c) Deformed bars (Grade-60)	61,696.32	Kg	100	13,646.0	8,419,080.00		
	Carriage of 100 Cft. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cft. (4.25 cu.m) of timber, by truck or by any other means owned by the contractor.(Lead Up to 400 KM)	467.74	Cu:m	1.0	2090	977,582.00		
6	Chapter 21 Item 13 Providing and fixing 1¼"x1¼"x3/16" (31x31x5 mm) angle iron step, in manhole chambers, including carriage and setting the same in work to correct lines and levels.	24	No	1.0	284.25	6,822.00		
/	Providing embedding 10" (250 mm) wide ¼" (6 mm) thick rubber water stopper in expansion joints of R.C.C. roof slab complete in all respects.	731.46	m	1.0	230.55	168,638.00		
Ö Q	Bitumen coating to plastered or cement concrete surface: ii) 14 lbs. per 100 Sft. (6.35 Kg per Sq.m)	50.90	Sm	1	76.75	3,907.00		
9	Providing and fixing G.I. pipe railing, as per standard drawing.	105.0322	m	1.00	3,031.70	318,426.00		
10	Chapter 3 Item 13.i Rehandling of earthwork: a) Lead up to a single throw of Kassi, phaorah or shovel	28.74	m	1.00	55.30	1,590.00		

2.1.5. Sludge Thickeners							
	MRS, 1st BI-Annual-2019 (1st January-	2019 to 30th Ju	ine-2019)	District	Lahore		
Sr. No.	Description	Quantity		Unit	Rate	Amount(PKR)	
11	Chapter 3 Item 17.a.b.c						
	Iransportation of earth all types when the total distance, including the lead covered in the item of work, is more than 1000 ft. (300 m) a) up to ¼ mile (400 m). b) for every 330 ft. (100 m) additional lead or part thereof, beyond ¼ mile (400 m) up to one mile. (1.6 Km.) c) for every ¼ mile (400 m) additional lead or part thereof, beyond one mile (1.6 Km.) up to 5 miles (8 Km). d) for every ½ mile (800 m) additional lead or part thereof, beyond 5 miles (8 Km).(Lead up to 8 Km)	2290.161	Cum	1.00	250.75	574,258.00	
					Total	16,068,598.00	
				Rupe	es in Million	16.069	

2.1.6. Sludge Drying Beds with Shades							
	MRS, 1st BI-Annual-2019 (1st January-	2019 to 30th Ju	ne-2019)	District	Lahore		
Sr. No.	Description	Quantit	;y	Unit	Rate	Amount(PKR)	
1	Chapter 3 Item 21-b						
	Earthwork excavation in irrigation channels, drains, etc. to designed section, grades and profiles, excavated material disposed-off and dressed within 50 ft. (15 m) lead: i) In ordinary Soil.	3763.601	Cu:m	1.00	233.65	879,365.00	
2	Chapter 6 Item 5-h						
	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate):						
	Apron Ratio 1: 3: 6	341.596	Cu:m	1.00	6967.65	2,380,124.00	
	Apron Ratio 1: 2: 4	27.96	Cu:m	1.00	7,964.85	222,721.00	
3	Chapter 6 Item 6-i-ii						
	Providing and laying reinforced cement concrete (including pre-stressed concrete), using coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete (but excluding the cost of steel reinforcement, its fabrication and placing in position, etc.):-						
	(a)(ii) Reinforced cement concrete in slab of rafts / strip foundation, base slab of column and retaining walls; etc. and other structural members other than those mentioned in 5(a) (i) above not requiring form work (i.e. horizontal shuttering) complete in all respects:						
	(2) Type B (nominal mix 1: 1½: 3)	468 152	Cum	1.00	10401 75	4 869 600 00	
l	NCC Dase Sidu	400.152	Cum	1.00	10401.75	4,009,000.00	

2.1.6. Sludge Drying Beds with Shades								
	MRS, 1st BI-Annual-2019 (1st January-2019 to 30th June-2019) District Lahore							
Sr. No.	Description	Quanti	ty	Unit	Rate	Amount(PKR)		
	(a) (i) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or pre-stressed members cast in situ, complete in all respects:							
	RCC Walls (1:11/2:3)	138.994	Cu:m	1.00	13818.95	1,920,746.00		
4	Chapter 6 Item 9-c							
-	Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):-('c) Deformed bars (Grade-60) Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars): ('c) Deformed bars (Grade-60)	121,429.12	Kg	100	13,646.00	16,570,217.00		
5	Chapter 1 Item 1							
	Carriage of 100 Cft. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cft. (4.25 cu.m) of timber, by truck or by any other means owned by the contractor.(Lead Up to 400 KM)	840.44	Cu:m	1.0	2090.56	1,756,995.00		
6	Chapter 6 Item 28							
	Providing embedding 10" (250 mm) wide ¼" (6 mm) thick rubber water stopper in expansion joints of R.C.C. roof slab complete in all respects.	541.760	m	1.0	230.55	124,903.00		
7	Chapter 3 Item 13.i							
	Rehandling of earthwork: a) Lead up to a single throw of Kassi, phaorah or shovel	948.365	Cu:m	1.0	55.30	52,445.00		
10	Chapter 3 Item 17.a.b.c							
	Transportation of earth all types when the total distance, including the lead covered in the item of work, is more than 1000 ft. (300 m) a) up to ¼ mile (400 m). b) for every 330 ft. (100 m) additional lead or part thereof, beyond ¼ mile (400 m) up to one mile. (1.6 Km.) c) for every ¼ mile (400 m) additional lead or part thereof, beyond one mile (1.6 Km.) up to 5 miles (8 Km). d) for every ½ mile (800 m) additional lead or part thereof, beyond 5 miles (8 Km).(Lead up to 8 Km)	2533.713	Cu:m	1.0	250.75	635,328.00		
11	Shades on Sludge Drying Beds	2008.00	Sq:m	1.0	4,842.00	9,722,736.00		
					Total	39,132,444.00		
				Rupe	es in Million	39.132		

2.1.7.	2.1.7. Rapid Sand Filters (10 No.) 02 Unit = 12 m x 6 m x 4.8 m							
	MRS, 1st BI-Annual-2019 (1st January-	2019 to 30th Ju	ne-2019)	District	Lahore			
Sr. No.	Description	Quantit	ÿ	Unit	Rate	Amount(PKR)		
1	Chapter 3 Item 21-b							
	Earthwork excavation in irrigation channels, drains, etc. to designed section, grades and profiles, excavated material disposed-off and dressed within 50 ft. (15 m) lead: i) In ordinary Soil.	17286.217	Cu:m	1.00	233.65	4,038,925.00		
2	Chapter 6 Item 5-h							
	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate):							
	Apron Ratio 1: 3: 6	1277.418	Cu:m	1.00	6947.65	8,875,053.00		
	Apron Ratio 1: 2: 4	48.540	Cu m	1.00	7964.85	386,614.00		
	Providing and laying reinforced cement concrete (including pre-stressed concrete), using coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete (but excluding the cost of steel reinforcement, its fabrication and placing in position, etc.):- (a)(ii) Reinforced cement concrete in slab of rafts / strip foundation, base slab of column and retaining walls; etc. and other structural members other than those mentioned in 5(a) (i) above not requiring form work (i.e. horizontal shuttering) complete in all respects: (2) Type B (nominal mix 1: 1½: 3) RCC Base Slab (a) (i) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or pre-stressed members cast in situ, complete in all respects:	1774.017	Cum	1.00	10401.75	18,452,881.00		
	RCC Walls (1:1 1/2:3)	1506.724	Cu:m	1.00	13818.95	20,821,344.00		
	Cantilever RCC top Slabs Ratio (1:2:4)	142.740	Cu:m	1.00	9324.50	1,330,979.00		
4	Chapter 6 Item 9-c							
	Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):-('c) Deformed bars (Grade-60) Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):('c) Deformed bars (Grade-60)	670,422.20	Kg	100	13,646.0	91,485,813.00		

2.1.7.	2.1.7. Rapid Sand Filters (10 No.) 02 Unit = 12 m x 6 m x 4. 8 m							
MRS, 1st BI-Annual-2019 (1st January -2019 to 30th June-2019) District Lahore								
Sr. No.	Description	Quant	ity	Unit	Rate	Amount(PKR)		
5	Chapter 1 Item 1							
	Carriage of 100 Cft. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cft. (4.25 cu.m) of timber, by truck or by any other means owned by the contractor.(Lead Up to 400 KM)	4,104.48	Cu:m	1.0	2090.56	8,580,668.00		
6	Chapter 21 Item 13 Providing and fixing 1¼"x1¼"x3/16" (31x31x5 mm) angle iron step, in manhole chambers, including carriage and setting the same in work to correct lines and levels.	1200	No	1.0	284.25	341,100.00		
7	Chapter 6 Item 28 Providing embedding 10" (250 mm) wide ¼" (6 mm) thick rubber water stopper in expansion joints of R.C.C. roof slab complete in all respects.	1574.400	m	1.0	230.55	362,978.00		
8	Chapter 13 Item 9-ii Bitumen coating to plastered or cement concrete surface: ii) 14 lbs. per 100 Sft. (6.35 Kg per Sq.m)	2262.432	Sq:m	1.0	76.75	173,642.00		
9	Chapter 18 Item 13 Providing and fixing G.I. pipe railing, as per standard drawing.	1050.400	m	1.0	3031.70	3,184,498.00		
10	Chapter 3 Item 13.1 Rehandling of earthwork: a) Lead up to a single throw of Kassi, phaorah or shovel	3071.041	Cu:m	1.0	55.30	169,829.00		
	Chapter 3 item 17.a.b.c Transportation of earth all types when the total distance, including the lead covered in the item of work, is more than 1000 ft. (300 m) a) up to ¼ mile (400 m). b) for every 330 ft. (100 m) additional lead or part thereof, beyond ¼ mile (400 m) up to one mile. (1.6 Km.) c) for every ¼ mile (400 m) additional lead or part thereof, beyond one mile (1.6 Km.) up to 5 miles (8 Km). d) for every ½ mile (800 m) additional lead or part thereof, beyond 5 miles (8 Km).(Lead up to 8 Km)	11477.651	Cu:m	1.0	250.75	2,878,021.00		
12	Chapter 19 Item 39.iii							
	Supply and fitting of cast iron manhole cover with frame, etc. complete.	40.00	Cu:m	1.0	1476.45	59,058.00		
	Non-Sci	heduleItems						
L	Filter Media							
13	Providing and Laying in position gravel, size (1/2"- 3/4" gauge) complete in all respect as per drawings and directed by the Engineer's in- charge.	288.00	Cu:m	1.0	5300.00	1,526,400.00		
14	Providing and Laying in position gravel, size (1/4"- 1/2" gauge) complete in all respect as per drawings and directed by the Engineer's in- charge.	288.00	Cu:m	1.0	5300.00	1,526,400.00		
15	Providing and Laying in position gravel, size (1/4"- 10 mesh) complete in all respect as per drawings and directed by the Engineer's in-charge.	288.00	Cu:m	1.0	5300.00	1,526,400.00		

2.1.7.1	2.1.7. Rapid Sand Filters (10 No.) 02 Unit = 12 m x 6 m x 4.8 m							
	MRS, 1st BI-Annual-2019 (1st January-20	019 to 30th Ju	une-2019)	District I	Lahore			
Sr. No.	Description	Description Quantity		Unit	Rate	Amount(PKR)		
16	Providing and Laying in position coarse sand, size (16 mesh to 20 mesh) complete in all respect as per drawings and directed by the Engineer's in- charge.	864.00	Cu:m	1.0	2500.00	2,160,000.00		
17	Providing and Laying in position coarse sand, size (10 mesh to 16 mesh) complete in all respect as per drawings and directed by the Engineer's in- charge.	288.00	Cu:m	1.0	2500.00	720,000.00		
					Total	168,600,603.00		
				Rupe	es in Million	168.601		

2.1.8.	2.1.8. Treated Water Tank and Pump House						
	MRS, 1st BI-Annual-2019 (1st January-2019 to 30th June-2019) District Lahore						
Sr. No.	Description	Quantii	ty	Unit	Rate	Amount(PKR)	
А	Treated Water Tank						
1	Chapter 3 Item 21-b						
	Earthwork excavation in irrigation channels, drains, etc. to designed section, grades and profiles, excavated material disposed-off and dressed within 50 ft. (15 m) lead: i) In ordinary Soil.	20081.318	Cu:m	1.00	233.65	4,692,000.00	
2	Chapter 6 Item 5-h						
	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate):						
	Apron Ratio 1: 3: 6	1265.382	Cu:m	1.00	6967.65	8,816,739.00	
	Apron Ratio 1: 2: 4	36.63	Cu:m	1.00	7,964.85	291,752.00	
3	Chapter 6 Item 6-i-ii		-	1			
	Providing and laying reinforced cement concrete (including pre-stressed concrete), using coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete (but excluding the cost of steel reinforcement, its fabrication and placing in position, etc.):-						
	(a)(ii) Reinforced cement concrete in slab of rafts / strip foundation, base slab of column and retaining walls; etc. and other structural members other than those mentioned in 5(a) (i) above not requiring form work (i.e. horizontal shuttering) complete in all respects:						
	(2) Type B (nominal mix 1: 1½: 3)						
	RCC Base Slab	964.752	Cu m	1.00	10401.75	10,035,109.00	
	(a) (i) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other						

2.1.8.	2.1.8. Treated Water Tank and Pump House					
	MRS, 1st BI-Annual-2019 (1st January-	2019 to 30th Ju	ne- 20 19)	District	Lahore	
Sr. No.	Description	Quantit	:y	Unit	Rate	Amount(PKR)
	structural members laid in situ or precast laid in position, or pre-stressed members cast in situ, complete in all respects:			4.00	40040.05	
	RCC Walls (1:11/2:3)	1047.660	Cu:m	1.00	13818.95	14,477,561.00
	Cantilever RCC top Slabs Ratio (1:2:4)	554.771	Cu:m	1.00	9324.50	5,172,958.00
4	Chapter 6 Item 9-c					
	Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):-('c) Deformed bars (Grade-60) Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):('c) Deformed bars (Grade-60)	402,482.40	Kg	100	13,646.00	54,922,748.00
5	Chapter 1 Item 1					
	Carriage of 100 Cft. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cft. (4.25 cu.m) of timber, by truck or by any other means owned by the contractor.(Lead Up to 400 KM)	3,369.54	Cu:m	1.0	2090.56	7,044,221.00
6	Chapter 21 Item 13					
	Providing and fixing 1¼"x1¼"x3/16" (31x31x5 mm) angle iron step, in manhole chambers, including carriage and setting the same in work to correct lines and levels.	266	No	1.0	284.25	75,611.00
7	Chapter 6 Item 28					
	Providing embedding 10" (250 mm) wide ¼" (6 mm) thick rubber water stopper in expansion joints of R.C.C. roof slab complete in all respects.	1460.000	m	1.0	230.55	336,603.00
8	Chapter 18 Item 13					
	Providing and fixing G.I. pipe railing, as per standard drawing.	175.800	m	1.0	3031.70	532,973.00
9	Chapter 3 Item 13.i					
	Rehandling of earthwork: a) Lead up to a single	1266.923	Cu:m	1.0	55.30	70,061.00
10	throw of Kassi, phaoran of shovel					
	Chapter 3 item 17.a.b.c Transportation of earth all types when the total distance, including the lead covered in the item of work, is more than 1000 ft. (300 m) a) up to ¼ mile (400 m). b) for every 330 ft. (100 m) additional lead or part thereof, beyond ¼ mile (400 m) up to one mile. (1.6 Km.) c) for every ¼ mile (400 m) additional lead or part thereof, beyond one mile (1.6 Km.) up to 5 miles (8 Km). d) for every ½ mile (800 m) additional lead or part thereof, beyond 5 miles (8 Km).(Lead up to 8 Km)	16932.956	Cu:m	1.0	250.75	4,245,939.00
			1		Sub-Total(A)	110,714,275.00
В	Raw Water Pump House					

2.1.8. Treated Water Tank and Pump House						
	MRS, 1st BI-Annual-2019 (1st January-	2019 to 30th Ju	ne-2019)	District	Lahore	
Sr. No.	Description	Quantit	ţy	Unit	Rate	Amount(PKR)
1	Chapter-7,Item 5-i					
	Pacca brick work in ground floor:	114 220	Curr	1.00	7921 20	804 202 00
	i) cement, sand mortar:	114.329	Cu:m	1.00	/821.30	894,203.00
2	Chapter-6,Item6-a-iii					
	Providing and laying reinforced cement concrete (including pre-stressed concrete), using coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete (but excluding the cost of steel reinforcement, its fabrication and placing in position, etc.): a). Reinforced cement concrete in roof slab, beams, columns, lintels, girders and other structural members laid in situ or pre-cast laid in position, or pre-stressed members cast in situ, complete in all respect, Type C (nominal mix 1:2:4)	64.455	Cu:m	1.00	6967.65	449,100.00
3	Ch-6,Item-9(b)					
	Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- ('c) Deformed bars (Grade40)	6,445.50	Kg	100	13,646.00	879,553.00
4	Chapter-1,Item-1					
	Carriage of 100 Cft. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cft. (4.25 cu.m) of timber, by truck or by any other means owned by the contractor.(Lead Up to 400 KM)	56.72	Cu:m	1.0	2090.56	118,577.00
5	Ch-11,Item-10(b)					
	Cement plaster 3/8" (10 mm) thick under soffit of R.C.C. roof slabs only, up to 20' height. b) 1:3	294.920	Sq.m	1.00	228.10	67,271.00
6	Ch-11,Item-9(b)					
	Cement plaster 1/2" thick in 1:4 up to 20 ft height	370.110	Sq.m	1.00	201.30	74,503.00
7	Ch-11,Item-25(a-iii)					
	White washing 3 coats on new surface.	665.030	Sq.m	1.00	30.75	20,450.00
8	Ch-11,Item-18(a)					
	Cement pointing 1:2 struck joints, on wall up to 20' height, i/c extra cost of labour and material for red oxide pigment in cement pointing to match with the colour of bricks (i) Ratio 1:5	352.965	Sq.m	1.00	216.70	76,488.00
9	Ch-6,Item-3(b)					

2.1.8.	2.1.8. Treated Water Tank and Pump House					
	MRS, 1st BI-Annual-2019 (1st January-	2019 to 30th Ju	ne-2019)	District	Lahore	
Sr. No.	Description	Quantit	:y	Unit	Rate	Amount(PKR)
	Cement concrete brick or stone ballast 1½ " to 2" (40 mm to 50 mm) gauge, in foundation and plinth: (b) Ratio 1: 4: 8	31.75	Cu:m	1.00	4738.15	150,446.00
10	Ch-10, Item-15(i) Providing and laying topping of cement concrete 1:2:4, including surface finishing and dividing in panels:-3"Thick	211.68	Sq.m	1.00	715.25	151,404.00
11	Ch-10,Item-42 Providing and fixing marble strip of any shade for dividing the mosaic flooring into panels a) Size 1½" x 3/8" (40 x 10 mm)	127.01	m	1.00	21.65	2,750.00
12	Ch-9,Item-5 Single layer of tiles 9"x4½"x1½" (225x113x40 mm) laid over 4"(100 mm) earth and 1" (25 mm) mud plaster without Bhoosa, grouted with cement sand 1:3 on top of RCC roof slab, provided with 34 lbs. per %Sft. or 1.72 Kg/Sq.m bitumen coating sandblinded.	231.78	Sq.m	1.00	732.85	169,859.00
13	Ch-9,Item-14 Khassi pernalas in cement sand mortar 1:2, 12" outside width finished smooth with a floating coat of neat cement	27.0	m	1.00	338.50	9,140.00
14	Ch-9,Item-15 Khurra on roof 2' x 2' x 6" (600 x 600 x 150 mm)	6.000	No	1.00	499.65	2,998.00
15	Ch-9,Item-16					
	BottomKhurasofbrickmasonryincementmortar 1:6, 4'x2'x4½" (1200x600x113 mm) over 3" (75 mm) cement concrete 1:4:8.	6.000	No	1.00	887.25	5,324.00
16	Ch-25,Item-41(b-v) Providing and fixing steel windows with openable glazed panels, using beam section for frame 1½"x1"x5/8"x1/8" (40x25x16x3 mm), Z-section for leaves ¾"x1"x¾"x1/8" (20x25x20x3 mm), T- section sashes 1"x1"x1/8" (25x25x3 mm), glass panes, wooden screed for glazing embedded over a thin layer of putty duly screwed with leaves, brass fittings, holdfast, duly painted, complete in all respects, including all cost of material and labour, etc. as per approved design and as directed by the Engineer-in-charge:- b) fixed with wire gauze, 22 SWG v) glass pane 5 mmthick	28.800	Sq.m	1.00	5070.80	146,039.00
17	Ch-25,Item-31 Making and fixing steel grated door with 1/16" thick (1.5mm) sheeting, including angle iron frame 2"x2"x3/8" (50x50x10 mm) and ¾" (20 mm) square bars 4" (100 mm) centre to centre, with lockingarrangement.	28.80	Sq.m	1.00	2360.75	67,990.00

2.1.8. Treated Water Tank and Pump House						
	MRS, 1st BI-Annual-2019 (1st January-	2019 to 30th Ju	ne-2019)	District	Lahore	
Sr. No.	Description	Quanti	ty	Unit	Rate	Amount(PKR)
18	Ch-12,Item-31					
	Providing and fixing M.S. flat ½"x1/8" (13mm x 3mm) grill including ¾" x 1/8" (20 mmx3 mm) M.S. flat frame, in windows of approved design, including painting three coats, complete in all respects.	9.68	Sq.m	1.00	11121.40	107,600.00
19	Ch-13, Item-5(c-i & ii)					
	Painting new surface: c) Preparing surface and painting of doors and windows any type (includingedges):					
	i) priming coat.	19.35	Sq.m	1.00	82.45	1,595.00
	ii) each subsequent coat of paint. (Two Coats)	38.700	Sq.m	1.00	44.30	1714.000
				1	Sub-Total(B)	3,397,004.00
C	ChlorineRoom					
1	Chapter-7,Item 5-i Pacca brick work in ground floor: i) cement, sand mortar:	25.776	Cu:m	1.00	7821.30	201,600.00
2	Chapter-6,Item6-a-iii					
2	Providing and laying reinforced cement concrete (including pre-stressed concrete), using coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete (but excluding the cost of steel reinforcement, its fabrication and placing in position, etc.): a). Reinforced cement concrete in roof slab, beams, columns, lintels, girders and other structural members laid in situ or pre-cast laid in position, or pre-stressed members cast in situ, complete in all respect, Type C (nominal mix 1:2:4)	53.797	Cu:m	1.00	6967.65	374,839.00
3	Ch-6,Item-9(b)					
	Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- ('c) Deformed bars (Grade40)	5,379.70	Kg	100	13,646.00	734,114.00
4	Carriage of 100 Cft (2.82 cum) of all materials like					
	stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cft. (4.25 cu.m) of timber, by truck or by any other means owned by the contractor.(Lead Up to 400 KM)	93.91	Cu:m	1.0	2090.56	196,326.00
5	Ch-11,Item-10(b)					

2.1.8.	2.1.8. Treated Water Tank and Pump House					
	MRS, 1st BI-Annual-2019 (1st January-	2019 to 30th Ju	ne- <u>20</u> 19)	District	Lahore	
Sr. No.	Description	Quanti	ty	Unit	Rate	Amount(PKR)
	Cement plaster 3/8" (10 mm) thick under soffit of R.C.C. roof slabs only, up to 20' height. b) 1:3	30.25	Sq.m	1.00	228.10	6,900.00
6	Ch-11,Item-9(b)					
	Cement plaster 1/2" thick in 1:4 up to 20 ft height	120.450	Sq.m	1.00	201.30	24,247.00
7	Ch-11,Item-25(a-iii)					
	White washing 3 coats on new surface.	150.700	Sq.m	1.00	30.75	4,634.00
8	Ch-11,Item-18(a)					
	Cement pointing 1:2 struck joints, on wall up to 20' height, i/c extra cost of labour and material for red oxide pigment in cement pointing to match with the colour of bricks (i) Ratio 1:5	140.855	Sq.m	1.00	216.70	30,523.00
9	Ch-6,Item-3(b)					
	Cement concrete brick or stone ballast $1\frac{1}{2}$ " to 2" (40 mm to 50 mm) gauge, in foundation and plinth: (b) Ratio 1: 4: 8	4.54	Cu:m	1.00	4738.15	21,499.00
10	Ch-10,Item-15(i)					
	Providing and laying topping of cement concrete 1:2:4, including surface finishing and dividing in panels:-3"Thick	30.25	Sq.m	1.00	715.25	21,636.00
11	Ch-10,Item-42					
	Providing and fixing marble strip of any shade for dividing the mosaic flooring into panels a) Size $1\frac{1}{2}$ " x $3/8$ " (40 x 10 mm)	18.15	m	1.00	21.65	393.00
12	Ch-9,Item-5					
	Single layer of tiles 9"x4½"x1½" (225x113x40 mm) laid over 4"(100 mm) earth and 1" (25 mm) mud plaster without Bhoosa, grouted with cement sand 1:3 on top of RCC roof slab, provided with 34 lbs. per %Sft. or 1.72 Kg/Sq.m bitumen coating sandblinded.	229.31	Sq.m	1.00	732.85	168,053.00
13	Ch-9,Item-14					
	Khassi pernalas in cement sand mortar 1:2, 12" outside width finished smooth with a floating coat of neat cement	4.5	m	1.00	338.50	1,523.00
14	Ch-9,Item-15					
	Khurra on roof 2' x 2' x 6" (600 x 600 x 150 mm)	1	No	1.00	499.65	500.00
15	Ch-9,Item-16					
	BottomKhurasofbrickmasonryincementmortar 1:6, 4'x2'x4½" (1200x600x113 mm) over 3" (75 mm) cement concrete 1:4:8.	1.000	No	1.00	887.25	887.00
16	Ch-25,Item-41(b-v)					
	Providing and fixing steel windows with openable glazed panels, using beam section for frame 1½"x1"x5/8"x1/8" (40x25x16x3 mm), Z-section for leaves ¾"x1"x¾"x1/8" (20x25x20x3 mm), T-section sashes 1"x1"x1/8" (25x25x3 mm), glass panes, wooden screed for glazing embedded over	3.60	Sq.m	1.00	5070.80	18,255.00

2.1.8.	2.1.8. Treated Water Tank and Pump House					
	MRS, 1st BI-Annual-2019 (1st January-	2019 to 30th Ju	ne-2019)	District	Lahore	
Sr. No.	Description	Quanti	ty	Unit	Rate	Amount(PKR)
	a thin layer of putty duly screwed with leaves, brass fittings, holdfast, duly painted, complete in all respects, including all cost of material and labour, etc. as per approved design and as directed by the Engineer-in-charge:- b) fixed with wire gauze, 22 SWG v) glass pane 5 mmthick					
17	Ch-25,Item-31					
	Making and fixing steel grated door with 1/16" thick (1.5mm) sheeting, including angle iron frame 2"x2"x3/8" (50x50x10 mm) and ¾" (20 mm) square bars 4" (100 mm) centre to centre, with lockingarrangement.	14.03	Sq.m	1.00	11121.40	155,978.00
18	Ch-13, Item-5(c-i & ii)					
	Painting new surface: c) Preparing surface and painting of doors and windows any type (includingedges):					
	i) priming coat.	19.35	Sq.m	1.00	82.45	1,595.00
	ii) each subsequent coat of paint. (Two Coats)	38.700	Sq.m	1.00	44.30	1714.000
					Sub-Total(C)	6,224,772.00
				Т	otal(A+B+C)	116,076,495.00
					No. of Units	03
				Tota	l Cost in PKR	348,229,485.00
				Rupe	es in Million	348.229

2.2.1 Supplying and Installation of Mechanical Equipment

Sr.No.	Description	Quoted Price in Euro (€)	Cost in PKR
1	Intake Structure & Screen Chamber	L.S	30,000,000
2	Coagulation/Flocculation and Clarifier Tanks to include the following:- HDPE and Stainless Steel piping of various sizes from 25mm to 150mm, for chemical flocculants and polymers, Laminar Filters and support system, stainless steel vacuum pipework for sludge removal, mixing blades, HDPE perforated pipes in Laminar tanks, sludge control valves, compressed air system and compressor, penstocks, aluminum handrails, traps and grills, installation works, testing and commissioning, safety, shipping of any imported goods to site and all import taxes and fees	2,400,000	406,872,000
3	Rapid Gravity Filtration Units to include the following:- Quartz sand 1mm particle size with min 65% silicon content, and gravel filter material 5mm particle size, air diffuser units, Air Blower system and all Stainless Steel piping for filter backwash, Motive Water Pumps and System and pipework/fittings, back wash pumps and pipework/fittings for filter backwash, Stainless Steel syphon units and gauges, penstocks, aluminum handrails, traps and grills, overhead	4,600,000	779,838,000

	cranes, installation works, testing and commissioning, safety, shipping of any imported goods to site and all import taxes and fees		
4	Wash Water and Sludge Treatment to include the following:- Water recovery pumps and pipework, level switches, Sludge pumps and pipework, Penstocks, agitators, pumps and pipework lower to upper tanks, guide rails, chains, HDPE pipework for polymer, perforated HDPE pipes, sludge valves operated by compressed air, compressed air piping, non-corrosive walkways, penstocks, perforated HDPE pipe for sludge beds, aluminum stop logs for sludge beds, aluminum handrails, traps and grills, installation works, testing and commissioning, safety, shipping of any imported goods to site and all import taxes and fees	2,400,000	406,872,000
5	Chemical Buildings to include the following:- Lime and Aluminum Sulphate mixers, polymer mixing tank system and special pumps, and interconnecting pipework in HDPE/Stainless Steel including fittings, Lime Special Pumps and controls, Aluminum Sulphate Pumps and controls, Chlorine handing and mixing system including special pumps and controls, Chlorine safety system including vacuum suction system and neutralization tower including sensors, valves, piping, fittings, aluminum handrails, traps and grills, installation works, testing and commissioning, safety, shipping of any imported goods to site and all import taxes and fees	1,500,000	254,295,000
6	Treated Water Tank to include the following:- inlet pipe Stainless Steel, overflow Pipe Stainless steel, outlet pipe stainless steel, aluminum handrails, traps and grills, installation works, testing and commissioning, safety, shipping of any imported goods to site and all import taxes and fees	310,000	52,554,300
7	Exploitation, administrative and electrical buildings to include the following:- Fully equipment public health laboratory all office furniture, with facility for real time monitoring of incoming and outgoing water quality, diesel tank for Generator, installation works, testing and commissioning, safety, shipping of any imported goods to site and all import taxes and fees	425,000	72,050,250
8	Pumping Machinery (as per Quotation attached)		
i	Providing, Installing, testing commissioning Centrifugal pump for Raw water having Discharge of 2,040 m ³ /h against 5 m dynamic head coupled with 60.00 BHP (45 KW) 1450 RPM. Rate includes providing, installing, MCU (Motor Control Unit), Base frame, Coupling, Coupling Guard (4 working & 3 standby).		33,591,805
ii	Providing, Installing, testing commissioning Vertical turbine pump for clear water having Discharge of 2,550 m ³ /h against 60 m dynamic head with required column pipe & bowl assembly, coupled with 560 KW 993 RPM vertical A.C electric motor. Rate further includes providing, installing VFD, MCU (Motor Control Unit), Base frame, Coupling, Coupling Guard, DN400 Butterfly Valve, pump manufacturer makes, erecting clamp		374,507,320

	motor stool with all accessories complete in all respect. (7 working & 2 standby)		
9	Spare Parts, set of critical spares for 1 year for all equipment including bearings, seals, filters, lubricants installation works, 5% pipe and fittings, testing and commissioning, safety, shipping of any imported goods to site and all import taxes and fees	500,000	84,765,000
10	Yard Piping to include the following:- All interconnecting pipes and fittings, penstocks, valves, manholes, service trenches, for raw water, clear water, sludge, waste water, lime milk, Aluminum sulphate solution, Chlorine solution, polymer to coagulation and recovering tanks, compressed air lines, pipes from 1400mm to 25mm in stainless steel, HDPE, DI, concrete as per design requirements, Collection Pit and pumps for overflow water return to canal, aluminum access ladders, grills, covers, installation works, testing and commissioning, safety, shipping of any imported goods to site and all import taxes and fees	1,600,000	271,248,000
11	Supply of Diesel Generator Set of 1600 EKW / 2000 KVA Prime Power, 1500 RPM, 400 Volts, 3 Phase, 50 Hertz at 0.8 power factor - 03 No. @ USD 390,000/-	-	175,500,000
	Total Mechanical Works		2,942,093,675
Note			
	1 Euro = 169.53 PKR		

2.2.2 Supplying and Installation Of Electrical Equipment

Sr. No.	Description	Quoted Price in Euro (€)	Cost in PKR
1	Coagulation/Flocculation and Clarifier Tanks to include the following:- Local Distribution Panels and sub panels, all switches, control units, cables, cabling to other buildings and Main Switch Panels, conduits, cable trays, installation works, testing and commissioning, safety, shipping of any imported goods to site and all import taxes and fees	1,000,000	169,530,000
2	Rapid Gravity Filtration Units to include the following:- Local Distribution Panels and sub panels, all switches, control units, cables, cabling to other buildings and Main Switch Panels, conduits, cable trays, installation works, testing and commissioning, safety, shipping of any imported goods to site and all import taxes and fees	1,700,000	288,201,000
3	Wash Water and Sludge Treatment to include the following:- Local Distribution Panels and sub panels, all switches, control units, cables, cabling to other buildings and Main Switch Panels, conduits, cable trays, installation works, testing and commissioning, safety, shipping of any imported goods to site and all import taxes and fees	1,550,000	262,771,500
4	Chemical Buildings to include the following:- Local Distribution Panels and sub panels, all switches, control units, cables, cabling to other buildings and Main Switch Panels, conduits, cable trays, installation works, testing and commissioning, safety, shipping of any imported goods to site and all import taxes and fees	1,350,000	228,865,500

5	Exploitation, administrative and electrical buildings to include the following: Local Distribution Panels and sub panels, all switches, control units, cables, cabling to other buildings and Main Switch Panels, Backup Generator with auto start/stop, conduits, cable trays, installation works, testing and commissioning, safety, shipping of any imported goods to site and all import taxes and fees	5,000,000	847,650,000
6	Clear Water Pumping Station to include the following:- Local Distribution Panels and sub panels, all switches, control units, cables, cabling to other buildings and Main Switch Panels, conduits, cable trays, installation works, testing and commissioning, safety, shipping of any imported goods to site and all import taxes and fees	800,000	135,624,000
7	Spare Parts to include the following:- Breakers all sizes, 03% lengths of cables, conduits and cable trays, installation works, testing and commissioning, safety, shipping of any imported goods to site and all import taxes and fees	390,000	66,116,700
9	Yard Piping to include the following:- Collection Pit and pumps for overflow water return to canal wiring, installation works, testing and commissioning, safety, shipping of any imported goods to site and all import taxes and fees	260,000	44,077,800
	Total Electrical Works		2,042,836,500

2.2.3 Supplying and Installation of SCADA

Sr. No.	Description	Quoted Price in	Cost in PKR
1	SCADA system Server, 60" display screen, SCADA software, design and build system, pressure sensors, electromagnetic flow meters on raw water, electromagnetic flow meters for backwash filter water, electromagnetic flow meters potable water outlet, electromagnetic flow meters for recovered water from sludge, electric or air controls on inlet and outlet valves to filter tank for backwash, air wash, sludge removal, aluminum sulphate, chlorine, lime milk and polymer, start controls for all pumps (Raw Water, Clear Potable Water, Motive Water, Backwash water, sludge, agitators, Recovery Tank pumps) through level control switches both immersed and beam type, all cat 6E interconnecting cabling, all relays, switches in main switch panel and sub-panels, uninterrupted power supplies on all panels, solenoids on all valves in WTP, installation works, testing and commissioning, safety, shipping of any imported goods to site and all import taxes and fees	1,350,000	228,865,500
	Total SCADA Works	1,350,000	228,865,500

3.1	Transmission Main including Valves, Fitting	gs etc. (H	DPE Pipe - Lengt	h 3.5 km)		
Sr.No.	Description	Unit	Qty	Unit Rate Rs	Amount. Rs.	
	N.S. Rate					
1	Providing and laying of Transmission Mains including laying, jointing, fittings/specials such as bends, tees, crosses whatever required at site drain crossing, drain crossing, testing shipment charges, duties, taxes, transportation to stores, transportation stores to site complete in all respects. Including provision for Specials i.e. bends, sluice valves, gate valves etc. Rate also includes the cost of excavation back filling, dismantling, restoration of roads, streets. Complete in all respect.					
	Transmission Main Including Valves, Fittings etc.;(HDPE Pipe PN-10/SDR-17 / equivalent pipe-Length 3.5 K.M)as per EPC mode design.					
	a) 1500 mm i/d (Quotation attached)	m	3,500.00	183,500.00	642,250,000	
		642,250,000				
				Rs. in Million	642.25	

4.1	Feeding Main including Valves, Fittings etc. (HDPE Pipe)					
Sr. No.	Description	Unit	Qty	Unit Rate Rs/Meter	Amount. Rs.	
	N.S. Rate					
1	Providing and laying of Feeding Mains including laying, jointing, fittings/specials such as bends, tees, crosses whatever required at site drain crossing, testing shipment charges, duties, taxes, transportation to stores, transportation stores to site complete in all respects. Including provision for Specials i.e. bends, sluice valves, gate valves etc. Rate also includes the cost of excavation back filling, dismantling, restoration of roads, streets. Complete in all respect.					
	Feeding Main Including Valves, Fittings etc.;(HDPE Pipe PN- 10/SDR-17/ equivalent pipe-Length 3.5 K.M)as per EPC mode design.					
	a)1500 mm i/d (Quotation attached)	m	191	183,500.00	35,048,500.00	
	b)1400 mm i/d.(Quotation attached)	m	3,681	143,000.00	526,383,000.00	
	c)900 mm i/d .(Analysis attached)	m	6,296	94,645.68	595,889,227.00	
	d)800 mm i/d.(Analysis attached)	m	5,517	77,716.48	428,761,828.00	
	e)630 mm i/d.(Analysis attached)	m	7,017	51,447.44	361,006,688.83	
	f)450 mm i/d.(Analysis attached)	m	32,325	23,603.96	762,997,863.00	
	Total Rs.	m	55,027	Total Rs.	2,710,087,106.83	
	g) Booster Pumps	No	150	150,000.00	22,500,000.00	
	G Total Rs.			Total Rs.	2,732,587,106.83	
			Rs. in N	Aillion.	2,732.59	

5.1	Distribution Network including Valves, Fittings etc.																
Sr. No	Description														Qty	Unit Rate Rs	Amount. Rs.
	N.S. Rat	e															
1	Providir fittings/ testings storesto sluice va dismant	ng laying, jointing ver required at site ion to stores, trans vision for Specials cost of excavation in all respect.															
	Distribution System Including Valves, Fittings etc.;(HDPE Pipe PN-10/SDR-17 / equivalent pipe-as per EPC mode design)																
	a)800 m	m i/d.(Analysisatt	ached)											m	826	77,716.48	64,193,813.65
	b)630m	m i/d.(Analysis att	ached)				1	1						m	790	51,447.44	40,643,477.86
		MRS. Ch:04 lt:45	5														
2		Dismantlingand	removing	road meta	anng.		I				T	<u> </u>	1				
	a 18''i/d 450 mm =				2,256.00	x 1.10	х	0.25	х	90%	=	Cu:m	558.36		-		
	b	12''i/d	315	mm	=	9,344.00	x	0.90	x	0.25	x	90%	=	Cu:m	1,892.16		-
	c 10"i/d 250 mm =			=	5,032.00	x 0.90 x		x	0.25	x	90%	=	Cu:m	1,018.98		-	
	d 8"i/d 200 mm = 5,922.00 e 6"i/d 160 mm = 4,349.00							0.80	x	0.25	x	80%	=	Cu:m	947.52		-
								0.70	x	0.25	x	80%	=	Cu:m	608.86		-
	f	4" i/d	110	mm	=	41,807.00	x	0.60	x	0.25	x	30%	=	Cu:m	1,881.32		-
	g	3"i/d	90	mm	=	11,417.00	x	0.60	x	0.25	x	30%	=	Cu:m	513.77		-
									Tota	I			=	Cu:m	7,420.96	442.35	3,282,662.00

а

b

С

d

е

f

g

а

b

с

d

12''i/d

10"i/d

8" i/d

315

250

200

mm

mm

mm

=

=

=

9,344.00

5,032.00

5,922.00

4

5

3

MRS.Ch:04 lt:19)-d														
Dismantling cement concrete with brick aggregate.															
18''i/d	450	mm	=	2,256.00	x	1.10	x	0.15	x	10%	=	Cu:m	37.22		-
12''i/d	315	mm	=	9,344.00	x	0.90	x	0.15	x	10%	=	Cu:m	126.14		-
10"i/d	250	mm	=	5,032.00	x	0.90	x	0.15	x	10%	=	Cu:m	67.93		-
8" i/d	200	mm	=	5,922.00	x	0.80	x	0.15	х	20%	=	Cu:m	142.13		-
 6" i/d	160	mm	=	4,349.00	x	0.70	x	0.15	x	20%	=	Cu:m	91.33		-
4" i/d	110	mm	=	41,807.00	x	0.60	x	0.15	х	70%	=	Cu:m	2,633.84		-
3"i/d	90	mm	=	11,417.00	x	0.60	x	0.15	х	70%	=	Cu:m	719.27		-
							Tota	I			=	Cu:m	3,817.87	663.50	2,533,156.00
MRS Ch:04 lt:19	-с														
Dismantlingcem	entconci	rete 1:2:4	olain.		-	-					_				
Quantity same as	=	3					=	Cu:m	3,817.87	2,432.95	9,288,684.00				
MRS Ch:04 lt:19	-с														
Excavation of tre depth from grou cutting pits for jo	Excavation of trenches in all kinds of soil, except cutting rock, for water supply pipelines up to 5 ft. (1.5 m) depth from ground level, including trimming, dressing sides, leveling the beds of trenches to correct grade and cutting pits for joints, etc. complete in all respects.														
18''i/d	450	mm	=	2,256.00	x	1.10	x	1.50			=	Cu:m	3,722.40		-

х

х

1.40

1.30

1.30

= Cu:m 11,773.44

=

=

Cu:m 5,887.44

Cu:m 6,158.88

0.90

0.90

0.80

х

х

х

_

-

-

	е	6" i/d	160	mm	=	4,349.00	x	0.70		1.20			=	Cu:m	3,653.16		-
	f	4" i/d	110	mm	=	41,807.00	x	0.60		1.20			=	Cu:m	30,101.04		-
	g	3"i/d	90	mm	=	11,417.00	x	0.60		1.20			=	Cu:m	8,220.24		-
									Tota	I			=	Cu:m	69,516.60	166.35	11,564,086.00
		N.S. Rate															
6		Providing and laying of Distribution Network (HDPE pipe - Class PN-10/SDR-17 - PE-100 (BLACK) FOR WATER ISO4427/DIN 8074/8075) including laying, jointing, fitting, drain crossing, testing, shipment charges, duties, taxes, transportation to stores, transportation stores to site complete in all respects. (Analysis attached)															
	а	18''i/d	450	mm	=									m	2,256.00	17,679	39,884,288.00
7		MRS Ch:23 It:42-b															
		Providing, laying, cutting, jointing, testing and disinfecting High Density Polyethylene Pipe (HDPE-100) working pressure pipe in trenches. complete in all respects:-															
		PN-10(SDR-17)															
	b	12"i/d 315 mm =												m	9,344.00	6,146.60	57,433,830.00
	С	10"i/d	250	mm	=									m	5,032.00	3,846.30	19,354,582.00
	d	8" i/d	200	mm	=									m	5,922.00	2,443.50	14,470,407.00
	е	6" i/d	160	mm	=									m	4,349.00	1,568.10	6,819,667.00
	f	4" i/d	110	mm	=									m	41,807.00	761.30	31,827,669.00
	g	3"i/d	90	mm	=									m	11,417.00	508.75	5,808,399.00
		N.S. Rate															
8		Provision made for HDPE specials such as tees, bends, reducers, crosses, C.I valves and all others required at site .															
		Take 20% of Item	No .				=	6	+	7			=	%	135,714,554	20%	27,142,910.80
---	-----------------------------	--------------------	----------	------------	---------	-------------------	---	------	------	------	---	-------	---	------	-------------	-----	---------------
	MRS Ch:21 It:12- a	MRS Ch:07 lt:30															
9		Supplying and fill	ing sand	under floo	r; or p	lugging in wells.											
	а	18''i/d	450	mm	=	2,256.00	х	1.10	x	0.75			=	Cu:m	1,873.02		-
	b	12''i/d	315	mm	=	9,344.00	x	0.90	x	0.62			=	Cu:m	5,212.02		-
	С	10"i/d	250	mm	=	5,032.00	x	0.90	x	0.55			=	Cu:m	2,512.46		-
	d	8" i/d	200	mm	=	5,922.00	x	0.80	x	0.50			=	Cu:m	2,391.42		-
	е	6" i/d	160	mm	=	4,349.00	x	0.80	x	0.46			=	Cu:m	1,617.05		-
	f	4" i/d	110	mm	=	41,807.00	x	0.70	x	0.41			=	Cu:m	12,138.49		-
	g	3"i/d	90	mm	=	11,417.00	x	0.70	x	0.39			=	Cu:m	3,155.05		-
									Tota	I			=	Cu:m	28,899.50		
		Deduct volume o	fpipe	1													
	а	18''i/d	450	mm	=	2,256.00	x	0.45	x	0.45	x	0.785	=	Cu:m	358.58		-
	b	12''i/d	315	mm	=	9,344.00	х	0.31	x	0.31	х	1.785	=	Cu:m	1,654.82		-
	С	10"i/d	250	mm	=	5,032.00	x	0.25	x	0.25	x	2.785	=	Cu:m	875.80		-
	d	8" i/d	200	mm	=	5,922.00	x	0.20	x	0.20	x	3.785	=	Cu:m	896.50		-
	е	6" i/d	160	mm	=	4,349.00	x	0.16	x	0.16	x	4.785	=	Cu:m	532.68		-
	f	4" i/d	110	mm	=	41,807.00	x	0.11	x	0.11	x	5.785	=	Cu:m	2,926.14		-

	g	3"i/d	90	mm	=	11,417.00	x	0.09	x	0.09	x	6.785	=	Cu:m	627.40		-
									Tota				=	Cu:m	7,871.93		
		Net Qty of sand			=	28,899.50	-	-	7871.9	93			=	Cu:m	21,027.58	643.15	13,523,888.00
10		MRSCh:03It:13-	-b	h) n to o	lood	f = 0 f f (1 f m)											
10		Renariung of ea	rtnwork:	0) UP to a	lead	51 50 IL. (15 III).			Г								
		Take 80% of Item	No.				=	5	=		55,61	13.28	=	Cu:m	55,613.28	77.40	4,304,467.87
		MRS Ch:03 It:24	- c	/ C: II					L,								
11		Compaction of ea	arthwork	(soft, ordi	nary c	or hard soil) :-c)Rar	nmin	gearthwo	ork (all	types of so	oil).						
		Quantity same as	s per item	No.			=	10					=	Cu:m	55,613.28	33.20	1,846,361.00
	MRS Ch:21 It:12- a	MRS Ch:21 lt:12	-a														
12		Restoration of me carpet and 10" (2 mm) depth of sto	etaled ro 50 ne metal	ad, on laid for sub-ba	servio ase an	ce line, including c d base.	ompa	ction:-a)	Carpet	ed road, w	ith 2'	' (50 mm)				
	а	18''i/d	450	mm	=	2,256.00	x	1.0	x	90%			=	Sq:m	2,030.40		-
	b	12''i/d	315	mm	=	9,344.00	x	0.90	x	90%			=	Sq:m	7,568.64		-
	с	10"i/d	250	mm	=	5,887.44	x	0.80	x	90%			=	Sq:m	4,238.96		-
	d	8" i/d	200	mm	=	6,158.88	x	0.8	x	80%			=	Sq:m	3,695.33		-
	е	6" i/d	160	mm	=	4,349.00	x	0.8	x	80%			=	Sq:m	2,609.40		-
	f	4" i/d	110	mm	=	41,807.00	x	0.60	x	30%			=	Sq:m	7,525.26		-
	g	3"i/d	90	mm	=	11,417.00	x	0.60	x	30%			=	Sq:m	2,055.06		-

									Tota				=	Sq:m	29,723.04	976.50	29,024,553.00
		MRS Ch:06 lt:3-0	ł														
13		Cement concrete 6: 12	e brick or	stone ball	ast 1½	ź " to 2" (40 mm to	o 50 m) gauge, i	in four	idation and	plin	th:- (a) R	atio	1:			
		Quantity same as	s per iten	۱No.			=	3					=	Cu:m	3,817.87	4,020.15	15,348,406.00
		MRS Ch:06 lt:5-f	•														
14		Cement concrete washing of stone	e plain inc aggregat	cluding pla e):1:2:4	cing, c	compacting, finish	ningar	dcuring	comple	ete (includir	ng sc	reeninga	ind				
		Quantity same as	s per iten	۱No.			=	4					=	Cu:m	3,817.87	7,964.85	30,408,754.00
		MRS Ch:06 lt:6-a	a-ii														
15		Providing and lay screened graded lifting, compactir reinforcement, it strip foundation, mentioned in 5(a Type C (nominal i	ring reinfo and wash ng, curing ts fabricat base slab t) (i) abov mix 1: 2: 4	orced ceme ned aggreg g, renderin tion and pl o of columr e not requ 4)	ent co gate, ir g and acing n and r iring f	ncrete (including n required shape a finishing exposed in position, etc.):- retaining walls; et orm work (i.e. ho	pre-st and de d surfa -(a)(ii) c. and rizonta	ressed cc sign, inclu ce, compl Reinforce other str al shutter	oncrete uding f lete (b ed cem uctura ing) co	e), using coa orms, moul ut excluding ent concre I members mplete in a	rses ds, s the te in othe Il res	and and huttering cost of st slab of ra er than th spects:- (g, feel fts / ose 3)	,			
		RCC thrust blocks	5.														
	а	18''i/d	450	mm	=	2,256.00	/	300	=	8.	0	No					
		8.0	х	3.00	х	1.00	х	1	=	C	u:m			24.0			
	b	12''i/d	315	mm	=	5,032.00	/	200	=	25.)	No					
		25.0	х	3.00	х	1.00	х	1		C	u:m	-		75.0			
	С	10"i/d	250	mm	=	5,032.00	/	200	=	25.0)	No					
		25.0	х	3.00	х	1.00	х	1		C	u:m			75.0			
	d	8" i/d	200	mm	=	5,922.00	/	200	=	30.)	No					
		30.0	х	3.00	х	1.00	х	1		C	u:m			90.0			
	е	6" i/d	160	mm	=	4,349.00	/	200	=	22.)	No					
		22.0	х	3.00	х	1.00	х	1	<u> </u>	C	u:m	1		66.0			
	f	4" i/d	110	mm	=	41,807.00	/	200	=	209.)	No					
		209.0	х	3.00	х	1.00	Х	1	<u> </u>	C	u:m	1	6	527.0			
	g	3"i/d	90	mm	=	11,417.00	/	200	=	57.0)	No					
		57.0	х	3.00	Х	1.00	Х	1		C	u:m		1	.71.0			

		Fabrication of mild steel reinforce				Total	Total = Cu:m 1128.0 ent concrete, including cutting, bending, laving in position,						1128.0	9,324.50	10,518,036		
16		Fabrication of mil making joints and reinforcement (al removal of rust fr	Fabrication of mild steel reinforcement for cement concrete making joints and fastenings, including cost of binding wire reinforcement (also includes removal of rust from bars):- (b) Deformed bars (Grade-40).				e, inclu and la	ıding cutt bour chaı	ing, be ges fo	ending, layi r binding o	ng in f stee	position, el					
		Qty. RCC as per it	em No				=	15	=	C	Cu:m		1	128.0			
		112	28.0		x	175.0	/	2.20	4	Kg		=	8	9564	89564	131.26	11,756,496
	MRS Ch:01 It:01	MRS	Ch:01 lt:(01													
17		Carriage of 100 Cft. (2.83 cu.m) of all materials like ston or 150 Cft. (4.25 cu.m) of timber, by truck or by any othe From Margalla Quarry At Taxila)			aggre mear	egate, spa ns owned	awl, ka I by th	inkar lime ie contract	(unsl :or.(L	aked), su ead up to	urkh o 40	i, etc. 0 KM					
		PCC 1:2:4 as per i	tem No.				=	14	=		3,81	7.87	=	Cu:m			
		RCC 1:2:4 as per i	tem No.				=	15	=		1,12	28.00	=	Cu:m			
						Total			=		4,94	5.87	=	Cu:m			
		Quantity of Bajri=			=	4,945.87	х	154	х	4			=	Cu:m	4,352.36	2,091.55	9,103,188.00
								7	х	100							
		MRSCh:03It:17-	-a,b,c														
18		Transportation of earth all types when the total distance, i more than 1000 ft. (300 m) a) up to ¼ mile (400 m). b) for e beyond ¼ mile (400 m) up to one mile. (1.6 Km.) c) for ever beyond one mile (1.6 Km.) up to 5 mile (8 Km).d) for every			icludir very 3: v ¼ mil 2 mile i	ng the lead 30 ft. (100 e (400 m) (800 m) a	d cove) m) ac addit dditio	red in the i dditional le ional lead c nal lead	tem o ead or or par	of work, i part the t thereo	s ereo f,	F,					
		Quantity same as	s per item	No.			=	3					=	Cu:m	3,817.87		
		Quantity same as per item No .			=	4					=	Cu:m	3,817.87				
		Quantity as per item No .			=	5	=	69,516.60		=							
		Dead volume of pipe as per item No .				=	9	=		7,87	1.93						
		Dead volume of pipe as per item No . Dead volume of sand as per item No .					=	9	=		21,02	27.58					

				NetTotal	=		=	40,617.10		Cu:m	40,617.10		
	Take 80% of abov	ve.			=	-	Ш	32,493.68	=	Cu:m	48,252.83	215.05	10,376,772.00
												Total Rs.	470,458,554.19
												Say Rs.	470.460

Sr. No.	Description	Unit	Qty	Unit Rate Rs	Amount. Rs.
1	Provide, install, test, disinfect & commission of Domestic Water Meters (Multi jet / Volumetric Rotary Piston type /Notating disc) size 15mm with all fittings. Accuracy Class-II and flow rate Q3/Q1 = 160 as per ISO 4064:2014 / OIML R49:2013 standard	No.	110,106	9,100.00	1,001,964,600
2 3	Provide, install, test, disinfect & commission of Commercial Water Meters (Multi jet / Volumetric Rotary Piston type /Notating disc) s i z e 20 t o 25 m m with all fittings. Accuracy Class-II and flow rate Q3/Q1 = 160 as per ISO 4064:2014 / OIML R49:2013 standard Provide, install, test, disinfect & commission Water Magnetic Flow Meters with all fittings.	No.	4,059	13,700.00	55,608,300
	a) 1400 mm	Set	2	8,895,000.00	17,790,000
	b) 1200 mm	Set	6	6,872,000.00	41,232,000
	c) 900 mm	Set	5	4,186,000.00	20,930,000
	d) 800 mm	Set	19	3,890,000.00	73,910,000
	e) 600 mm	Set	16	1,654,000.00	26,464,000
	f) 450 mm	Set	91	1,254,000.00	114,114,000.00
				Total	1,352,012,900
				Rs. in Million	1,352.010

	5.3	Domestic & Commercial Water Meters and Water Flow Meters
--	-----	---

6.5 General Items with Allied Works

Sr. No.	Description	Unit	Qty.	Rate	Amount
1	Providing and fixing G.I. pipe railing, as per standard drawing.	m	18,180.00	3031.70	44,497,368
2	Plain GI sheet iron spouts fixed in position, including painting.	Each	24,240.00	392.75	9,520,260
3	Sign Boards	L.S	200.00	30,000.00	6,000,000
				Total	60,017,628
			R	s. in Million	60.02

Annexure-C

SUMMARY OF POPULATION PROJECTIONS

Summary of population projections is given below:

		Year	2017	2020	2025	2030	2035	2040
	Sr	Growth Rate		2.83	2.75	2.68	2.61	2.54
Phases	No	Sub Division	Population 2017	Projected Population 2020	Projected Population 2025	Projected Population 2030	Projected Population 2035	Projected Population 2040
	1	Shadipura	223384	242891	278177	317350	360807	408818
Phase	2	Baghbanpura	357875	389127	445656	508414	578036	654952
i nase i	3	Mustafabad	100196	108946	124773	142343	161835	183370
	4	Fateh Garh	388415	422333	483687	551801	627364	710844
								1957984
	5	Shadbagh	304935	331564	379731	433205	492528	558066
Phase II	15	Datanagar	228822	248804	284949	325076	369591	418770
	14	Gujjar pura	210765	229170	262462	299423	340425	385724
								1362560
	9	Anarkali	144834	157482	180360	205758	233934	265063
	17	City	226342	246107	281860	321552	365585	414232
Phase III	18	Ravi Road	97968	106523	121998	139178	158237	179293
	19	Krishan Nagar	318814	346655	397014	452922	514945	583466
	8	Shimla Hill	98759	107383	122983	140302	159514	180740
								1622793
	6	Mirsi Shah	105497	114710	131374	149874	170398	193072
Phase IV	10	Tajpura	247908	269557	308716	352190	400418	453700
	11	Mugalpura	134553	146303	167557	191152	217328	246247
								893019
	7	Gulberg	152099	165381	189407	216079	245669	278358
	12	Ichra	211410	229871	263266	300339	341467	386904
	13	Mozang	183899	199958	229007	261256	297032	336556
Flidse v	20	Gulshan-e- Ravi	185091	201254	230491	262949	298957	338738
	16	Samanabad	153775	167203	191494	218460	248376	281426
								1621982
	34	Dholanwal	48533	52771	60437	68948	78390	88821
	21	Allama iqbal town	83614	90916	104123	118786	135052	153023
	22	Farrukhabad	103031	112028	128303	146371	166415	188558
	23	Green town	288747	313962	359572	410208	466381	528440
	24	Industrial area	333305	362411	415060	473509	538350	609986
	25	Garden Town	100921	97421	109734	125675	143933	164842
1 \A/D	26	Johar town	266008	289237	331256	377904	429653	486825
	27	Mustafa town	399736	434643	497785	567884	645649	731562
	28	Sabzazar	250483	272357	311923	355848	404577	458412
	29	Shahdara	212942	231537	265173	302516	343942	389708
	30	Township	140069	152301	174426	198989	226238	256342
	31	Jublee town	263650	286673	328319	374554	425845	482509
	32	LDA Avenue-I	287980	313128	358617	409118	465142	527036
	33	Farrukhabad	35681	38797	44433	50690	57632	65300
								5131366

		Year	2017	2020	2025	2030	2035	2040
	C r	Growth Rate		2.83	2.75	2.68	2.61	2.54
Phases	No.		Population	Projected	Projected	Projected	Projected	Projected
	NO	Sub Division	2017	Population	Population	Population	Population	Population
			2017	2020	2025	2030	2035	2040
	35	Barki	188711	185711	205190	234999	268092	304804
	36	Bhaseen	140443	137443	152707	174892	199520	226842
	37	Chung	205538	202538	223487	255953	291997	331983
	38	Halloke	123265	120265	134029	153500	175116	199096
	39	Hundiara	220462	217462	239714	274538	313199	356088
	40	Jia Bagga	60962	57962	66286	75915	86606	98465
	41	Kamahan	1230126	1227126	1337547	1531857	1747576	1986886
	42	Manga	106535	103535	115838	132666	151349	172074
	43	Niaz Baig	11630	8630	12646	14483	16522	18785
	44	Riwind	164142	161142	178476	204404	233188	265120
	45	Industrial NW	25870	22870	28129	32216	36752	41785
	46	Johar Town NW	95411	92411	103743	118814	135545	154107
	47	Garden Town NW	13727	10727	14926	17094	19501	22172
Rural	48	Ichra NW	7143	4143	7767	8895	10148	11537
and	49	Mustafa Town NW	7825	4825	8508	9744	11117	12639
Non-	50	Gulshan-e-ravi NW	95271	92271	103591	118640	135347	153881
WASA	51	Krishna Nagar NW	29614	26614	32200	36878	42071	47832
	52	Ravi Road NW	18550	15550	20170	23100	26353	29962
	53	Kasur Pura NW	50587	47587	55005	62995	71866	81708
	54	City NW	4096	1096	4454	5101	5819	6616
	55	Gujar pura NW	27118	24118	29486	33770	38525	43801
	56	Baghbanpura NW	3906	906	4247	4864	5549	6309
	57	Darrogawala NW	20005	17005	21752	24912	28420	32312
	58	Muslimabad NW	17792	14792	19346	22156	25276	28737
	59	Salamat Pura NW	57431	54431	62446	71518	81589	92762
	60	Fateh Garh Nw	36072	33072	39222	44920	51246	58263
	61	Shadra-NW	36500	30000	39687	45453	52056	59618
	62	Kahna	114860	124890	143033	163176	185521	210207
	63	Cantt,DHA,RA Bazar	1087838	1084338	1182834	1354668	1551465	1776852
	64	Model Town	34980	31480	38035	43560	49888	57136
								6888376

Annexure - C

ANNEXURE - D

Punjab Environmental Quality Standards (PEQS)

ANNEXURE - D (1)

Punjab Environmental Quality Standards for Municipal and Liquid Industrial Effluents



PUBLISHED BY AUTHORITY

LAHORE MONDAY AUGUST 15, 2016

GOVERNMENT OF THE PUNJAB LAW AND PARLIAMENTARY AFFAIRS DEPARTMENT

NOTIFICATION (120 of 2016)

12th August 2016

The following Notification No. SO(G)/EPD/7-26/2013, dated 05.08.2016 regarding the Punjab Environmental Quality Standards for Municipal and Liquid Industrial Effluents is published for general information:

> DR SYED ABUL HASSAN NAJME Secretary Government of the Punjab Law and Parliamentary Affairs Department

1192

Government of the Punjab Environment Protection Department

NOTIFICATION: No. SO(G)/EPD/7-26/2013. – In exercise of the powers conferred under clause (c) of sub-section (1) of section 4 of the Punjab Environmental Protection Act; 1997 (XXXIV of 1997), the Environmental Protection Council has approved the following as the Punjab Environmental Quality Standards for Municipal and Liquid Industrial Effluents.

Punjab Environmental Quality Standards for Municipal and Liquid Industrial Effluents (mg/l, unless otherwise defined)

No	Parameter	Into Inland Waters	Into Sewage Treatment
1	2	3	4
1	Temperature or Temperature Increase *	≤ 3 ⁰ C	$\leq 3^{\circ}C$
2	pH value (H ⁺)	6-9	6-9
3	Biochemical Oxygen Demand (BOD ₅) at 20 °C	80	250
4	Chemical Oxygen Demand (COD) ⁽¹⁾	- 150	400 ·
5.	Total suspended solids (TSS)	200	400
6	Total dissolved solids (TDS)	3500	3500
7	Grease and Oil	10	10
8	Phenolic compounds (as phenol)	0.1	.0.3
9	Chloride (as Cl [−]).	1000	. 1000
10	Fluoride (as F ⁻)	10	10
11	Cyanide (as CN ⁻) total	1.0	1.0
. 12	An-ionic detergents (as MBAs) ⁽²⁾	20	20
13	Sulfate (SO ₄ ²⁻)	600	1000

6			
No	Parameter	Into Inland Waters	Into Sewage Treatment
.1	2	3	. 4
14	Sulfide (S ²⁻)	1.0	1.0
15	Ammonia (NH3)	40	40
16	Pesticides ⁽³⁾	0.15	0.15
17	Cadmium (Cd) ⁽⁴⁾	0.1	0.1
18	Chromium (trivalent and hexavalent) ⁽⁴⁾⁽¹⁾	1.0	1.0
19	Copper (Cu) ⁽⁴⁾	1.0	1.0
20	Lead (Pb) ⁽⁴⁾	0.5	0.5
21	Mercury (Hg) ⁽⁴⁾	0.01	0.01
22	Selenium (Se) ⁽⁴⁾	0.5	0.5
23	Nickel(Ni) ⁽⁴⁾	1.0	1.0
24	Silver(Ag) ⁽⁴⁾	1.0	1.0
25	Total Toxic metals	2.0	2.0
26	Zinc (Zn)	5.0	5.0
27	Arsenic (As) ⁽⁴⁾	1.0	1.0 -
28	Barium (Ba) ⁽⁴⁾	1.5	1.5
25	Iron (Fe)	8.0	8.0
30	Manganese (Mn)	1.5	1.5
31	Boron (B) ⁽⁴⁾	6.0	6.0
. 32	2 Chlorine (Cl_2)	1.0	1:0

Explanations:

1. Assuming minimum dilution 1:10 on discharge, lower ratio would attract progressively stringent standards to be determined by the Provincial Environmental Protection Agency. By 1:10 dilution means, for example that for each one cubic meter of treated effluent, the recipient water body should have 10 cubic meter of water for dilution of this effluent.

2. Methylene Blue Active Substances; assuming surfactant as biodegradable.

- Pesticides include herbicides, fungicides and insecticides.
- 4. Subject to total toxic metals, discharge should not exceed level given at S.N. 25.
- 5. Applicable only when and where sewage treatment is operational and $BOD_5=80$ mg/l is achieved by the sewage treatment system.
 - The effluent should not result in temperature increase of more * than 30°C at the edge of the zone where initial mixing and dilution take place in the receiving body. In case zone is not defined, use 100 meters from the point of discharge.
 - The value for industry is 200 mg/l. **

Note: 1. Dilution of liquid effluents to meet to the PEQS limiting value is not permissible through fresh water mixing with the effluent before discharging into the environment.

The concentration of pollutants in water being used will be 2. subtracted from the effluent for calculating the PEQS limits.

diatan!

(IQBAL MOHAMMED CHAUHAN) Secretary, Government of the Punjab Environment Protection Department

ANNEXURE - D (2)

Punjab Environmental Quality Standards for Motor Vehicles Exhaust and Noise

EXTRA ORDINARY ISSUE





LAHORE MONDAY AUGUST 15, 2016

PUBLISHED BY AUTHORITY

GOVERNMENT OF THE PUNJAB LAW AND PARLIAMENTARY AFFAIRS DEPARTMENT

NOTIFICATION (123 of 2016)

12th August 2016

The following Notification No. SO(G)/EPD/7-26/2013, dated 05.08.2016 regarding the Punjab Environmental Quality Standards for motor vehicle exhaust and noise is published for general information:

DR SYED ABUL HASSAN NAJMEE

Secretary Government of the Punjab Law and Parliamentary Affairs Department

1202

Government of the Punjab **Environment Protection Department**

NOTIFICATION: No. SO(G)/EPD/7-26/2013. - In exercise of the powers conferred under clause (c) of sub-section (1) of section 4 of the Punjab Environmental Protection Act, 1997 (XXXIV of 1997), the Environmental Protection Council has approved the following as the Punjab Environmental Quality Standards for motor vehicle exhaust and noise:

Punjab Environmental Quality Standards for Motor Vehicle Exhaust and Noise

(i) For In-use Vehicles

No	Parameter	Standards (maximum permissible limit)	Measuring methods	Applicability
1	2	3	4	5
1	Smoke	40% or 2 on the Ringlemann Scale during engine acceleration mode	To be compared with Ringlemann Chart at a distance of 6 meters or more	Immediate effect
2	Carbon Monoxide	6%	Under idling conditions: Non dispersive infrared detection through gas analyzer	
3	Noise	85 dB(A)	Sound-meter at 7.5 meter from the source	

For New Vehicles (ii)

EMISSION STANDARDS FOR DIESEL VEHICLES

(a) For Passenger Cars and Light Commercial Vehicles (g/km)

Type of Vehicle	Category/Class	Tiers	со	HC+ NOx	РМ	•Measuring method	Applicability
1	2	3	4	5	6	7	8

	· · · ·		1.1	c		· · ·	^
Passenger	M1: with reference	Pak-II IDI	1.0	Q:7	0.08		All imported and locally
Cars	mass (RW) upto 2500 kg				 [manufactured diesel
н 10				3 ² 8 9	la e		vehicles with effect from
· · ·	Cars with RW over 2500 kg to	Pak-II, DI	1.0	0.9	0,10	NEDC	01-07-2012
ε. 'α	meet NI category standards		،)	
Light Commercial	N1-I(RW<1250kg)	Pak-II, IDI	. 1.0 	0.70	0.08		
Vehicles		Pak-II, DI	1.0	0.90	0.10		
	N1-11(1250kg< RW<1700kg)	Pak-II, IDI	1.25	1.0	0.12		
*		Pak-II, DI	1.25	1.3	0.14		
	N1- III(RW>1700kg)	Pak-II, Pak-II	1.50) 1.2	0.1	7	
		Pak-II, D	1 1.5	0 .1.6	0.2	.0	· · · · · · · · · · · · · · · · · · ·

Parameters Standards (maximum permissible limit)	Measuring method
85 dB(A)	Sound-meter at 7.5 meters from the source

(b) For Heavy Duty Diesel Engine and Large Goods Vehicles (g/KWh)

Type of Vehicle	Category/ Class	Tiers	со	нс	NOx	PM	Measuring method	Applicability
	- 2	3	4	5	6	7	8	9
Heavy Duty Diesel Engine	Trucks & Buses	Pak-II	4.0.	1.1	7.0	0.15	ECE-R-49	All imported and locally manufactured diesel vehicles with effect from 01-07-2012
Large Goods Vehicl	N2(2000 and up)	Pak-II	4.0	7.0	1.1	0.15	EDC	

1203

es		· · · · · · · · · · · · · · · · · · ·
Parameters	Standards (maximum permissible limit)	Measuring methods
Noise	85 dB(A)	Sound-meter at 7.5 meters from
		the source

EMISSION STANDARDS FOR PETROL VEHICLES (g/km)

Type of Vehicle	Category/Class	Tiers	CO	'HC+ NOx	Measuring method	Applicability
1	2.	3	4	5	6	7
Passenger Cars	M1: with reference mass (RW) upto 2500kg. Cars with RW over 2500kg to meet. NI category standards	Pak-II	2.20	0.5	NEDC(EC E15+EUDC L)	All imported and new models * locally manufactured petrol vehicles with effect from 01-07-2009**
Light Commercia	N1- I(RW<1250kg)	Pak-II	2.20	0.5		
1 venicies	N1-II(1250kg> RW<1700kg)	Pak-II	4.0	0.65		
	N1- III(RW>1700kg)	Pak-II	5.0	0.08		
Motor Rickshaws	2,4 strokes<150cc	Pak-II	5.5	1.5	ECER 40	
Cycles	2,4 strokes>150cc	Pak-II	- 5.5	1.3		*

arameters	permissible mint)	
Noise	85 dB(A)	Sound-meter at 7.5
	Noise	Noise 85 dB(A)

Explanations:

			•
÷	DI:	Direct Injection	
	IDI:	Indirect Injection	
8	EUDCL:	Extra Urhan Driving Cycle	
100	NEDC:	New European Driving Cycle	
	ECE:	Urban Driving Cycle	
	M:	Vehicles designed and constructed for the carriage of passengers and	
2	1.1111111111	comprising no more than eight seats in addition to the driver's seat.	
	N:	Motor vehicles with at least four wheels designed and constructed for the	
	10 ₁₀	carriage of goods	
	*	Now Model means both model and design type change	
2	**	The existing Model of petrol driven vehicles locally manufactured with	1
		immediately switched over to Pak-II emission standards but not later than	
		30 th June 2012	

புலாலு.

(IQBAL MOHAMMED CHAUHAN) Secretary, Government of the Punjab Environment Protection Department

ANNEXURE - D (3)

Punjab Environmental Quality Standards for Ambient Air

EXTRA ORDINARY ISSUE

REGISTERED No. L-7532



LAHORE MONDAY AUGUST 15, 2016

GOVERNMENT OF THE PUNJAB LAW AND PARLIAMENTARY AFFAIRS DEPARTMENT

NOTIFICATION (122 of 2016)

12th August 2016.

The following Notification No. SO(G)/EPD/7-26/2013, dated 05.08.2016 regarding the Punjab Environmental Quality Standards for Ambient Air is published for general information:

DR SYED ABUL HASSAN NAJMEE

Secretary Government of the Punjab Law and Parliamentary Affairs Department

(1197)

nn Dar

Government of the Punjab Environment Protection Department

NOTIFICATION: No. SO(G)/EPD/ 7-26 /2013. – In exercise of the powers conferred under clause (c) of sub-section (1) of section 4 of the Punjab Environmental Protection Act, 1997 (XXXIV of 1997), Environmental Protection Council has approved the following as the Punjab Environmental Quality Standards for Ambient Air:

Punjab Environmental Quality Standards for Ambient Air

Pollutant	Time-weighted average	Concentration in Ambient Air	Method of measurement
Sulfur Dioxide	Annual Average*	80 μg/m ³	Ultraviolet Fluorescence
(SO ₂)	24 hours**	120 µg/m ³	
Oxides of Nitrogen	Annual Average*	40 μg/m ³	Gas Phase Chemiluminescence
as (NO)	24 hours**	40 μg/m ³	
Oxides of Nitrogen	Annual Average*	40 μg/m ³	Gas Phase Chemiluminescence
as (NO ₂)	24 hours**	80 μg/m ³	
Ozone (O ₃)	l hour	130µg/m ³	Non dispersive UV absorption method
Suspended Particulate Matter	Annual Average*	360µg/m ³	High Volume Sampling, (Averag
(SPM)	24 hours**	500µg/m ³	than $1.1 \text{ m}^3/\text{min}$).
Respirable Particulate Matter	Annual Average*	120µg/m ³	Preferably β-Ray absorption method
PM10	24 hours**	150µg/m ³	
Respirable Particulate Matter	Annual Average*	15µg/m ³	Preferably β-Ray absorption metho
PM2.5	24 hours**.	35µg/m ³	

1198

Pollutant	Time-weighted average	Concentration in Ambient Air	Method of measurement	
	1 hour	15µg/m ³		
	Annual Average*	1 μg/m ³	ASS Method after sampling using FPM 2000 or	
Lead (Pb)	24 hours**	1.5µg/m ³	equivalent Filter paper	
Carbon Monovide	8 hours**	5 mg/m^3 .	Non Dispersive	
(CO)	1 hour	410 mg/m ³	method	

* Annual arithmetic mean of minimum 104 measurements in a year taken twice a week 24 hourly at uniform interval.

** 24 hourly /8 hourly values should be met 98% of the in a year. 2% of the time, it may exceed but not on two consecutive days.

matral.

(IQBAL MOHAMMED CHAUHAN) Secretary, Government of the Punjab Environment Protection Department

ANNEXURE - D (4)

Punjab Environmental Quality Standards for Noise

EXTRA ORDINARY ISSUE

The

REGISTERED No. L-7532



PUBLISHED BY AUTHORITY

LAHORE MONDAY AUGUST 15, 2016-

GOVERNMENT OF THE PUNJAB LAW AND PARLIAMENTARY AFFAIRS DEPARTMENT

NOTIFICATION (121 of 2016)

12th August 2016

The following Notification No. SO(G)/EPD/7-26/2013, dated 05.08.2016 regarding the Punjab Environmental Quality Standards for Noise is published for general information:

(1198)

DR SYED ABUL HASSAN NAJMEE

Secretary Government of the Punjab Law and Parliamentary Affairs Department

and the first for Page

Government of the Punjab Environment Protection Department

NOTIFICATION: No. SO(G)/EPD/7-26 /2013. In exercise of the powers conferred under clause (c) of sub-section (1) of section 4 of the Punjab Environmental Protection Act, 1997 (XXXIV of 1997), the Environmental Protection Council has approved the following as the Punjab Environmental Quality Standards for Noise:

		Effective July, 2	from 1 st 2010	Effective from 1 st July, 2013			
х т	Cotogory of Area/Zone	Limits in dB(A) Leq*					
INO.	Category of Mon 2	Day Time	Night Time	Day Time	Night Time		
		65	50	. 55	45		
1	Residential Area (A)	00	. 60	65	55		
2	Commercial Area (B)	10 .		75	65		
3	Industrial Area (C)	80	75				
Å	Silence Zone (D)	55	45	50	45		

Punjab Environment Quality Standards for Noise

Note:

1196

1. Day time hours; 6:00am to 10:00pm.

2. Night Time hours; 10:00 pm to 6:00 am.

- Silence Zone: Zones which are declared as such by the competent authority. An area comprising not less than 100 meters around hospital, educational institutions and courts
- 4. Mixed categories of areas may be declared as one of the four above mentioned categories by the competent authority
- dB(A) Leq: Time weighted average of the level of sound in decibel on scale A which is relatable to human hearing.

(IQBAL MOHAMMED CHAUHAN) Secretary, Government of the Punjab Environment Protection Department

ANNEXURE - D (5)

Punjab Environmental Quality Standards for Treatment of Liquid and Disposal of Bio-Medical Waste EXTRA ORDINARY ISSUE

The





ab Gazette

PUBLISHED BY AUTHORITY

LAHORE MONDAY AUGUST 15, 2016

GOVERNMENT OF THE PUNJAB LAW AND PARLIAMENTARY AFFAIRS DEPARTMENT

NOTIFICATION (119 of 2016)

12th August 2016

The following Notification No. SO(G)/EPD/7-26/2013, dated 05.08.2016 regarding the Punjab Environmental Quality Standards for Treatment of Liquid and Disposal of Bio-medical Waste by Incineration, Autoclaving, Microwaving, and Deep Burial is published for general information:

DR SYED ABUL HASSAN NAJMEE

Secretary Government of the Punjab Law and Parliamentary Affairs Department

Price Rs. 10.00 Per Page

Government of the Punjab Environment Protection Department

NOTIFICATION: No. SO(G)/EPD/ 7-26/2013: In exercise of the powers conferred under clause (c) of sub-section (1) of section 4 of the Punjab Environmental Protection Act, 1997 (XXXIV of 1997), the Environmental Protection Council has approved the following as the Punjab Environmental Quality Standards for Treatment of Liquid and Disposal of Bio-medical Waste by Incineration, Autoclaving, Microwaving, and Deep Burial.

All bio-medical waste incinerators shall meet the following operating and emission standards:

A. Operating Standards:

1.

Combustion Efficiency, computed as given below, shall be at least 99.0%:

Combustion Efficiency =
$$\frac{\% CO_2}{\% CO_2 + \% CO} \times 100$$

2. Minimum temperature of the primary chamber shall be 800°C.

3. The gas residence time in secondary chamber shall be at least 1 (one) second at the temperature of $1200 \pm 50^{\circ}$ C with at least 3% oxygen in the stack emissions.

No.	Parameter	Standard				
1.	2.	3.	4. Sampling Duration in minutes, unless stated			
- - -		Limiting concentration in mg/NM ³ unless stated				
1.*	Particulate matter	50	30 or 1NM ³ of sample volume, whichever is more			
2.	Nitrogen Oxides expressed as NO ₂	400	30 for online sampling or grab sample			
3. :	HCI	50	30 or 1 NM ³ of sample volume, whichever is more			

B. Emission Standards:

1187

No.	Parameter	Standard						
1.	2.	. ⁹ .	3.,	. •		4.		
4.	Total Dioxins and Furans	0.1 ng TEQ/N ³ (at 11% O ₂)			8 hours or 5NM ³ of sample volume, whichever is more			
5.	Hg and its compounds		0.05	. 15	2 hour sample which	s or 1NM ³ of e volume, ever is more		

Note:

- (a) Air pollution control devices shall be installed or retrofitted with the incinerator to achieve the above given emission standards. All existing incinerators shall comply with these standards within a period of 2 years from the date of this notification.
- (b) Secondary combustion chambers and pollution control devices of existing incinerators shall be suitably retrofitted, if necessary, to achieve these standards.
- (c) Chlorinated plastics shall not be incinerated and the wastes incinerated shall also not be chemically treated with any chlorinated disinfectant.
- (d) Ash from incineration of biomedical waste shall be disposed of at a Hazardous Waste Treatment and Disposal Facility. However, it may be disposed of in municipal landfill, if the toxic metals in incineration ash are within the regulatory quantities as defined under the Hazardous Waste or as revised from time to time.
- (e) Only low Sulphur fuel such as Light Diesel Oil, CNG, or LGP shall be used as fuel in the incinerator.
- (f) Stack gaseous emissions shall be monitored under maximum capacity of the incinerator once in three months through a laboratory approved under the Punjab Environmental Protection Act, 1997 and record of such analysis results shall be maintained and submitted to EPA Punjab. For dioxins and furans, monitoring shall be done once in a year.
- (g) Continuous emission monitoring system for the CO, CO₂, and O₂ parameters shall be installed in stack and its data shall be transmitted in real time to the servers at EPA Punjab.
- (j) The monitored values shall be corrected to 11% Oxygen on dry basis.
- (k) In addition to complying with temperature and residence time standards. incinerators (combustion chambers) shall be operated with such temperature, retention time and turbulence, as to achieve Total Organic

Carbon (TOC) content in the slag and bottom ashes less than 3% or their loss on ignition shall be less than 5% of the dry weight.

(1) Combustion gas analyzers shall be used to measure CO₂, CO and O₂.

DEEP BURIAL.

1188

- 1. A pit or trench shall be dug about 2 meters deep. It shall be half filled with waste, then covered with lime within 50 cm of the surface, before filling the rest of the pit with soil.
- 2. It shall be ensured that animals do not have any access to burial sites. Covers of galvanized iron/wire meshes may be used.
- 3. Burial shall be performed under close and dedicated supervision:
- 4. The deep burial site shall be relatively impermeable and no shallow well should be close to the site.
- 5. The pits shall be away from habitation, and sited so as to ensure that no contamination of any surface water or ground water occurs. The area should not be prone to flooding or erosion.
- 6. The location of the deep burial site shall be authorized by EPA Punjab.
- 7. A record of all pits for deep burial shall be maintained.

AUTOCLAVING

2:

Dedicated autoclave shall be used for disinfecting and treating bio-medical waste.

- 1. In a gravity flow autoclave, medical waste shall be subjected to:
 - (i) a temperature of not less than 125°C at 15 pounds per square inch (psi) with a residence time of not less than 60 minutes; or
 - (ii) a temperature of not less than 135 °C and a pressure of 30 psi with an autoclave residence time of not less than 45 minutes; or
 - (iii) a temperature of not less than 150 °C and a pressure of 50 psi with an autoclave residence time of not less than 30 minutes.
 - In a vacuum autoclave, medical waste shall be subjected to a minimum of one pre-vacuum pulse to purge the autoclave of all air. Waste shall be treated at:
 - (i) a temperature of not less than 125 °C and pressure of 15 psi with a autoclave residence time of not less than 45 minutes. or
 - (ii) a temperature of not less than 135 °C and a pressure of 35 psi with an autoclave residence time of not less than 30 minutes.
 - Medical waste shall be deemed treated if all parameter (residence time, temperature and pressure) indicators indicate that their required values

were reached during the autoclaving process. If for any reasons, either of the parameter (residence time, temperature or pressure) was not reached, the entire batch of waste shall be autoclaved again until all the required parameters (temperature, pressure and residence time) are achieved.

1189

For recording of operational parameters, each autoclave shall have graphic or computer recording devices which will automatically and continuously monitor and record dates, time of day, load identification number and operating parameters throughout the entire length of the autoclave cycle.

The autoclave should completely and consistently kill the approved biological indicator at its maximum design capacity. Biological indicator for autoclave shall be *Bacillus stearothermophilus* spores using vials or spore strips with at least 1×10^4 spores per milliliter.

Under no circumstances will an autoclave have minimum operating parameters less than a residence time of 30 minutes, regardless of temperature and pressure, a temperature less than 125°C or a pressure less than 15 psi.

A chemical indicator strip/tape that changes color when a certain temperature is reached can be used to verify that a specific temperature has been achieved. It may be necessary to use more than one strip over the waste package at different location to ensure that the inner content of the package has been adequately autoclaved

STANDARDS OF MICROWAVING

Microwave treatment shall not be used for cytotoxic or radioactive wastes, contaminated animal carcasses, body parts, and large metal items.

The microwave system shall comply with the efficacy test/routine tests and a performance guarantee provided by the manufacturer/supplier.

The microwave should completely and consistently kill the bacteria and other pathogenic organisms that is ensured by approved biological indicator at its maximum design capacity. Biological indicators for microwave shall be *Bacillus Subtilis* spores using vials or spore strips with at least 1×10^1 spores per milliliter.

LIQUID WASTE

5.

1.

2.

3.

The effluent generated from a hospital should conform to the following limits:

	PARAMETERS	PERMISSIBLE LIMITS	
6	рН	6.3-9.0	

οσ/İ		20 20		1.2	-			
16/1	•		* (*	ii .	i	(2)	12	2 1
ng/l		2			l s e ^{re}		15	1
mg/l		•.	-		2 B.			201
	ng/l mg/l	ng/l mg/l	ng/l mg/l	ng/l mg/l	ng/l mg/l	ng/l mg/l	ng/l mg/l	ng/l mg/l

These limits are applicable to the hospitals, which are either connected to sewers without terminal sewage treatment plant or not connected to public sewers.

For discharge into public sewers with terminal treatment facilities, the general standards as notified under the Punjab Environmental Protection Act, 1997 shall be applicable.

المماتحا

(IQBAL MOHAMMED CHAUHAN) Secretary, Government of the Punjab Environment Protection Department

Annexure-E

Gap Analysis and Requirements for Statutory Clearances
Gap Analysis and Requirements for Statutory Clearances

Tonic	World Bank Policies	Pakistan Laws and Regulations	How the gap will be
		r akistan Laws and Regulations	addressed in the FMF
Screening	The Bank undertakes environmental	Farly screening of projects is	Subprojects will be screened
Corcorning	screening of each proposed project to	carried out according to Pakistan	under both systems
	determine the appropriate extent and type	Environmental protection Agency	
	of anyironmental assessment. The Bank	Poviow of IEE and EIA	
	classifies the proposed project into one of	Review of The ERA	
	four estagarias depending on the type	Regulations, 2000. The EFA	
	location categories, depending on the type,	classifies the proposed project	
	location, sensitivity, and scale of the project	into two categories	
	and the nature and magnitude of its		
	potential environmental impacts.		
Safeguard	For a Category A project: EIA and EMP For	For Schedule 1: IEE For Schedule	Safeguard
document	a Category B project: Less detailed EIA	2: EIA	Instruments/Documents will
requirement (IEE,	than Category A, and / or an EMP For a		be prepared in consideration
EIA, EMP)	Category C project: Only Screening, no		with or as per requirements
	documentation required		of both the systems
Physical cultural	OP4.11 requires the development of PCR	In Antiquities Act 1975, there is no	The World Bank system will
resources	management plan or its incorporation in	requirement for such procedures	be followed.
	EMP developed for EA		
Consultation	According to OP 4.01 Category A and B	According to PEPA 1997, there is	Consultation will also be held
	requires consultations with project affected	no provision for consultation at	at earlier stage as required.
	groups and local nongovernmental	screening stage. However, a	
	organizations (NGOs). Category A projects	public consultation/hearing is	
	require at least two consultations: (a)	conducted after preparation of	
	shortly after environmental screening and	Draft EIA for EPA approval.	
	before the terms of reference for the EA are		
	finalized: and (b) after preparation of Draft		
	EIA report		

Annexure-E(1)

Annexure-E(1)

COMPARISON BETWEEN IFC/AIIB AND PEQS FOR NOISE

	IFC / AIIB			PEQS	
Receptor	Day Time	Night Time		Day Time	Night Time
	07:00 - 22:00	22:00 - 07:00			
Residential,	55	45	Residential Area (A)	55	45
Institutional and					
Educational					
Industrial and	70	70	Commercial Area (B)	65	55
Commercial					
	•		Industrial Area (C)	75	65
			Silence Zone (D)	50	45

COMPARISON BETWEEN IFC / AIIB AND PEQS GUIDELINES FOR NOISE

According to the guidelines of IFC and PEQS for noise it can be observed that;

- **1.** there are no hours mention for day and night time in PEQS
- 2. the Industrial and Commercial values have a quiet difference
- 3. the values of PEQS for Industrial and Commercial are more stringent then IFC

Annexure-F

TRAFFIC COUNT

Annexure - F

Traffic Count

The traffic count was observed in 4 different time segments including the peak hours of the day. The total number of vehicles passing through were count manually including Tractor Trolleys, Chingchi Autos, Autos, Donkey Carts, Trucks, Wagons, Loaders, Pickups, Bikes and cars. Per day vehicles including all were estimated as 501 vehicles in a day of 16 hours.

Calculation

501 Vehicles per day

501 X 7 = 3507 per week

For confidence ratio/limit total number of vehicles were divided by 0.95 to get the total number of vehicles per week after confidence limit.

3507 X 0.95 = 3691.57 ~ 3692

For the conversion factor for low urban area traffic count the total number of vehicles were multiplied to 0.98 for the annual average daily traffic rate.

3692 X 0.989 = 3618

Annual Average Daily Traffic Rate = 3618 Vehicles



Pictorial Profile for Traffic Count at Bhaini Road

Annexure - G

PACKAGE 03 - LAB REPORTS

Surface Water Treatment Plant

LAB Reports

Surface Water Treatment Plant

Ambient Air Monitoring Reports



Formerly : Global Environmental Lab (GEL)

Doc # GEL-TP-08-F-003 lasue # 01 Date: 15-12-17 PAGE I OF 1

AMBIENT AIR QUALITY MONITORING REPORT

Report reference No: Name of Customer: Address:

Date of Monitoring:

Date of Completion of Analysis:

Project:

Location:

GEL/Internal/06-19/A-2 Lahore Water & Sanitation Authority 31 - B, Zahoor Elahi Road, Block B Gulberg II, Lahore-Pakistan. Lahore Water & Wastewater Project Mentioned Below 30.06.2019 05.07.2019

Date: 05.07.2019

S. NO.	Source	CO (mg/m ³)	O ₃ (ug/m ³)	SO _{2 (} ug/m ³)	NO₂ (<i>u</i> g/m³)	Noise (dBA)	PM ₁₀ (<i>u</i> g/m ³)	Remarks
	PEQS	10	130	120	80	75	? 150	
1	1 Km Away From Ranger Area, 400 m Right Down Dera Haji Akram	BDL	13	2.6	35.5	48.2	27	
2	Western Side of Project	BDL	17	2.6	31.7	42.3	36	-
3	Mid Side, Dera Mian Yousaf	BDL	14	2.6	41.1	43.8	30	
4	Northern Side of Project	BDL	19	2.6	29.9	42.1	28	
5	Project Area Towards, Gang-e-Sandhuwan	1.1	16	5.2	43	43.2	34	
Deviatio	on from standard mothed if any	NII						

PEQS: Punjab Environmental Quality Standards.

BDL: Below detectable limit. This report is not valid for any negotiation

1. Report Prepared by:

2. Checked/Verified by:

3. Signature of the incharge of the environmental laboratory:

Ghyast Manager (Admin) 05.07.2019

END OF THE REPORT

Name:

Date:

Designation:



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org



GLOBAL ECO LAB Formerly : Global Environmental Lab (GEL)

Doc.# GEL-TP-08-F-003 Innue # 01 Innue Date: 15-12-17 PAGE 1 OF 1

AMBIENT AIR QUALITY MONITORING REPORT

Date: 05.07.2019

Report reference No: Name of Customer: Address:

Project: Location: Date of Monitoring: Date of Completion of Analysis: GEL/Internal/07-19/A-1 Lahore Water & Sanitation Authority 31 - B, Zahoor Elahi Road, Block B Gulberg II, Lahore-Pakistan. Lahore Water & Wastewater Project Mentioned Below 01.07.2019 05.07.2019

S. NO.	Location	CO (mg/m ³)	O ₃ (ug/m ³)	SO _{2 (} ug/m³)	NO₂ (<i>u</i> g/m³)	Noise (dBA)	PM ₁₀ (<i>u</i> g/m ³)	Remark s
	PEQS	10	130	120	80	75	150	
1	Near Graveyard	BDL	14	2.6	29.9	50.3	30	
2	Boundary Line Behind Cold Storage, Dera Imran Hafeez	1.1	18	5.2	37.4	51.4	36	
3	Gang-e-Sandhuwan Population	1.1	22	20.8	74.8	61.5	60	
4	Gang-e-Sandhuwan Road	1.1	19	23.5	71.0	59.4	78	3
5	Taij Garh Grave Yard	1.1	24	15.6	59.8	58.2	68	
Deviatio	on from standard method if any:	Nil						

PEQS: Punjab Environmental Quality Standards.

BDL: Below detectable limit. This report is not valid for any negotiation

1. Report Prepared by:

2. Checked/Verified by:

3. Signature of the incharge of the environmental laboratory:

Ghyasuddin Manager (Admin)

Date: 05.07.2019

Name:

Designation:



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org



Formerly : Global Environmental Lab (GEL)

Doc.# GEL-TP-08-F-003 Issue # 01 Issue Date: 15-12-17 PAGE 1 OF 1

Date: 05.07.2019

AMBIENT AIR QUALITY MONITORING REPORT

Report reference No: Name of Customer: Address:

Project: Location: Date of Monitoring: Date of Completion of Analysis: GEL/Internal/07-19/A-2 Lahore Water & Sanitation Authority 31 - B, Zahoor Elahi Road, Block B Gulberg II, Lahore-Pakistan. Lahore Water & Wastewater Project Mentioned Below 02.07.2019 05.07.2019

S. NO.	Location	CO (mg/m ³)	O ₃ (ug/m ³)	SO _{2 (} ug/m³)	NO ₂ (<i>u</i> g/m ³)	Noise (dBA)	PM ₁₀ (<i>u</i> g/m ³)	Remarks
	PEQS	10	130	120	80	75	150	يې 1- يې د يې د ي
1	Taij Garh	3.4	28	18.3	74.8	62.2	86	
2	Shalimar Ring Road Industrial Scheme	5.7	26	28.7	67.3	64.3	102	
3	Al Rahim Gardens End Point	1.1	23	20.8	63.5	53.4	60	.
4	Mominpura Grid Station (Back Side) Al Rahim Gardens	2.2	29	15.6	67.3	58.4	60	
5	Hando Chowk (Industries) Mominpura Road	4.6	21	31.3	61.7	69.8	96	
Deviction	a fram standard method if on "	Nil	1 1 A 1 A 1	1997 - Contra 19	Section 2. In the section of the sec			

Deviation from standard method if any: PEQS: Punjab Environmental Quality Standards

BDL: Below detectable limit.

This report is not valid for any negotiation.

1. Report Prepared by:

Analyst

2. Checked/Verified by:

3. Signature of the incharge of the environmental laboratory:

Ghyasud

Name: Designation:

ation: Manager (Admin Date: 05.07.2019

END OF THE REPORT



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org



Formerly : Global Environmental Lab (GEL)

Doe # GEL-TP-08-F-003 Issue # 01 Issue Date: 15-12-17 PAGE 1 OF 1

05.07.2019

Date:

AMBIENT AIR QUALITY MONITORING REPORT

Report reference No: Name of Customer: Address:

Date of Monitoring:

Date of Completion of Analysis:

Project:

Location

GEL/Internal/06-19/A-1 Lahore Water & Sanitation Authority 31 - B, Zahoor Elahi Road, Block B Gulberg II, Lahore-Pakistan. Lahore Water & Wastewater Project Mentioned Below 29.06.2019 05.07.2019

Source S. NO. CO (mg/m³) PM₁₀ (ug/m³) O₃ (ug/m³) SO_{2 (}ug/m³) NO2 (ug/m3) Noise (dBA) Remarks PEQS 10 130 120 75 150 80 From Where Link Canal to be 1 1.1 14 5.2 56.1 54 56.1 Extracted From BRB Canal 2 Transmission Main 2nd Point BDL 12 2.6 44.8 44.8 38 3 Transmission Main 3rd Point BDL 15 2.6 40 46.7 46.7 Transmission Main End Point at Start of Ranger Area 300 m BDL 2.6 4 11 41.1 41.1 31 Right Down Just Before End of Ranger 5 BDL 16 2.6 48.6 48.6 29 Area, 300 m Right Down Deviation from standard method if any: Ni

PEQS: Punjab Environmental Quality Standards.

BDL: Below detectable limit.

This report is not valid for any negotiation

1. Report Prepared by:

2. Checked/Verified by:

3. Signature of the incharge of the environmental laboratory:

Name: Ghyasu Designation: Manager (Admin) Date: 05.07.2019

END OF THE REPORT



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org

Surface Water Treatment Plant

Ground Water Quality Reports



IBAL ECO I

Formerly : Global Environmental Lab (GEL)

GEL TP-ULF-O 15-12-17

CHEMICAL ANALYSIS TEST REPORT

07.07.2019 Dated

Кероп	reference No:	GEL/IN	lemai/07-19/	V-2			
Name o	of Customer:	Lahore	Water & San	itation Authority			
Address	S:	31 - B, Zahoor Elahi Road, Block B Gulberg II,					
		Lahore-	Pakistan.				
Project	Name:	Lahore	Water & Was	stewater Project			
Nature	of Sample:	Ground	Water Tube	Well Mid Point (Der	ra Mian Yousaf)		
Date of	sample Received	02 07 2	019				
Sample	Condition:	Satisfac					
Data of	completion of analysis:	07 07 2	010	Sec. 1	SPARS.		
Date of	completion of analysis.	07.01.2	013				4 I, 2
Sr. No.	Parameters	and the second s	Unit	PEQS	Concentration	Method	Remarks
1	Arsenic	۰. ۲	mg/l	<u><</u> 0.05	0.028	AAS	s. 1, 11 -
2	Cadmium		mg/l	0.00	BDL	AAS	
3	Chloride*		mg/l	<250	55.0	Digital Titrator	
4	Iron 🧭	-00	mg/l	0.3	BDL	AAS	·
5	Manganese		mg/l	<u>≤1.5</u>	0.052	AAS	
6	Mercury	1 8	mg/l	≤0.001	BDL	AAS	ć
7	pH Value*	÷		6.5 to 8.5	7.50	pH meter	2.5
8	Nitrite	i la	mg/l	≤0.3	0.031	HACH Method 8507	
9	Oil & Grease		mg/l	NS	BDL	Extraction	
10	Phenolic Compounds	1	mg/l	0.002	BDL	HACH Method 8047	
11	Selenium		mg/l	0.01	BDL	AAS	," i X - "
12	Sulphate		mg/l	NS	60.0	HACH Method 8035	
13	Chromium		mg/l	≤0.05	BDL	AAS	2 4.7 P
14	Colour		cu	≤15	0.0	HACH Method 8025	age -
15	Taste	199	<u> </u>	Not Objectionable	Not Objectionable	Taste Pannel	
16	Total Dissolved Solids		mg/l	<1000	384.0	Evaporation	
17	Turbidity		NTU	<5	0.04	Turbidity meter	
18	Total Coliforms	- Strain	MPN/ 100ml	0	0	Culture	n - Ali

Deviation from standard method if any: PEQS:Punjab Environmental Quality Standards.

BDL: Below detectable limit. *Selected parameters for ISO-17025 scope.

AAS: Atomic Absorption Spectrophotometer

Analyst

e.

1. Report Prepared by:

2. Checked/Verified by:

3. Signature of incharge of the environmental la

M.Asi Name: Ghyasuudin Designation: Manager (Admin) Date: 07.07.2019 END OF THE REPORT



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org, Website: www.gel-intl.org



GLOBAL ECO L

Formerly : Global Environmental Lab (GEL)

GEL-TP-08-F-001 date: 15-12-17 PAGE 1 OF 1

Dated: 07.07.2019

CHEMICAL ANALYSIS TEST REPORT

B	
Report reference No:	GEL/Internal/07-19/W-1
Name of Customer:	Lahore Water & Sanitation Authority
Address:	31 - B, Zahoor Elahi Road, Block B Gulberg II,
	Lahore-Pakistan.
Project Name:	Lahore Water & Wastewater Project
Nature of Sample:	Ground Water Tube Well (Dera Haji Akram, 1 Km Away
	From Ranger Area)
Date of sample Received:	01.07.2019
Sample Condition:	Satisfactory
Date of completion of analysis:	07.07.2019

Sr. No.	Parameters	Unit	PEQS	Concentration	Method	Remarks
1	Arsenic	mg/l	<u>≤</u> 0.05	0.035	AAS 🕢	
2	Cadmium	mg/l	0.00	BDL	AAS	
3	Chloride*	mg/l	<250	64.0	Digital Titrator	
4	Iron	mg/l	0.3	BDL	AAS	
5	Manganese	mg/l	≤1.5	0.049	AAS	
6	Mercury	mg/l	≤0.001	BDL	AAS	
7	pH Value*		6.5 to 8.5	7.42	pH meter	- 10
8	Nitrite	mg/l	≤0.3	0.022	HACH Method 8507	
9	Oil & Grease	mg/l	NS	BDL	Extraction	
10	Phenolic Compounds	mg/l	0.002	BDL	HACH Method 8047	
11	Selenium	mg/l	0.01	BDL	AAS	
12	Sulphate	mg/l	NS	74.0	HACH Method 8035	
13	Chromium	mg/l	≤0.05	BDL	AAS	i -
14	Colour	cu	≤15	0.0	HACH Method 8025	- 1 ⁴⁶
15	Taste		Not Objectionable	Not Objectionable	Taste Pannel	±
16	Total Dissolved Solids	mg/l	<1000	481.0	Evaporation	
17	Turbidity	NTU	<5	0.08	Turbidity meter	
18	Total Coliforms	MPN/ 100ml	0	0	Culture	

Deviation from standard method if any:

PEQS:Punjab Environmental Quality Standards.

BDL: Below detectable limit. *Selected parameters for ISO-17025 scope.

AAS: Atomic Absorption Spectrophotometer

Sardar Dalyst

1. Report Prepared by:

- 2. Checked/Verified by:
- 3. Signature of incharge of the environme

M.Asi Cinie Ghyasi Name Designation: Manager (Admin) Date 07.07.2019 END OF THE REPORT



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org



Formerly : Global Environmental Lab (GEL)

E 15-12-17

CHEMICAL ANALYSIS TEST REPORT

Report	reference No:	GEL/Internal/06-19/	W-4		Dated:	07.07.2019
Name	of Customer:	Lahore Water & Sa	nitation Authority	-	<u>=</u>	
Addres	S:	31 - B, Zahoor Elah	i Road, Block B Gul	berg II,		
		Lahore-Pakistan.				
Project	Name:	Lahore Water & Wa	stewater Project			
Nature	of Sample:	Ground Water Tube	Well (Dera mian In	nran Hafeez		
		Boundary Lind Back	side of Cold Store)			
Date of	sample Received:	30.06.2019				
Sample	Condition	Satisfactory		C7****		
Date of	completion of analysis:	07 07 2019		9		
	,			1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		
Sr.	Parameters	Unit	PEOS	Concentration	Method	Remarks
No.		0	1245	concentration	method	Remarks
Ι.						
<u> </u>	Arsenic	mg/l		0.027	AAS 🦽	
<u>,</u>	Cadmium				1.1.5	
	Cadinadin	mg/i	0.00	BDL	AAS	
3	Chloride*	mall	<250	37.0	Digital Titrator	
			-250	52.0		
4	Iron	mg/l	0.3	BDL	AAS	
				17		
5	Manganese	mg/l	≤1.5	0.041	AAS	
				47	10-10-21	
6	Mercury	mg/l	≤0.001	BDL	AAS	
-				100 L		
/	pH Value*		6.5 to 8.5	7.51	pH meter	
•	Nitrite		(0.3	0.070	HACH Method 8507	
- 0	hidite	Ing/I	20.5	0.020		
9	Oil & Grease	me/l	NS	BDI	Extraction	
			110		Extraction	
10	Phenolic Compounds	mg/l	0.002	BDL	HACH Method 8047	
				11/2-		
11	Selenium	mg/l	0.01	BDL	AAS	
	5 M.				HACH Method 8035	
12	Sulphate	mg/l	NS	52.0	The first fi	
	a		10.05		1.0	
13	Chromium	mg/I	≤0.05	BDL	AAS	
14	Colour		C15	0.0	HACH Method 8025	
14	Cubur		512	0.0		
15	Taste		Not Objectionable	Not Objectionable	Taste Pannel	
	none -				Tuste Funici	
16	Total Dissolved Solids	mg/l	<1000	348.0	Evaporation	
17	Turbidity	NTU	<5	0.03	Turbidity meter	
		MPN/100ml	0	0	Culture	
18	Total Coliforms	WENT TOOM		~ ~	culture	
eviation f	rom standard method if any	: Nil				

Deviation from standard method if any:

PEQS:Punjab Environmental Quality Standards. BDL: Below detectable limit. *Selected parameters for ISO-17025 scope.

AAS: Atomic Absorption Spectrophotometer

1195 A

oratory

Name Designation:

Date:

END OF THE REPORT

M.

С

1. Report Prepared by:

2. Checked/Verified by:

3. Signature of incharge of the environmental la



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

Ghyasu

Manager (Admin)

07.07.2019

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org



OBAL ECO LA

Formerly : Global Environmental Lab (GEL)

GEL-TP-08 F-001 Issue date: 15-12-17 PAGE 1 OF 1

07.07.2019

Dated:

CHEMICAL ANALYSIS TEST REPORT

Report reference No:	GEL/Internal/06-19/W-2
Name of Customer:	Lahore Water & Sanitation Authority
Address:	31 - B, Zahoor Elahi Road, Block B Gulberg II,
	Lahore-Pakistan.
Project Name:	Lahore Water & Wastewater Project
Nature of Sample:	Ground Water Tube Well (Main Road Near Graveyard/
•	Cold Store Mosque)
Date of sample Received:	29.06.2019
Sample Condition:	Satisfactory
Date of completion of analysis:	07.07.2019

Sr. No.	Parameters	Unit	PEQS	Concentration	Method	Remarks
1	Arsenic	mg/l	≤0.05	0.024	AAS 🧑	-
2	Cadmium	mg/l	0.00	BDL	AAS	
3	Chloride*	mg/l	<250	38.0	V. Digital Titrator	
4	iron	mg/l	0.3	BDL	AAS	
5 🗧	Manganese	mg/l	≤1.5	0.058	AAS	
6	Mercury	mg/l	≤0.001	BDL	AAS	
7	pH Value*		6.5 to 8.5	7.50	pH meter	
8	Nitrite	mg/l	≤0.3	0.024	HACH Method 8507	
9	Oil & Grease	mg/l	NS	BDL	Extraction	
10	Phenolic Compounds	mg/l	0.002	BDL	HACH Method 8047	
11	Selenium	mg/l	0.01	BDL	AAS	
12	Sulphate	mg/l	NS	54.0	HACH Method 8035	
13	Chromium	mg/l	≤0.05	BDL	AAS	
14	Colour	сц	≤15	0.0	HACH Method 8025	
15	Taste		Not Objectionable	Not Objectionable	Taste Pannel	
16	Total Dissolved Solids	mg/l	<1000	349.0	Evaporation	
17	Turbidity	NTU	<5	0.05	Turbidity meter	
10	Total Coliforms	MPN/ 100ml	0	0	Culture	

Deviation from standard method if any:

Nil

C

PEQS:Punjab Environmental Quality Standards.

BDL: Below detectable limit. *Selected parameters for ISO-17025 scope.

AAS: Atomic Absorption Spectrophotometer

1. Report Prepared by:

2. Checked/Verified by:

3. Signature of incharge of the environmental lab

tor Ghyasud Name Designation: Manager (Admin) 07.07.2019 Date END OF THE REPORT

Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org



Formerly : Global Environmental Lab (GEL)

GEL-TP-08-F-00 15-12-11 E 1 OF 1

CHEMICAL ANALYSIS TEST REPORT

Report	elerence No.	Dated: 07.07.2019				
Name o	f Customer:			ý.		
Address	5	31 - B, Zahoor Elahi	Road, Block B Gul	berg II,		
		Lahore-Pakistan.				
Project I	Name:	Lahore Water & Was	stewater Project			
Nature of	of Sample:	Ground Water Tube	Well (Bajwa Farm)			
Date of	sample Received:	29.06.2019				
Sample	Condition:	Satisfactory	100 F 20			
Date of	completion of analysis:	07.07.2019	1	and a start of the		
Sr. No.	Parameters	Unit	PEQS	Concentration	Method	Remarks
1	Arsenic	mg/l	<u></u> ≤0.05	0.028	AAS	
2	Cadmium	mg/l	0.00	BDL	AAS	
3	Chloride*	mg/l	<250	42.0	Digital Titrator	
4	Iron	mg/l	0.3	BDL	AAS	
5	Manganese	mg/l	≤1.5	0.051	AAS	
6	Mercury	mg/l	≤0.001	BDL	AAS	
7	pH Value*		6.5 to 8.5	7.54	pH meter	
8	Nitrite	mg/l	≤0.3	0.018	HACH Method 8507	
9	Oil & Grease	mg/l	NS	BDL	Extraction	
10	Phenolic Compounds	mg/l	0.002	BDL	HACH Method 8047	· · · · ·
11	Selenium	mg/l	0.01	BDL	AAS	
12	Sulphate	mg/l	NS	52.0	HACH Method 8035	$\frac{1}{N} = r$
13	Chromium	mg/l	≤0.05	BDL	AAS	生き
14	Colour	cu	≤15	0.0	HACH Method 8025	
15	Taste		Not Objectionable	Not Objectionable	Taste Pannel	2 ⁽¹ .) r
16	Total Dissolved Solids	mg/l	<1000	342.0	Evaporation	
17	Turbidity	NTU 🚽	<5	0.04	Turbidity meter	
18	Total Coliforms	MPN/ 100ml	0	0	Culture	

Deviation from standard method if any:

PEQS:Punjab Environmental Quality Standards.

BDL: Below detectable limit. *Selected parameters for ISO-17025 scope.

AAS: Atomic Absorption Spectrophotometer

637 Al Analys

1. Report Prepared by:

2, Checked/Verified by:

3. Signature of Incharge of the environmental lab

M.ASIT Name Ghvas Designation: Manager (Admin) Date 07.07.2019 END OF THE REPORT



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org

Surface Water Treatment Plant

Surface Water Quality Reports



Formerly : Global Environmental Lab (GEL)

GEL-TP-08-F-001 Luque # 01 e: 15-12-17 PAGE 1 OF 1

07.07.2019

Date:

CHEMICAL ANALYSIS TEST REPORT

Report reference No:	GEL/Internal/06-19/W-3
Name of Customer:	Lahore Water & Sanitation Authority
Address:	31 - B, Zahoor Elahi Road, Block B Gulberg II,
	Lahore-Pakistan.
Project Name:	Lahore Water & Wastewater Project
Nature of sample:	Surface Water (From Where Link Canal to be Extracted
	From BRB Canal)
Sample Condition:	Satisfactory
Date of sample received:	29.06.2019
Date of completion of analysis:	07.07.2019

S.No.	Parameters.	Unit	PEQS	Concentrations	Method	Remarks
1	pH Value*		6-9	7.66	pH Meter	
2	Total Dissolved Solids	mg/l	3500	102.0	Evaporation	
3	Total Suspended Solids	mg/l	200	80.0	Filtration	
4	BOD₅	mg/l	80	5.0	BOD Trak	
5	Zinc	mg/l	5.0	0.058	Atomic Absorption	
6	Lead	mg/l	0.5	BDL	Atomic Absorption	
7	Nitrite	mg/l		0.032	Spectrophotometer	

Deviation from standard method if any: Nil PEQS: Punjab Environmental Quality Standards

*These parameters are included in the scope of ISO 17025.

3. Signature of the incharge of environmental laboratory:

BDL: Below detectable limit. This report is not valid for any negotiation Analyst

2. Checked/Verified by:

1. Report Prepared by:

C

Name:

Designation:

Ghyasuddin

Manager (Admin) 07.07.2019

Date: END OF THE REPORT



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan.

PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org

Surface Water Treatment Plant

Soil Analysis Report



Formerly : Global Environmental Lab (GEL)

Dox # GEL / LAB / 4/ 15 here # 61 1 61 -64-12 PAGE 1 OF 1

SOIL ANALYSIS TEST REPORT

Report reference No:	GEL/Internal/07-19/Soil-2	Dated: 07.07.2019
Name of customer:	Lahore Water & Sanitation Authority	
Address:	31 - B, Zahoor Elahi Road, Block B Gulberg II,	
	Lahore-Pakistan.	
Project Name:	Lahore Water & Wastewater Project	
Nature of sample:	Soil Sample Mid Point Dera Mian Yousaf	
Date of sampling:	02.07.2019	
Date of completion of analysis:	07.07.2019	

S.No.	Parameters	Units	NEQS	Concentration	Remarks
1	pН		NS	7.71	rionarito
2	Sulphate	mg/kg	NS	72	
3	Sulphide	mg/kg	NS	1.1	
4	Chloride	mg/kg	NS	82	- al
5	Fluoride	mg/kg	NS	BDL	S
6	Sodium	mg/kg	NS	141	1
7	Potassium	mg/kg	NS	6.9	
8	Calcium	mg/kg	NS	238.0	
9	Magnesium	mg/kg	NS	42	
10	Iron	mg/kg	NS	0.031	
11	Barium	mg/kg	NS	2.2	
12	Zinc	mg/kg	NS	9.6	

This report is not valid for any negotiation.

NS: Not Specfied. BDL: Below detectable limit.

1 Sample analyzed by:

A

Designation:

Date:

ratory: Name:

3 Signature of incharge of the environmental lab

2 Ckecked/Verified by:

Ghyasuddin

Manager (Admin) 07.07.2019

END OF THE REPORT



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org



Formerly : Global Environmental Lab (GEL)

GEL/LAB/4/18 kaus # 01 Date : 01 -04-12 PAGE 1 OF 1

SOIL ANALYSIS TEST REPORT

07.07.2019 Dated:

Address: Project Name:

Nature of sample:

Report reference No:

Name of customer:

GEL/Internal/07-19/Soil-1 Lahore Water & Sanitation Authority 31 - B, Zahoor Elahi Road, Block B Gulberg II Lahore-Pakistan. Lahore Water & Wastewater Project Soil Sample 1 Km Away From Ranger Area 400 M Down Eight, Dera Haji Akram 01.07.2019 07.07.2019

Date of sampling: Date of completion of analysis:

S.No.	Parameters	Units	NEQS	Concentration	Remarks
1	pH		NS	7.86	
2	Sulphate	ma/ka	NS	80	
3	Sulphide	mg/kg	NS	1.5	A.H.
4	Chloride	mg/kg	NS	93	1
5	Fluoride	mg/kg	NS	BDL	
6	Sodium	mg/kg	NS	148	
7	Potassium	mg/kg	NS	7.5	
8	Calcium	mg/kg	NS	304.0	
9	Magnesium	mg/kg	NS	65	
10	Iron	mg/kg	NS	0.032	
11	Barium	mg/kg	NS	2.8	
12	Zinc	mg/kg	NS	11.2	

This report is not valid for any negotiation. NS: Not Specfied.

BDL: Below detectable limit.

1 Sample analyzed by:

2 Ckecked/Verified by: 3 Signature of incharge of the environmental laboratory: Ghyasuddin Name: Designation: Manager (Admin) Date: 07.07.2019

END OF THE REPORT



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org



JBAL ECO LA

Formerly : Global Environmental Lab (GEL)

Doe .# GEL/LAB/4/18 Haue # 03 aue Date : 01 -04-12 PAGE 1 OF 1

SOIL ANALYSIS TEST REPORT

07.07.2019 Dated:

Address: Project Name:

Nature of sample:

Date of sampling:

Date of completion of analysis:

Report reference No:

Name of customer:

GEL/Internal/06-19/Soil-3 Lahore Water & Sanitation Authority 31 - B, Zahoor Elahi Road, Block B Gulberg II Lahore-Pakistan Lahore Water & Wastewater Project Soil Sample Boundary Line Behind Cold Storage Dera Imran Hafeez 30.06.2019 07.07.2019

C No	Baramotore	Units	NEQS	Concentration	Remarks
5.NO.	Farameters	Onto	NS	7.91	di la
1	рН		110	86	
2	Sulphate	mg/kg	NS	60	
3	Sulphide	mg/kg	NS	1.9	6-1983
4	Chloride	ma/ka	NS	102	2 6. Ø
4	Shieride	malka	NS	BDL	÷
5	Fluonde	mg/kg	NS	156	
6	Sodium	mg/kg	110	9.2	
7	Potassium	mg/kg	NS	0.2	
8	Calcium	mg/kg	NS	310.0	
	Magnosium	ma/ka	NS	72	
9	Magnesium	iligitig	NS	0.41	
10	Iron	mg/kg	110	2.2	
11	Barium	mg/kg	NS	3.2	
12	Zinc	mg/kg	NS	14.7	

This report is not valid for any negotiation.

NS: Not Specfied.

BDL: Below detectable limit.

1 Sample analyzed by:

Analyst

Name: Designation:

Date:

2 Ckecked/Verified by:

Ghyasuddin Manager (Admin)

07.07.2019

3 Signature of incharge of the environ ental laboratory:

END OF THE REPORT



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org



Formerly : Global Environmental Lab (GEL)

Doc .# GEL/LAB/4/18 issue # 01 ue Date : 01 -04-12 PAGE 1 OF 1

SOIL ANALYSIS TEST REPORT

Report reference No:	GEL/Internal/06-19/Soil-2			Dated:	07.07.2019
Name of customer:	Lahore Water & Sanitation Authority				
Address:	31 - B, Zahoor Elahi Road, Block B Gulberg II				
	Lahore-Pakistan.	. and			
Project Name:	Lahore Water & Wastewater Project	1			
Nature of sample:	Soil Sample Near Graveyard	and I			
Date of sampling:	29.06.2019		and the		
Date of completion of analysis:	07.07.2019				

S.No.	Parameters	Units	NEQS	Concentration	Remarks
1	pН		NS	7.67	
2	Sulphate	mg/kg	NS	78	
3	Sulphide	mg/kg	NS	1.2	
4	Chloride	mg/kg	NS	68	
5	Fluoride	mg/kg	NS	BDL	
6	Sodium	mg/kg	NS	143	
7	Potassium	mg/kg	NS	5.5	
8	Calcium	mg/kg	NS	238.0	
9	Magnesium	mg/kg	NS	62	
10	Iron	mg/kg	NS	0.29	
11	Barium	mg/kg	NS	1.8	
12	Zinc	mg/kg	NS	9.5	

This report is not valid for any negotiation.

NS: Not Specfied.

BDL: Below detectable limit.

1 Sample analyzed by:

2 Ckecked/Verified by: nental lab 3 Signature of incharge of the e ratory Name: Ghyast Designation: Manager (Admin) Date: 07.07.2019

END OF THE REPORT



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org



Formerly : Global Environmental Lab (GEL)

Doe # GEL/LAB/4/38 houe#03 houe Dote:01-04-12 PAGE 1 OF 1

07.07.2019

Dated:

SOIL ANALYSIS TEST REPORT

Report reference No: Name of customer: Address:

Project Name: Nature of sample: GEL/Internal/06-19/Soil-1 Lahore Water & Sanitation Authority 31 - B, Zahoor Elahi Road, Block B Gulberg II, Lahore-Pakistan. Lahore Water & Wastewater Project Soil sample From Where Link Canal to Extracted From BRB Canal 29.06.2019 sis: 07.07.2019

Date of sampling: Date of completion of analysis:

S.No.	Parameters	Units	NEQS	Concentration	Remarks
1	pН		NS	7.84	
2	Sulphate	mg/kg	NS	82	
3	Sulphide	mg/kg	NS	1.5	
4	Chloride	mg/kg	NS	72	- <u>_</u>
5	Fluoride	mg/kg	NS	BDL	10
6	Sodium	mg/kg	NS	138	
7	Potassium	mg/kg	NS	7.2	
8	Calcium	mg/kg	NS	246.0	
9	Magnesium	mg/kg	NS	58	
10	Iron	mg/kg	NS	0.32	
11	Barium	mg/kg	NS	2.5	
12	Zinc	mg/kg	NS	11.8	

This report is not valid for any negotiation.

NS: Not Specfied.

BDL: Below detectable limit.

Analyst

2 Ckecked/Verified by:

1 Sample analyzed by:

3 Signature of incharge of the environmental laboratory:

END OF THE REPORT

Name Ghyasuddin

Designation: Manager (Admin Date: 07.07.2019



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-Intl.org

Annexure - H

PACKAGE 04 - LAB REPORTS

Water Distribution Area

LAB Reports

Water Distribution Network

Ambient Air Monitoring

Reports



GLOBAL ECO LA Formerly : Global Environmental Lab (GEL)

Doc.# OEL-TP-08-F-003 Issue # 01 Date: 15-12-17 PAGE I OF I

AMBIENT AIR QUALITY MONITORING REPORT

Date: 10.07.2019

Report reference No: Name of Customer: Address:

Date of Completion of Analysis:

Project:

Location: Date of Monitoring: GEL/Internal/07-19/A-3 Lahore Water & Sanitation Authority 31 - B, Zahoor Elahi Road, Block B Gulberg II, Lahore-Pakistan Lahore Water & Wastewater Project Mentioned Below 03.07.2019 10.07.2019

S. NO.	Location	CO (mg/m ³)	O ₃ (ug/m ³)	SO _{2 (} <i>u</i> g/m ³)	NO ₂ (<i>u</i> g/m ³)	Noise (dBA)	PM ₁₀ (<i>u</i> g/m ³)	Remarks
	PEQS	10	130	120	80	75	150	
1	Main Canal Road, Below Ring Road Bridge	5.7	28	20.9	59.2	72.1	102	н с. (н)
2	Dera Gujran Orange Train Station	2.3	26	7.8	46.8	73.5	74	
3	Drogewala Chowk	6.9	24	26.1	76.7	82.3	128	
4	Fateh Garh	4.6	31	13.1	58.0	68.4	91	
Deviati	n from standard method if any:	Nil			<u>,</u> -			

Deviation from standard method if any:

PEQS: Punjab Environmental Quality Standards. BDL: Below detectable limit.

This report is not valid for any negotia

2. Checked/Verified by:

1. Report Prepared by:

Signature of the incharge of the environmental laboratory:

Ghya Manager (Admin) 10.07.2019

END OF THE REPORT

Name:

Date:

Designation:



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org



GLOBAL ECO LAB Formerly : Global Environmental Lab (GEL)

GELTP-44-F-403 lame # 01 - 15-17-17 PAGEIOFI

Date: 10.07.2019

AMBIENT AIR QUALITY MONITORING REPORT

Report reference No: Name of Customer: Address:

Date of Monitoring:

Date of Completion of Analysis:

Project:

Location:

GEL/Internal/07-19/A-4 Lahore Water & Sanitation Authority 31 - B, Zahoor Elahi Road, Block B Gulberg II Lahore-Pakistan Lahore Water & Wastewater Project Mentioned Below 04.07.2019 10.07.2019

S. NO.	Location	CO (mg/m ³)	O ₃ (ug/m ³)	SO _{2 (} ug/m ³)	NO ₂ (<i>u</i> g/m ³)	Noise (dBA)	PM ₁₀ (<i>u</i> g/m ³)	Remarks
	PEQS	10	130	120	80	75	150	
1	Near Dry Port, Railway Phatak, Shoib Autos Mughalpura	3.4	19	18.3	54.5	78.2	88	с. Т
2	Nawan Pull	2.3	22	13.1	52.2	60.3	105	
3	Sukh Nehr	2.3	17	10.4	50.4	68.6	92	
4	Baghbanpura Orange Station	2.3	24	15.6	66.5	78.3	123	
Deviatio	on from standard method if any:	Nil						

Deviation from standard method if any:

PEQS: Punjab Environmental Quality Standards. BDL: Below detectable limit.

This report is not valid for any negotia

1. Report Prepared by:

2. Checked/Verified by:

Signature of the incharge of the environmental laboratory:

Ghyas Manager (Admin) 10.07.2019

END OF THE REPORT

Name:

Date:

Designation:



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org



Formerly : Global Environmental Lab (GEL)

Doc.# OEL-TP-08-F-003 Issue # 01 Date: 15-12-17 PAGE | OF I

Date: 10.07.2019

AMBIENT AIR QUALITY MONITORING REPORT

Report reference No: Name of Customer: Address:

Project: Location: Date of Monitoring: Date of Completion of Analysis:

GEL/Internal/07-19/A-5 Lahore Water & Sanitation Authority 31 - B, Zahoor Elahi Road, Block B Gulberg II, Lahore-Pakistan. Lahore Water & Wastewater Project Mentioned Below 05.07.2019 10.07.2019

S. NO.	Location	CO (mg/m ³)	O ₃ (ug/m ³)	SO _{2 (} ug/m³)	NO₂ (<i>u</i> g/m³)	Noise (dBA)	PM ₁₀ (<i>u</i> g/m ³)	Remarks
	PEQS	10	130	120	80	75	150	
1	Cantt Drain Ittehad Park	1.1	30	18.3	60.4	61.1	67	
2	Mustafaabad Allama Iqbal Road, Dharampura	3.4	21	23.5	53.8	72.3	83	
3	National Museum of Science & Technology, UET	2.3	26	13.1	54.5	74.2	119	
4	Wagha Town, Near Ring Road,	1.1	18	7.8	58.3	62.5	82	
Deviatio	on from standard method if any:	Nil			2 1 2 2 4 00			

any PEQS: Punjab Environmental Quality Standards.

BDL: Below detectable limit.

This report is not valid for any negotiation

1. Report Prepared by:

2. Checked/Verified by:

3. Signature of the incharge of the environmental laboratory: Name: Designation:

Ghya Manager (Admin) Date: 10.07.2019

END OF THE REPORT



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org



GLOBAL ECO LAB Formerly : Global Environmental Lab (GEL)

Doc.# GEL-TP-08-F-003 Issue # 01 Issue Date: 15-12-17 PAGE 1 OF 1

Date: 15.07.2019

AMBIENT AIR QUALITY MONITORING REPORT

Report reference No: Name of Customer: Address:

Project: Location: Date of Monitoring: Date of Completion of Analysis: GEL/Internal/07-19/A-7 Lahore Water & Sanitation Authority 31 - B, Zahoor Elahi Road, Block B Gulberg II, Lahore-Pakistan. Lahore Water & Wastewater Project Mentioned Below 07.07.2019 15.07.2019

S. NO.	Location	CO (mg/m ³)	O ₃ (ug/m ³)	SO _{2 (} <i>u</i> g/m ³)	NO ₂ (<i>u</i> g/m ³)	Noise (dBA)	PM ₁₀ (<i>u</i> g/m ³)	Remarks
	PEQS	10	130	120	80	75	150	
1	Lakhodair, Near Ring Road	2.3	21	7.8	54.5	65.6	82	
2	Bassi Morr Gol Chakkar, Yasin Hospital Ring Road Toll Plaza	2.3	24	20.9	60.8	70.2	102	
3	Mominpura Road Near Hardware Store	3.4	19	15.7	54.5	73.8	79	
4	Karol Ghati, Ring Road	6.9	26	31.3	42.6	66.1	101	
Deviatio	on from standard method if any:	Nil		-	1. 1. 1. 1. 1.			

Deviation from standard method if any: PEQS: Punjab Environmental Quality Standards. BDL: Below detectable limit. This report is not valid for any negotiation.

G

Analyst

1. Report Prepared by:

2. Checked/Verified by:

3. Signature of the incharge of the environmental laboratory:

Ghya Manager (Admin) 15.07.2019

END OF THE REPORT

Name:

Date:

Designation:



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org



GLOBAL ECO LAB Formerly : Global Environmental Lab (GEL)

Doc.# GEL-TP-08-F-003 Issue # 01 Issue Date: 15-12-17 PAGE I OF I

AMBIENT AIR QUALITY MONITORING REPORT

Date: 15.07.2019

Report reference No: Name of Customer: Address:

Date of Monitoring:

Date of Completion of Analysis:

Project: Location: GEL/Internal/07-19/A-8 Lahore Water & Sanitation Authority 31 - B, Zahoor Elahi Road, Block B Gulberg II, Lahore-Pakistan. Lahore Water & Wastewater Project Mentioned Below 08.07.2019 15.07.2019

S. NO.	Location	CO (mg/m ³)	O ₃ (ug/m ³)	SO₂ (u g/m³)	NO ₂ (<i>u</i> g/m ³)	Noise (dBA)	PM ₁₀ (<i>u</i> g/m ³)	Remarks
	PEQS	10	130	120	80	75	150	
1	Atif Park Boghewal Chowk	3.4	26	10.4	62.4	66.1	93	
2	Shahalu Chowk	9.1	27	15.7	70.5	76.4	107	
3	Ghoray Shah Road, Govt Boys Compary School, Kot Khawaja Road	2.3	19	20.9	68.2	73.6	76	
4	Siraj Road, Near Sultan Pura Road	2.3	17	7.8	54.0	71.2	130	
Deviation from standard method if any:		Nil			100			

Deviation from standard method if any: PEQS: Punjab Environmental Quality Standards.

BDL: Below detectable limit.

This report is not valid for any negotiat

1. Report Prepared by:

Checked/Verified by:

3. Signature of the incharge of the environmental laboratory:

Ghyasu Manager (Admin) 15.07.2019

END OF THE REPORT

Name: Designation:

Date:



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org





Formerly : Global Environmental Lab (GEL)

Doc.# GEL-TP-08-F-003 Issue # 01 Issue Date: 15-12-17 PAGE 1 OF 1

AMBIENT AIR QUALITY MONITORING REPORT

GEL/Internal/07-19/A-9

Lahore-Pakistan.

Mentioned Below

09.07.2019

15.07.2019

Lahore Water & Sanitation Authority

Lahore Water & Wastewater Project

31 - B, Zahoor Elahi Road, Block B Gulberg II

Date: 15.07.2019

Report reference No: Name of Customer: Address:

Project: Location: Date of Monitoring: Date of Completion of Analysis:

S. NO.	Location	CO (mg/m ³)	O ₃ (ug/m ³)	SO _{2 (} ug/m³)	NO₂ (<i>u</i> g/m³)	Noise (dBA)	PM ₁₀ (<i>u</i> g/m ³)	Remarks
	PEQS	10	130	120	80	75	150	
1	Orange Train Station # 6, Before UET	4.6	21	10.4	57.4	74.3	105	
2	Shalimar Link Road Near Mosque	9.1	26	23.5	47.5	75.7	136	
3	Railway Workshop Colony Nabipura	1.1	22	5.2	·50.1	55.4	64	
4	Takiya Yateem Shah, WASA Tubewell	2.3	24	7.8	62.4	63.2	79	
Deviat	and former advectional and the state							

Sardar

T)

ABalyst

Deviation from standard method if any: PEQS: Punjab Environmental Quality Standards. BDL: Below detectable limit.

This report is not valid for any negotiation

1. Report Prepared by:

2. Checked/Verified by:

3. Signature of the incharge of the environmental laboratory:

Name: Ghyasudd Designation: Manager (Admin) 15.07.2019 Date:

END OF THE REPORT

Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org


GLOBAL ECO LAB

Formerly : Global Environmental Lab (GEL)

Dess # GEL_TP-04LF-6473 (annue # 0) (annue Date: 15-12-17 PAGE 1 C# 1

AMBIENT AIR QUALITY MONITORING REPORT

Date: 15.07.2019

Report reference No: Name of Customer: Address:

Date of Monitoring:

Date of Completion of Analysis:

Project: Location: GEL/Internal/07-19/A-10 Lahore Water & Sanitation Authority 31 - B, Zahoor Elahi Road, Block B Gulberg II, Lahore-Pakistan. Lahore Water & Wastewater Project Mentioned Below 10.07.2019 15.07.2019

S. NO.	Location	CO (mg/m³)	O ₃ (ug/m ³)	SO _{2 (} ug/m³)	NO ₂ (<i>u</i> g/m ³)	Noise (dBA)	PM ₁₀ (<i>u</i> g/m³)	Remarks
	PEQS	10	130	120	80	75	150	
1	Abdullah Chowk Salamat Pura	4.6	<mark>1</mark> 8	18.3	60.8	72.6	102	
2	Gulshan-e-Haider Colony, Opposite to Young Scholar School, Backroad of Orange Train	1.1	21	13.1	52.4	58.4	81	
3	Rangwala Karkhana, Backside of Zahra Shafi Hospital	5.7	20	18.3	62.6	72.2	105	2 2
4	Masjid Khoo Jattan	4.6	16	15.7	50.3	69.8	97	
Deviati	on from standard mathod if any:	Nil						

Deviation from standard method if any: PEQS: Punjab Environmental Quality Standards.

BDL: Below detectable limit. This report is not valid for any negotiation

2. Checked/Verified by:

1. Report Prepared by:

Con alyst

3. Signature of the incharge of the environmental laboratory:

Ghyasu

Manager (Admin

15.07.2019

Name: _____ Designation: ____ Date:

END OF THE REPORT



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org



GLOBAL ECO LA

Formerly : Global Environmental Lab (GEL)

Doc.# GEL-TP-08-F-003 innue # 01 le: 15-12-17 PAGE 1 OF 1

AMBIENT AIR QUALITY MONITORING REPORT

Date: 18.07.2019

Report reference No: Name of Customer: Address:

GEL/Internal/07-19/A-11 Lahore Water & Sanitation Authority 31 - B, Zahoor Elahi Road, Block B Gulberg II Lahore-Pakistan. Lahore Water & Wastewater Project Mentioned Below 11.07.2019

Project: Location: Date of Monitoring: Date of Completion of Analysis:

S. NO.	Location	CO (mg/m ³)	O ₃ (ug/m ³)	SO _{2 (} ug/m³)	NO₂ (<i>u</i> g/m³)	Noise (dBA)	PM ₁₀ (<i>u</i> g/m ³)	Remarks
	PEQS	10	130	120	80	75	> 150	
1	Bhaini Road Droghewala, Near English Grammer School/Afzal Marriage Hall	6.9	18	10.4	68.5	70.6	92	
2	Ring Road Zahra Peer/Bhaini Road, Factory Road	5.7	23	31.3	46.2	70.2	89	
3	MA Cold Storage Ring Road	2.3	20	18.3	48.1	72.5	81	
4	Boghiwal Road Near Latif Marriage Hall	4.4	18	15.7	60.8	71.4	84	
Deviati	on from standard method if any:	Nil	all a fell	10 1800	C Wart I B			

PEQS: Punjab Environmental Quality Standards. BDL: Below detectable limit. This report is not valid for any negotiation

18.07.2019

1. Report Prepared by:

2. Checked/Verified by:

3. Signature of the incharge of the environmental laboratory:

Ghyasi Manager (Admin)

18.07.2019

END OF THE REPORT

Name: Designation:

Date:



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org



GLUBAL ECO L

Formerly : Global Environmental Lab (GEL)

Doc # GEL-TP-08-F-003 Issue # 01 ue Date: 15-12-17 PAGE I OF I

AMBIENT AIR QUALITY MONITORING REPORT

Date: 18.07.2019

Report reference No: Name of Customer: Address:

Project:

GEL/Internal/07-19/A-12 Lahore Water & Sanitation Authority 31 - B, Zahoor Elahi Road, Block B Gulberg II, Lahore-Pakistan. Lahore Water & Wastewater Project Mentioned Below 12.07.2019 18.07.2019

Location: Date of Monitoring: Date of Completion of Analysis:

S. NO.	Location	CO (mg/m ³)	O ₃ (ug/m ³)	SO _{2 (} ug/m³)	NO ₂ (<i>u</i> g/m ³)	Noise (dBA)	PM ₁₀ (<i>u</i> g/m ³)	Remarks
	PEQS	10	130	120	80	75	150	
1	Mian Mir Road, Sikander Road	2.3	24	18.3	56.4	68.2	82	
2	Harbanspura Road Jalal Colony	3.4	20	23.5	70.9	71.8	121	
3	Ring Road, Service Road	2.3	20	10. <mark>4</mark>	58	64.9	87	*
Deviati	on from standard method if any:	Nil			1.	2		

Deviation from standard method if any:

PEQS: Punjab Environmental Quality Standards. BDL: Below detectable limit.

This report is not valid for any negotiation

1. Report Prepared by:

2. Checked/Verified by:

3. Signature of the incharge of the environmental laboratory:

Name: Ghyasud Manager (Admin) Designation: Date: 18.07.2019

END OF THE REPORT



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org Package - 04

Water Distribution Network

Ground Water Quality Reports



Address:

Sr.

No

OBAL ECO LA

Formerly : Global Environmental Lab (GEL)

#: 15-12-17

CHEMICAL ANALYSIS TEST REPORT

Dated: 15.07.2019

Remarks

GEL/Internal/07-19/W-14 Report reference No: Name of Customer: Lahore Water & Sanitation Authority 31 - B, Zahoor Elahi Road, Block B Gulberg II, Lahore-Pakistan Lahore Water & Wastewater Project Project Name: Nature of Sample: Ground Water Tube Well (Wagah Town, Near Ring Road) Date of sample Received: 10.07.2019 Sample Condition: Satisfactory Date of completion of analysis: 15.07.2019 Parameters Unit PEQS Concentration Method 0.042 mg/l <0.05 Arsenie

2	Cadmium	mg/l	0.00	BDL	AAS 🦰
3	Chloride*	mg/l	<250	38.0	Digital Titrator
4	Iron	mg/l	0.3	BDL	AAS 🤭
5	Manganese	mg/l	\$1.5	0.064	AAS
6	Mercury	mg/l	≤0.001	BDL	AAS COL
7	pH Value*		6.5 to 8.5	7.10	pH meter
8	Nitrite	mg/l	≤0.3	0.024	HACH Method 8507
9	Oil & Grease	mg/l	NS	BDL	Extraction
10	Phenolic Compounds	mg/l	0.002	BDL	HACH Method 8047
11	Selenium	mg/l	0.01	BDL	AAS
12	Sulphate	mg/l	NS	38.0	HACH Method 8035
13	Chromium	mg/l	≤0.05	BDL	AAS
14	Colour	cu	≤15	0.0	HACH Method 8025
15	Taste		Not Objectionable	Not Objectionable	Taste Pannel
16	Total Dissolved Solids	mg/l	<1000	362.0	Evaporation
17	Turbidity	NTU	ও	0.02	Turbidity meter
10	Total Coliforms	MPN/100ml	0	0	Culture

Deviation from standard method if any: Nil

PEQS:Punjab Environmental Quality Standards.

BDL: Below detectable limit *Selected parameters for ISO-17025 scope.

AAS: Atomic Absorption Spectrophotometer

dar

1. Report Prepared by:

- 2. Checked/Verified by:
- 3. Signature of incharge of the environme

Col.: Ghyas Name Manager (Admin) 15.07.2019 Designation: Date END OF THE REPORT



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org



Address:

GLOBAL ECO LAB

Formerly : Global Environmental Lab (GEL)

Doc.# GEL-TP-08-F-00 Issue # 01 date: 15-12-17 PAGE 1 OF 1

Dated: 15.07.2019

CHEMICAL ANALYSIS TEST REPORT

Report reference No: GEL/Internal/07-19/W-13 Name of Customer: Lahore Water & Sanitation Authority 31 - B, Zahoor Elahi Road, Block B Gulberg II Lahore-Pakistan. Project Name: Lahore Water & Wastewater Project Nature of Sample: Ground Water Tube Well (Shah Gohar, Eid Gah Mehmood Boti) Date of sample Received: 09.07.2019 Sample Condition: Satisfactory 15.07.2019 Date of completion of analysis:

Sr. No.	Parameters	Unit	PEQS	Concentration	Method	Remarks
1	Arsenic	mg/l	≤0.05	0.029	AAS	
2	Cadmium	mg/l	0.00	BDL	AAS 🥖	
3	Chloride*	mg/l	<250	38.0	Digital Titrator	
4	Iron 📕	mg/l	0.3	BDL	AAS	
5	Manganese	mg/l	≤1.5	0.034	AAS	
6	Mercury	mg/l	≤0.001	BDL	AAS	
7	pH Value*		6.5 to 8.5	7.54	pH meter	
8	Nitrite	mg/l	≤0.3	0.022	HACH Method 8507	
9	Oil & Grease	mg/l	NS	BDL	Extraction	
10	Phenolic Compounds	mg/l	0.002	BDL	HACH Method 8047	
11	Selenium	mg/l	0.01	BDL	AAS	
12	Sulphate	mg/l	NS	45.0	HACH Method 8035	
13	Chromium	mg/l	≤0.05	BDL	AAS	en de la c
14	Colour	cu	≤15	0.0	HACH Method 8025	
15	Taste		Not Objectionable	Not Objectionable	Taste Pannel	
16	Total Dissolved Solids	mg/l	<1000	386.0	Evaporation	
17	Turbidity	NTU	<5	0.03	Turbidity meter	
18	Total Coliforms	MPN/100ml	0	0	Culture	

Deviation from standard method if any: Nil

PEQS:Punjab Environmental Quality Standards.

BDL: Below detectable limit. *Selected parameters for ISO-17025 scope.

AAS: Atomic Absorption Spectrophotometer

Sardar 1997 AT alyst

С

1. Report Prepared by:

2. Checked/Verified by:

3. Signature of Incharge of the environm



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org

Name

Date

Designation:

END OF THE REPORT

Ghyasu

Manager (Admin)

15.07.2019



Report reference No:

GLOBAL ECO L

Formerly : Global Environmental Lab (GEL)

2-08-F-001 te: 15-12-17

CHEMICAL ANALYSIS TEST REPORT

Report I	reference No:	GEL/Int	ernal/07-19/M	/-12		Dated: 15 07 2019		
Name o	f Customer:	Lahore	Water & Sani	tation Authority		-	10.01.2010	
Address	S:	31 - B, 2	Zahoor Elahi I	Road, Block B Gulb	erg II,			
		Lahore-	Pakistan.					
Project	Name:	Lahore	Water & Was	tewater Project				
Nature of	of Sample:	Ground	Water Tube \)				
Date of	sample Received:	09.07.2	019			,		
Sample	Condition:	Satisfac	tory	and second				
Date of	completion of analysis:	15.07.2	019	10.00	1 seal			
Sr.				and the second sec	in strenge			
No.	Parameters		Unit	PEQS	Concentration	Method	Remarks	
	57	-			7.58			
1	Arsenic		mg/l	≤0.05	0.038	AAS		
	· · · · · · · · · · · · · · · · · · ·				1	*		
2	Cadmium		mg/l	0.00	BDL	AAS 🥢		
3	Chloride*		mg/l	<250	25.0	Digital Titrator		
			iiig/i	~230	23.0			
4	Iron 🤐 🥐		mg/l	0.3	BDL	AAS		
	100					45		
5	Manganese	2.1	mg/l	≤1.5	0.025	AAS		
	Marauny	1		CO 001		445		
	wercury		mg/i	20.001	BDL	AAS		
7	pH Value*			6.5 to 8.5	7.60	pH meter		
					1	HACH Mathed 9507		
8	Nitrite		mg/l	≤0.3 <mark>.</mark>	0.019	HACH Methou 8507		
						Future at lan		
<u>-</u>	Oll & Grease		mg/1	NS	BDL	Extraction		
10	Phenolic Compounds		mg/l	0.002	BDL	HACH Method 8047		
				227				
11	Selenium	8 2 3	mg/l	0.01	BDL	AAS		
						HACH Method 8035		
12	Sulphate		mg/I	NS	31.0			
12	Chromium		mg/l	<0.05	BDL	AAS		
- 15	Chromium		1116/1			un all and all another	Epster	
14	Colour		cu	≤15	0.0	HACH Method 8025	10	
		1.143	-					
15	Taste	1.1		Not Objectionable	Not Objectionable	Taste Pannel		
			mall	<1000	275.0	Evaporation		
16	Total Dissolved Solids		ing/	-1000	27510			
17	Turbidity		NTU	<5	0.02	Turbidity meter		
			MPNI / 100-1	0	0	Culture		
18	Total Coliforms		WPN/ 100mi	0	NY CATCOL			
Desident's	from standard method if a	nv:	Nil					

Deviation from standard method if any:

PEQS:Punjab Environmental Quality Standards.

BDL: Below detectable limit.

*Selected parameters for ISO-17025 scope. AAS: Atomic Absorption Spectrophotometer

1. Report Prepared by:

2. Checked/Verified by:





Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org



Bonort reference No:

GLOBAL ECO LAB

Formerly : Global Environmental Lab (GEL)

Doc.# GEL-TP-08-F-001 e date: 15-12-17 PAGE 1 OF 1

CHEMICAL ANALYSIS TEST REPORT

GEL /latoraal/07 10/0/ 11

15.07.2019 Dated

i topoit i	cicicitoc no.	OLD INCOMMENT TO/T										
Name of	f Customer:	Lahore Water & San	itation Authority									
Address	:	31 - B, Zahoor Elahi	Road, Block B Gult	berg II,								
		Lahore-Pakistan.										
Project I	Name:	Lahore Water & Was	stewater Project									
Nature c	of Sample	Ground Water Tube	Well (Dilawar Roa	d Misri Shah)								
Date of	sample Received	08.07.2019	8.07.2019									
Comple	Condition:	Satisfactory	atisfactory									
Data of	Condition.	15 07 2010		and a								
Date of t	completion of analysis.	15.07.2019										
Sr. No.	Parameters	Unit	PEQS	Concentration	Method	Remarks						
1	Arsenic	mg/l	<u>≤</u> 0.05	0.038	AAS							
2	Cadmium	mg/l	0.00	BDL	AAS							
3	Chloride*	mg/l	<250	82.0	Digital Titrator							
4	Iron 🦰	mg/l	0.3	BDL	AAS							
5	Manganese	mg/l	≤1.5	0.042	AAS							
6	Mercury	mg/l	≤0.001	BDL	AAS							
7	pH Value*		6.5 to 8.5	7.78	pH meter							
8	Nitrite	mg/l	≤0.3	0.023	HACH Method 8507							
9	Oil & Grease	mg/l	NS	BDL	Extraction							
10	Phenolic Compounds	mg/l	0.002	BDL	HACH Method 8047							
11	Selenium	mg/l	0.01	BDL	AAS							
12	Sulphate	mg/l	NS	100.0	HACH Method 8035							
13	Chromium	mg/l	≤0.05	BDL	AAS	1.1						
14	Colour	cu	≤15	0.0	HACH Method 8025	.K.						
15	Taste		Not Objectionable	Not Objectionable	Taste Pannel							
16	Total Dissolved Solids	mg/l	<1000	504.0	Evaporation							
17	Turbidity	NTU	<5	0.07	Turbidity meter							
		MPN/100ml	0	0	Culture							

Deviation from standard method if any:

PEQS:Punjab Environmental Quality Standards.

BDL: Below detectable limit. *Selected parameters for ISO-17025 scope.

AAS: Atomic Absorption Spectrophotometer

dar Analyst

Ch

1. Report Prepared by:

Checked/Verified by:

3. Signature of incharge of the enviro



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

Ghyasu

Manager (Admin) 15.07.2019

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org

Name

Designation: Date END OF THE REPORT



GLOBAL ECO LA

Formerly : Global Environmental Lab (GEL)

GEL-TP-08-F-00 date: 15-12-17 PAGE 1 OF 1

CHEMICAL ANALYSIS TEST REPORT

Dated: 15.07.2019

Remarks

Report reference No:		GEL/Interna	al/07-19/V								
Name of	f Customer:	Lahore Wa	ter & Sani	itation Authority							
Address	:	31 - B, Zah	oor Elahi	Road, Block B Gulb	erg II,						
		Lahore-Pak	kistan.								
Project Name: Nature of Sample: Date of sample Received:		Lahore Wa	ter & Was								
		Ground Wa	Ground Water Tube Well (Nadia Ghee Mill Tohid Park)								
		08.07.2019									
Sample	Condition:	Satisfactor	/								
Date of o	completion of analysis:	15.07.2019			der the						
Sr. No.	Parameters	L, a	Unit	PEQS	Concentration		Metho				
1	Arsenic	n *	mg/l	≤0.05	0.031	AAS					
,	Cadmium			0.00	RDI						

2	Cadmium	mg/l	0.00	BDL	AAS 🧀
3	Chloride*	mg/l	<250	78.0	Digital Titrator
4	Iron	mg/l	0.3	BDL	AAS
5	Manganese	mg/l	≤1.5	0.038	AAS
6	Mercury	mg/l	≤0.001	BDL	AAS
7	pH Value*		6.5 to 8.5	7.64	pH meter
8	Nitrite	mg/l	≤0.3	0.018	HACH Method 8507
9	Oil & Grease	mg/l	NS	BDL	Extraction
10	Phenolic Compounds	mg/i	0.002	BDL	HACH Method 8047
11	Selenium	mg/l	0.01	BDL	AAS
12	Sulphate	mg/l	NS	90.0	HACH Method 8035
13	Chromlum	mg/l	≤0.05	BDL	AAS
14	Colour	cu	≤15	0.0	HACH Method 8025
15	Taste		Not Objectionable	Not Objectionable	Taste Pannel
16	Total Dissolved Solids	mg/l	<1000	468.0	Evaporation
17	Turbidity	NTU	<5	0.04	Turbidity meter
18	Total Coliforms	MPN/ 100ml	0	0	Culture

Ahsan/Sardar

Name

Designation: Date

END OF THE REPORT

Analyst

M.Asif

Chie

Deviation from standard method if any:

PEQS:Punjab Environmental Quality Standards.

BDL: Below detectable limit. *Selected parameters for ISO-17025 scope.

AAS: Atomic Absorption Spectrophotometer

1. Report Prepared by:

- 2. Checked/Verified by:
- 3. Signature of incharge of the environme

Ni



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

Ghyasuddin

Manager (Admin)

15.07.2019

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org



GLOBAL ECO LA К

Formerly : Global Environmental Lab (GEL)

Doc.# GEL-TP-08-F-001 Issue # 01 date: 15-12-17 PAGE 1 OF 1

CHEMICAL ANALYSIS TEST REPORT

Report r Name of Address	eference No: f Customer: :	GEL/Int Lahore 31 - B.2	ernal/07-19/W Water & Sani Zahoor Elahi I	/-9 tation Authority Road, Block B Gu	lberg II.	Dated:	10.07.2019
Project I Nature c	Name: of Sample:	Lahore Lahore Ground	Pakistan. Water & Was Water Tube	tewater Project Well (Faisal Child	iren Park Mughalpura	a)	
Date of a Sample Date of a	sample Received: Condition: completion of analysis:	06.07.2 Satisfac 10.07.2	019 ctory 019		<u></u>		
Sr. No.	Parameters		Unit	PEQS	Concentration	Method	Remarks
1	Arsenic	7	mg/l	≤0.05	0.046	AAS	
2	Cadmium		mg/l	0.00	BDL	aas 🦽	4
3	Chloride*		mg/l	<250	78.0	Digital Titrator	
4	Iron		mg/l	0.3	BDL	AAS	
5	Manganese		mg/l	≤1.5	0.052	AAS 🖉	
6	Mercury		mg/l	≤0.001	BDL	AAS	
7	pH Value*			6.5 to 8.5	7.40	pH meter	
8	Nitrite		mg/l	≤0.3	0.022	HACH Method 8507	
9	Oil & Grease		mg/l	NS	BDL	Extraction	
10	Phenolic Compounds	-	mg/l	0.002	BDL	HACH Method 8047	
11	Selenium	2	mg/l	0.01	BDL	AAS	
12	Sulphate	1	mg/l	NS	95.0	HACH Method 8035	
13	Chromium		mg/l	≤0.05	BDL	AAS	5.00
14	Colour			415		HACH Method 8025	100

Total Coliforms 18 Deviation from standard method if any: Ni

PEQS:Punjab Environmental Quality Standards.

Total Dissolved Solids

BDL: Below detectable limit.

Turbidity

14

15

16

17

Colou

Taste

*Selected parameters for ISO-17025 scope. AAS: Atomic Absorption Spectrophotometer

20 82

Name

Date

Designation

END OF THE REPORT

≤15

Not Objectionable

<1000

<5

0

mg/l

NTU

MPN/ 100m

0.0

Not Objectionable

492.0

0.04

0

aste Panne

Evaporation

Culture

Ghyasudel

Manager (Admin)

10.07.2019

Turbidity meter

1. Report Prepared by:

2. Checked/Verified by:

3. Signature of incharge of the environ



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org



Sr.

GLOBAL ECO LA

Formerly : Global Environmental Lab (GEL)

Dec.# GEL-TP-08-F-001 lasue # 01 lasue date: 13-12-17 PAGE 1 OF 1

CHEMICAL ANALYSIS TEST REPORT

10.07.2019 Dated:

Sr. No.	Parameters		Unit	PEQS	Concentration	I		
Date of c	ompletion of analysis:	10.07.2	019		1			
Sample	Condition:	Satisfactory						
Date of s	ample Received:	06.07.2019						
Nature o	f Sample:	Ground Water Tube Well (Salamatpura Bari Janazgah)						
Project N	lame:	Lahore Water & Wastewater Project						
		Lahore	Lahore-Pakistan.					
Address		31 - B,	ulberg II,					
Name of	Customer:	Lahore						
Report re	eference No:	GEL/Int						

No.	Farameters	Unit	PEQS	Concentration	Method	Remarks
1	Arsenic	mg/l	≤0.05	0.037	AAS	
2	Cadmium	mg/l	0.00	BDL	aas 🥜	
3	Chioride*	mg/l	<250	84.0	Digital Titrator	
4	Iron	mg/l	0.3	BDL	AAS	
5	Manganese	mg/l	≤1.5	0.061	AAS	
6	Mercury	mg/l	≤0.001	BDL	AAS	
7	pH Value*		6.5 to 8.5	7.49	pH meter	
8	Nitrite	mg/l	≤0.3	0.025	HACH Method 8507	
9	Oil & Grease	mg/l	NS	BDL	Extraction	
10	Phenolic Compounds	mg/l	0.002	BDL	HACH Method 8047	
11	Selenium	mg/l	0.01	BDL	AAS	
12	Sulphate	mg/l	NS	110.0	HACH Method 8035	
13	Chromium	mg/l	≤0.05	BDL	AAS	and .
14	Colour	cu	s15	0.0	HACH Method 8025	20
15	Taste		Not Objectionable	Not Objectionable	Taste Pannel	
16	Total Dissolved Solids	mg/l	<1000	534.0	Evaporation	
17	Turbidity	NTU	<5	0.08	Turbidity meter	
18	Total Coliforms	MPN/100ml	0	0	Culture	
eviation	from standard method if any:	NII				

Deviation from standard method if any:

PEQS:Punjab Environmental Quality Standards.

BDL: Below detectable limit. *Selected parameters for ISO-17025 scope.

AAS: Atomic Absorption Spectrophotometer

san Zardar Analyst

- 1. Report Prepared by:
- 2. Checked/Verified by:

M.A.S e 3. Signature of Incharge of the environmental labor Name Ghyasuddin Designation: Manager (Admin) Date 10.07.2019 END OF THE REPORT



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org



GLOBAL ECO LAB

Formerly : Global Environmental Lab (GEL)

-12-1 1 OF

CHEMICAL ANALYSIS TEST REPORT

Report	reference No:	GEL/Ir	nternal/07-19/	W-7		Dated	: 10.07.2019
Name of Customer:		Lahore Water & Sanitation Authority					
Address:		31 - B, Zahoor Elahi Road, Block B Gulberg II,					
		Lahore	-Pakistan.				
Project	Name:	Lahore	Water & Wa	stewater Project			
Nature	of Sample:	Ground	d Water WAS	A Tube Well (Tak	ia Yateem Shah)		
Date of	sample Received:	05.07.2	2019		/		
Sample	Condition:	Satisfa	ictory				
Date of	completion of analysis:	10.07.2	2019		1 m		
Sr. No.	Parameters		Unit	PEQS	Concentration	Method	Remarks
1	Arsenic		mg/l	<u>≤0.05</u>	0.042	AAS	
2	Cadmium		mg/l	0.00	BDL	AAS 🥜	
3	Chloride*		mg/l	<250	92.0	Digital Titrator	
4	Iron		mg/l	0.3	BDL	AAS	
5	Manganese		mg/l	≤1.5	0.041	AAS	
6	Mercury		mg/l	≤0.001	BDL	AAS	
7	pH Value*			6.5 to 8.5	7.55	pH meter	
8	Nitrite		mg/l	≤0.3	0.021	HACH Method 8507	
9	Oil & Grease		mg/l	NS	BDL	Extraction	r.
10	Phenolic Compounds		mg/l	0.002	BDL	HACH Method 8047	
11	Selenium		mg/l	0.01	BDL	AAS	
12	Sulphate		mg/l	NS	105.0	HACH Method 8035	1
13	Chromium		mg/l	≤0.05	BDL	AAS	1997
14	Colour		cu	≤15	0.0	HACH Method 8025	₽.
15	Taste			Not Objectionable	Not Objectionable	Taste Pannel	
16	Total Dissolved Solids		mg/l	<1000	518.0	Evaporation	
17	Turbidity		NTU	<5	0.05	Turbidity meter	
18	Total Coliforms		MPN/ 100ml	0	0	Culture	

PEQS:Punjab Environmental Quality Standards.

BDL: Below detectable limit. *Selected parameters for ISO-17025 scope.

AAS: Atomic Absorption Spectrophotometer

A 11 Analyst

1. Report Prepared by:

2. Checked/Verified by: 3. Signature of incharge of the environm Name Ghyasu Designation: Manager (Admin) Date 10.07.2019 END OF THE REPORT



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org



GLOBAL ECO LAB

Formerly : Global Environmental Lab (GEL)

GEL-TP-08-F-001 ue date: 15-12-17 PAGE 1 OF 1

CHEMICAL ANALYSIS TEST REPORT

7.2019

Report reference No: <u>GE</u>		GEL/Int	EL/Internal/07-19/W-6			Dated:	10.07.201	
Name of	f Customer:	Lahore	Water & San	itation Authority		-	20 A	
Address	:	31 - B, 2	Zahoor Elahi	Road, Block B Gu	berg II,			
		Lahore-	Pakistan.					
Project I	Name:	Lahore	Water & Was	stewater Project				
Nature c	of Sample:	Ground	Water Tube	Well (Infantry Roa	d)			
Date of a	sample Received:	05.07.2	019					
Sample	Condition:	Satisfac	tory					
Date of o	completion of analysis:	10.07.2	019					
Sr. No.	Parameters		Unit	PEQS	Concentration	Method	Remarks	
1			mg/l	≤0.05	0.042	AAS		
2	Cadmium		mg/l	0.00	BDL	AAS 🦯		
3	Chloride*		mg/l	<250	72.0	Digital Titrator		
4	Iron		mg/l	0.3	BDL	AAS		
5	Manganese		mg/l	≤1.5	0.057	AAS 🛩		
6	Mercury		mg/l	≤0.001	BDL	AAS		
7	pH Value*			6.5 to 8.5	7.75	pH meter		
8	Nitrite		mg/i	≤0.3	0.026	HACH Method 8507		
9	Oil & Grease		mg/l	NS	BDL	Extraction		
10	Phenolic Compounds		mg/l	0.002	BDL	HACH Method 8047		
11	Selenium	·	mg/l	0.01	BDL	AAS		
12	Sulphate		mg/l	NS	80.0	HACH Method 8035		

<0.05

≤15

Not Objectionable

<1000

<5

0

mg/l

cu

mg/l

AAS

HACH Method 8025

Taste Pannel

Evaporation

Culture

Turbidity meter

BDL

0.0

Not Objectionable

445.0

0.06

0

Turbidity 17 NTU MPN/ 100m Total Coliforms 18 Nil

Deviation from standard method if any: PEQS:Punjab Environmental Quality Standards.

Total Dissolved Solids

BDL: Below detectable limit.

Chromium

Colour

Taste

13

14

15

16

*Selected parameters for ISO-17025 scope.

AAS: Atomic Absorption Spectrophotometer

1. Report Prepared by:

2. Checked/Verified by:

3. Signature of incharge of the environm

Cł Name: Ghyasuddin Designation: Manager (Admin) Date 10.07.2019 END OF THE REPORT



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org

Package - 04

Water Distribution Network

Surface Water Quality

Reports



GLOBAL ECO LA

Formerly : Global Environmental Lab (GEL)

GEL-TP-08-F-00 Lusue # 0) date: 15-12-17 PAGE 1 OF 1

Date: 10.07.2019

CHEMICAL ANALYSIS TEST REPORT

Report reference No:	GEL/Internal/07-19/W-4		
Name of Customer:	Lahore Water & Sanitation Authority		
Address:	31 - B, Zahoor Elahi Road, Block B Gulberg II,		
	Lahore-Pakistan.		
Project Name:	Lahore Water & Wastewater Project		
Nature of sample: Surface Water (Mustafaabad Allama Igbal Road Dharampura			
	Lahore Canal)		
Sample Condition:	Satisfactory		
Date of sample received:	03.07.2019		
Date of completion of analysis:	10.07.2019		

S.No.	Parameters.	Unit	PEQS	Concentrations	Method	Remarks
1	pH Value*	<u>.</u>	6-9	7.88	pH Meter	
2	Total Dissolved Solids	mg/l	3500	114.0	Evaporation	
3	Total Suspended Solids	mg/l	200	374.0	Filtration	
4	BOD₅	mg/l	80	6.0	BOD Trak	11 - K
5	Zinc	mg/l	5.0	0.064	Atomic Absorption	
6	Lead	mg/l	0.5	BDL	Atomic Absorption	
7	Nitrite	mg/l		0.036	Spectrophotometer	

Deviation from standard method if any: Nil PEQS: Punjab Environmental Quality Standards

*These parameters are included in the scope of ISO 17025. BDL: Below detectable limit. This report is not valid for any negotiation

1. Report Prepared by:

Sardar ALLIVS

2. Checked/Verified by:

3. Signature of the incharge of environmental aboratory:





Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org



HOBAL ECO LA

Formerly : Global Environmental Lab (GEL)

GEL-TP-08-F-00 15-12-17 PAGE 1 OF 1

10.07.2019

Date:

CHEMICAL ANALYSIS TEST REPORT

Report reference No:	GEL/Internal/07-19/W-3	
Name of Customer:	Lahore Water & Sanitation Authority	
Address:	31 - B, Zahoor Elahi Road, Block B Gulberg II,	
	Lahore-Pakistan.	
Project Name:	Lahore Water & Wastewater Project	
Nature of sample:	Surface Water (Near Ring Road, Main Canal Road)	
Sample Condition:	Satisfactory	- Alle
Date of sample received:	03.07.2019	She
Date of completion of analysis:	10.07.2019	Sere S

S.No.	Parameters.	Unit	PEQS	Concentrations	Method	Remarks
1	pH Value*		6-9	7.81	pH Meter	
2	Total Dissolved Solids	mg/l	3500	103.0	Evaporation	
3	Total Suspended Solids	mg/l	200	142.0	Filtration	
4	BOD₅	mg/l	80	4.0	BOD Trak	
5	Zinc	mg/l	5.0	0.092	Atomic Absorption	
6	Lead	mg/l	0.5	BDL	Atomic Absorption	
7	Nitrite	mg/l		0.028	Spectrophotometer	

Deviation from standard method if any: Nil

PEQS: Punjab Environmental Quality Standards *These parameters are included in the scope of ISO 17025.

BDL: Below detectable limit. This report is not valid for any negotiation

1. Report Prepared by:

Analyst

2. Checked/Verified by:

Chi alvet

Name: Designation:

Date: END OF THE REPORT

Ghyasuddin

Manager (Admin) 10.07.2019

3. Signature of the incharge of environmental laboratory:



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org

Package - 04

Water Distribution Network

Waste Water/ Drain Water Quality Reports



GLOBAL ECO LA

Formerly : Global Environmental Lab (GEL)

GEL-TP-08-F-00 le: 15-12-17 PAGE 1 OF 1

Date: 10.07.2019

CHEMICAL ANALYSIS TEST REPORT

Report reference No:	GEL/Internal/07-19/W-5		
Name of Customer:	Lahore Water & Sanitation Authority		
Address:	31 - B, Zahoor Elahi Road, Block B Gulberg II,		
	Lahore-Pakistan.		
Project Name:	Lahore Water & Wastewater Project		
Nature of sample:	Drain Water (Cantt. Drain)		
Sample Condition:	Satisfactory		
Date of sample received:	04.07.2019		
Date of completion of analysis:	10.07.2019		

S.No. Parameters. Unit Remarks PEQS Concentrations Method 1 pH Value* 6-9 7.26 pH Meter 886.0 Total Dissolved Solids 2 3500 mg/l Evaporation 3 374.0 Total Suspended Solids mg/l 200 Filtration 4 228.0 BOD₅ 80 mg/l BOD Trak 5 Zinc mg/l 5.0 0.160 Atomic Absorption 6 Lead mg/l 0.5 0.05 Atomic Absorption Nitrite mg/l 0.510 7 Spectrophotometer

Deviation from standard method if any: Nil

PEQS: Punjab Environmental Quality Standards

*These parameters are included in the scope of ISO 17025 BDL: Below detectable limit. This report is not valid for any negotiation

1. Report Prepared by:

2. Checked/Verified by:

3. Signature of the incharge of environmental laboratory:





Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org

Package - 04

Water Distribution Network

Soil Quality Reports



Report reference No:

GLOBAL ECO LAB

Formerly : Global Environmental Lab (GEL)

Doc J GEL/LAB/4/18 Insue J 01 Insue Date : 01 -04-12 PAGE 1 OF 1

SOIL ANALYSIS TEST REPORT

Dated: 18.07.2019

 Name of customer:
 Lahore Water & Sanitation Authority

 Address:
 31 - B, Zahoor Elahi Road, Block B Gulberg II, Lahore-Pakistan.

 Project Name:
 Lahore Water & Wastewater Project

 Nature of sample:
 Soil Sample Wagh Town, Near Ring Road

 Date of sampling:
 12.07.2019

 Date of completion of analysis:
 18.07.2019

S.No.	Parameters	Units	NEQS	Concentration	Remarks
1	pH		NS	7.91	
2	Sulphate	mg/kg	NS	76	
3	Sulphide	mg/kg	NS	2.3	
4	Chloride	mg/kg	NS	74	10
5	Fluoride	mg/kg	NS	BDL	
6	Sodium	mg/kg	NS	154	
7	Potassium	mg/kg	NS	9.3	
8	Calcium	mg/kg	NS	257.0	
9	Magnesium	mg/kg	NS	61	
10	Iron	mg/kg	NS	0.034	
11	Barium	mg/kg	NS	2.2	
12	Zinc	mg/kg	NS	13.7	

This report is not valid for any negotiation.

NS: Not Specfied.

BDL: Below detectable limit.

1 Sample analyzed by:

2 Ckecked/Verified by:

GEL/Internal/07-19/Soil-4

3 Signature of incharge of the environmental laboratory:

Name: Ghya Manager (Admin) Designation: Date: 18.07.2019

END OF THE REPORT



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org



GLOBAL ECO LAB Formerly : Global Environmental Lab (GEL)

Doc .# GEL / LAB / 4 / 18 Issue # 01 Issue Date : 01 - 04-12 PAGE 1 OF 1

SOIL ANALYSIS TEST REPORT

Dated: 18.07.2019

 Report reference No:
 GEL/Internal/07-19/Soil-3

 Name of customer:
 Lahore Water & Sanitation Authority

 Address:
 31 - B, Zahoor Elahi Road, Block B Gulberg II

 Lahore-Pakistan.
 Lahore Water & Wastewater Project

 Nature of sample:
 Soil Sample Near Cant Drain

 Date of sampling:
 12.07.2019

Date of completion of analysis: 18.07.2019 Remarks Parameters Units NEQS Concentration S.No. NS 8.32 1 bΗ 110 2 Sulphate mg/kg NS NS 9.8 3 Sulphide mg/kg 138 NS 4 Chloride mg/kg BDL 5 Fluoride NS mg/kg NS 256 6 Sodium mg/kg NS 15.4 7 Potassium mg/kg 310.0 NS 8 Calcium mg/kg NS 98 9 Magnesium mg/kg NS 0.045 10 Iron mg/kg NS 5.3 11 Barium mg/kg NS 21.8 12 Zinc mg/kg

This report is not valid for any negotiation. NS: Not Specfied.

BDL: Below detectable limit.

1 Sample analyzed by:

2 Ckecked/Verified by:

Analyst

ratory:

3 Signature of incharge of the environmental la

Ghyasuddin Name Designation: Manager (Admin) 18.07.2019 Date:

END OF THE REPORT



Certificate No: 112/DD(Lab)/EPA/05/2017 Certified By "Environmental Protection Department" - Government of the Punjab

2nd and 3rd Floor, 4-5 Commercial Area, Cavalry Ground , Lahore- Cantt, Pakistan. PABX: 0092 42 36670097 till 98. Compliance: 0092 42 36681281. Email: info@gel-intl.org. Website: www.gel-intl.org

Annexure - I

ENVIRONMENTAL MONITORING OF PACKAGE 03



Ambient Air Quality Monitoring





Noise Monitoring





Annexure - J

ENVIRONMENTAL MONITORING OF PACKAGE 04





Ambient Air Quality Monitoring





Ambient Air Quality Monitoring



Ambient Air Quality Monitoring



Ambient Air Quality Monitoring



Ambient Air Quality Monitoring



Noise Monitoring




Surface Water Sampling



Surface Water Sampling

Annexure - J



Surface Water Sampling



Soil Sampling

Annexure - K

PICTORIAL PROFILE OF FLORA AND FAUNA PACKAGE 03 AND 04





















Annexure - L

PICTORIAL PROFILE OF INDUSTRIAL SURVEY OF PACKAGE 03 AND 04

Picture Gallery





Annexure-M

PICTORIAL PROFILE OF PUBLIC CONSULTATION







PICTORIAL PROFILE OF PUBLIC CONSULTATION



PICTORIAL PROFILE OF PUBLIC CONSULTATION



PICTORIAL PROFILE OF PUBLIC CONSULTATION

Annexure-N

PUBLIC CONSULTATION FEEDBACK FORMS

Name	Age	Occupation	Address	Educat	Income	Caste	Family	Feedback	Signature	Contac
				ion		d la	System))
Nagina	23	Teacher	Harbans	BS. Comos	13,000]-	Rehman	Separate	12 all >> : 42 yo 6	th	0305.
Tehnina	. 23	Teacher	Harbans	BS- Comp. Sci	1 S,0001 -	Rehmui	Separate	ر منوبه ر. بد الما بد	2	· \
20 nas	52	Manager	Grean park	under- matric	30,000 .	Shiekh	Joint.	اس مناو بر بد بدى	لوزي نعا	0324
Saima	30	house wife	upper mall,	modric	15,000	madik	Joint.	مرور مكناط يسي .	Que 1	1595
Kallb -e- Abbas	53.	Banker	MBA, almustata Brai	BSC.	25,0001-	Rayport	Joint.	ير المك الجامنهوي	A A A A A A A A A A A A A A A A A A A	62220
Sordeel	37	Juli Cer Shop(Salkimale)	Burhampun	mi ddle	deily	khan	Joint.	یم آپ کے ساق اور تعری آنتہ اور	للرجار	1
Imran	36	Salesman	Mug hulpum,	Matric	(Sipcol-	Raypoot	Joint	うりううえるり	07	egeo.
Atif	28	Sales man	mughter	Matric	23,0001-	khan	Joint	ارچا برو براط مهم.	All	4520
Sakina	ol	howsenife	Shelabert	ы).	30,0001 -	Raypoot	Joint:	بانی کی کو بودا کے سل سالہ مناح سر		
M. Leusar	CE	opticen	Hoperabala	Matric	- 1000105	Peifort	Joint .	مرود لمكنا با يح.		- artes
Ali Haider	23'	Shop teeps	G.T. Pord	MBA	30,0001-	Reipport	Seprede	سلک کے بیٹر یک لیے اب _ع اور لوگوں کی هزور ت کے لیکا	di di di	-950
Noven	10	Jowo wife	Defence	F.A	50,0001-	Butt 9	eparate	اس منعد ہے پر جلدی عل،ک جا نے۔	Noneenbul	44559
murtaza	20	Sules 7	Dargatun	B.A	3 Supple	Syed	Separa	the me be will us to	- Aller	(E

			Socia	l Surv	'ey Fe	edba	ick Fo	:m:		
Name	Age	Occupation	Address	Educat	Income	Caste	Family	Feedback	Signature	Contact #
	2			ion	and a		System	1.1		
Umall	Se Se	Shop	Maphalasa	Mathic	30X	Rainot	Tint	منعوب مكتاجاني	SARO	- Here
Tadial	SS	Cher	Mughel muso	Maluic	354	Sher Kh	Sendele	. Hit : 40 and find -	X	534-568
Hayan Nus	state 52	Cont. Sekuri	t Mughalpura	F.A.	27 X	Gued.	Toint	1 40 6 1 6 1 6 1 6 1	S-HSSAN.	5/12-8020
(humin	35	Shen	Shaliman	Matul	Kox	Sheikh	Sentet	and on you	top	224-426
Verhold. N	X	Rickshow	Gral man	Six	2 CK	Acash	Tont	- ce (6 liz)	11:11	0311=4=2)
Anwar	.on	Shep	Sinchaula	B.S.	XQE	Pethan	Tint	Section Wilso	Sund D	271647
M. Shakel	in	She n	Baghwan Jug	Matric	yox	Lipet.	Tit	2112 2 2 2	dit.	03344177
Tangen Man	an 22	She to	Sirgh outo	Matui	324	Kasindu	Sepurk.	21. 0. 12 - 2	J. J.	27220.
Alian	24.	Shep	Sinahanka	Nates	1SK	whik	Toint	Wer ?	Phen	124 620
Nax II	ion	khan (Sina shull	E.A	20%	Tett	Toint	As in a lel	int.	1982 Barto
Audit	17	(Leo	Praid- P Alan	with .	Yok	Calliet	kon de	Cred Si Culture	1670	olphakaoza
Nasil	se.	Japan	Han by Chook	1		Malik	Leniste	C. / Curidite ,	100	039620
M. La dame	2	Hotel	Hande The of	<i>«</i>	N. N.	Ansei	Songate	24020 7293	مارن	156949371
11										
Alan to M	2		Varian 2 and chat				Shoul -	n		

				Social	Surv	ey Fe	edba	ck Fo	rm:		
	Name	Age	Occupation	Address	Educat	Income	Caste	Family	Feedback	Signature	Contact #
			A R A		ion			System			
	Bashir	44	DRIVER	Allonna Japal Load Dhasanpus	Math	25/000	Asain	Toint	aig in for the	in the second	1
	shahab	44	Emplyee	Dhavan pusa	Mathic	20,000	Sheith	Joint	Soul - relation	À	4811480
	Naseer	23	Employa	Charampusa	F.A.	00/000	lajout	Dint	Ere Meiling (E	Com	0304736
	Shahzad	38	Employe	Dhasampure	Fef	0001/1	Ahain	Dint	(id b) by by here	Shehrd	1320 1483 101
je.	Nhseen Javeid	39	Branch Non.	Dharangues	Matric	40,000	lajout	Separate	Elsinger	M. H	2301414610
	Anjum Shoh geo	5	Eng log	Dharampuse	Matric	15,000	Akain	Khalate	aige in hill of the	Atonal a	03237047
	M. Fahi	(32	Bonter	Deveny we	MBA	25000	Mugha	. birt	JENG! / NO	The	221531
3	Zebrat	34	Employ	Dharang we	Mudale	10/00	0 Pathan	Teint	win (for Direli	7. LAUna	144210 2000
	Umar	28	Business	Chargengeure	Phasmaey	20,000	[ajou]	Seme	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~		2384 4/26/28
	M. Zaha	33	- Employa	mughalpue	Rina	800-1000	Asain	Sement	- 16 x 2 x 3 1 -	Black	0 3047265202
	Qaiser	23	Salesman	Mugalpare	mathi	16000	Agein	Land	cieles preis	D.A	5244 9994 C
	Ahson	20	Designer	Murphal pre	T.Com	15,000	Quesh	lint.	Cher she ch for	The way	1919 65784
1	Komal	7	Teachix	Murthal mue	B.SUDANA	12,000	Mucha	Separa	the delagar	A A O	1401-402
-			C	1 0 (D	1			bu

		18		Socia	l Surv	ey Fe	edba	ack Fc	um:		
	Name	Age	Occupation	Address	Educat	Income	Caste	Family	Feedback	Signature	Contact #
	-	2						System	2		
	Say Jan Ze	30	Laborer	Hande Luija	A/N.	Xal	Gafiel	Toid	رمر کا فیال الما	walt	818
	Abdel Com	35	Zamidan	Canj-Sinhun	AINA	,	Leyout New	Tint	l'que este fé	interes ?	222-550
	Jarna de	52.	Comidal.	Gang - Sind wan	AIN		Reyard	turat	کارو بارغنا از ن	- 0 2 2 2	I
	Acher	·Sh	Shep	Carj-Ched	Matri	25K	Algin	Juint	surgician f	102	0303-95/36
	Brag	'n	Shep	"	Matic		Kaboo	Landa	ille & Aller	A der	2300 4261507
	Sig at 1	38	Sup/Hatel	"	AIN		Jutt	First	aigue in glad	() () () () () () () () () () () () () (0342 7490
	lazan M	1h	Shep	"	AIN		CM port	Energy	-22 [63] [6		0311-810
	N. Seller	22	Shep		NIA		Lainet	Toint.	ましょしょううき	1xh	2602
	(What A)	30.	Shep	4	whethe		Awan	Sint	علاقه لزاك لحي	12020	0347-43
Ch.	With - KAmp	14	Shep	N	NA	-	Ana	Seneral	12 allal col) 39 ') 5/ 45 -		1211-4131
	Kerry W	27.	Gep		Midlle		Awan	Tolat	Elevery C	5000	3-354929
_4	iggat the	20.	Shep		AIN		Cong	South	le circuis l	With	0324-49
4	Achs in Mr	57	Shep		NIA		Awan	Jost	or all see ?	المحسن على	1321- 6011990
	Rizwan 4	-01	gale	1	NIA	18	Awan	Joint	the second secon	1 19014	24-45

Š
Address Educat
ion
-Shalamar Metro
Shalamar B.A
Shalanar Matri
Sholanal -
Speland Moth
Shalomer Middle
Begundese medde
Begun Pusa Natric
Begun Mate Matrie
Cepinluse Riman
Begun Pure Rinsey
Cequiners Middle
Begun Pure Middle

Name	Age	Occupation	Address	Educat	Income	Caste	Family	Feedback	Signature	con
				ion			System			
Amis	ゴカ	Genera	Alique 9 5 bal	1:4	Suk	Abbahi	5	1 S Jugar B	-T-T-O	120
Hefen	39	Salasman	Shelamar	F.A	Sok	Rapad	5	in the second		032.
inter ?	din 50	Tondood	Man. 983 al	Nill	10 K	Shukh	2	Ward Vor	2	SE 38
M. Ume	12 13	1000 pca	Alime 94620 Road	Middle	124	But	H	(0) > (12) / 2) 1	1 Impir	0301
M. Aleem	68	4 th meetimic	11	howing	18/2	But	h	· La Liveland (1961	3/2/13	039
Stely.	10 40	2imidara	Dhorm	E	80 6	Cryint	h	. سين كا محاوضه عمط	attert	0300
Icim to	n 22.	Mo bik 51.0	myhol Para	middle	5'k	khen	h	الجامنعة عصاف باذيع	Pul-	05210
f. ym	3,	R'KHAW	Daloshud	Nill	20K	15 halt	S	181 200 cm & .		1214
m. Aza	M 31	Shopkelo	Shalamer	1.w	15k	Le har	5	مان ، اعلى معارراد		
Jared	189	Come "	Shelm at	/w/	35k	Neu	h	- الأخر أي كر ال	NIG	1189
indra's	Z.	Rehn'	Mond.	m	10-12	Ola ceri	+	الطامنوير في .	, to	0324
ASSA	. 4.	Crort Brild Ca	singh Puza	middle	24K	Raifu	th	الميز بن مفعود م.	And a	4254
In which	60.	Relised	bingh has	M adar'	IOK	- M	F	1. 27.16:21	to int	1334

				Socia	l Surv	ey Fe	edba	CK FG	:uu		,
	Name	Age	Occupation	Address	Educat	Income	Caste	Family	Feedback	Signature	Contact #
					ion			System		0.0	
	Munix	60	Shop herper	Baghan Pure.	matric	15,000	Sheild	Separa	diare the fal	mont	249 arriv
1	Abrd	38	Shogkee	lage ban	Middle	15/000	attan .	but	MELLE CON	ple	0313-4001
	Sydar	24	Eng dage	Collan	Matric	00000	Paiput	Toint .	anon ver in	Ship	03008855233
	Ortan	23	Vendor	Bagiden	1	32,000	Perfort	Fint	2012 12:00		ł
e la la	m-Rigg	23	Hadwar	Church	mathe	10,000	meshi	Bint	aisig in 1/gol in-	Halm	0323-7526
	Abu Rakas	21	Student	Mehsoll	D -5		Tutt	Cearsold	いしていうう	June 1	030 S S000 129
	Folyof	23	Vendor	Chung.	matric	15,000	Parout	(Dint	chilicht 202	1.2.11	0380
	Saltar	HS.	Employer:	Hone Backen	1	13,000	Ul Gui al	Segrat	inger superior		0320-47
	Any yas	ah	Sequency	Agd Guda]		Khar	Pint)[ib & ling & is superior		
	Georget	-Sh	Employee	Pix Madul	Matric	15000	Mughel	Dink	منهورجلين تكنا	Shaft	943777
	Abrel	94	Employe	Janderple		18,000	Arach	Senant	(5'20110 C) 20)	2100	e322
	pureid	Sh	Manafer	Canjor	1	Ì	Meyon	pint	and in your		7848023
	Ary	25	merkanit	Canjay	1	1000	tuet	tint	service and	1	322-43
			5	mball			,	2			26367

		۰. ۱	Social	Surv	'ey Fe	edba	CK To	:w.c		
Name	Age	Occupation	Address	Educat ion	Income	Caste	Family System	Feedback	Signature	Contact #
traport	¹ o	OWNer Pusinen mun	Shebzimandi C. T. I abore	Pri 221e	15-11000.	Raipoot	Separade	يم الجا بردبيك في	9	532-W2
Musaret	38.	bow wife	A 6.T.	matric	20 10001-	Reiptont	Separate	یایی کی کی کو یور اکنے کے اول اچا طریق بے	XIA	02020
Sumera	HH	a tim schould	nabi pura	F.A	15,0001.	Mali k	Joint	اس منصو بے پر جلس ی	8	-2220
								× 1,2,1,2,1,1,1,1,1,1,1,1,1,1,1,1,1,1,1,1	4 c	9 20 27
Wis-Hadi	04	Teacher	Daro genule	Master	-1-0001L	Syed	Bointe	مال)ى بېزى کا اددىكى كەردىكە كى غرورت يودى كى خىكىلە	A)	032240
Alam	23	Soles	Chamen Park, Baawan	£.₽	20,0001-	Reyport	Separate	3/12/2020.20.	1	HOLAN
Syca	·Lh	optican	Cyari - Shalu	Modric 1	B,000-	Sycd	Separate	فرور لكنا بإ سي	A	03039677
Mobers M. Sarfara	35	guard	Shadi pura Bandrog d	Matric	13,0001 -	Rajpoot	Joint .	10 2 2 2 2 2	Safat	0324. 1449
Mehmons	25	Teacher	Bagana	grad-	16,0001.	Mughe	Sep. P	لوگى بومان بانى نرا	i P	100 1000
Har wag	35	Sales	Chugi Stop	F.A	27,0001-	Ansori	Separate	2512 10 20 20 20 10	And ind	100-10 10 C
Nazir	.47	Slupleepe	" Chugi	F.A	1,Lac	Mian	Joint.	فرور بكنا جيا بجي.	a munta	choo wer
Dani U	26	Ow her Businewman	Church stop', Islam Park	I. Com	500,000	Sheikh	Joint	2 12 1- 121	Corp.	323-40448
Pares	\$23	OW NEV BUDINEN MON	Handu	Nil .	22 1000	Rajet	Joints.	اس منھو ہے پر جلد	2 mg	030982031
1			Chauk			•	and the second	على درامد مرمين .		

Name	Age	Occup	Address	Edu	Income	Caste	Family	Feedback	Sign	Contact #
						i,	System			
Rahim Ogd	12	Carlenter	weshe Town	musta	2-01	Parkan	12	aulor Jelle	Ort	0321
Niemat	38	Ge Pada	waghe Town	Nin	10	Pallow.	h	Entrate South		0305
Alenue	27	Entines	Taj Bash	BSE	50	Arain	h	Un for with	Church	2500
Hom PAD.W	2	Notes	Lethedair	Mite	0	Jut	h	putter on Oxy live	M. A.L. M.	1250
Refred	30	Olechristen	Yiab a Abel	Mille	50	tut	h	135 éring (1) 2) 1) 2)	Rese at 11.	0334
Nadeem	38	Farms	Whe darg	Nit	25-30	Twit	F	Flight april 2 mil	Contraction of the second seco	0333
Khelid	49	ka bbar	Bhain	matri	21-01	120341	h	(ez) 2. 2. 2. 2. Re	3	0303 2850 18
							۰ ۲	2	-	1
										8.
							į.			
	1				4	ŢÇ,				
						1. S				
				1		-310				

Annexure-O

PICTORIAL PROFILE OF CONSULTATION WITH GOVERNMENT OFFICIALS AND RESPONSIBLE AUTHORITIES



Consultation with Deputy Secretory (Planning), Punjab Forest Department, Lahore.



Consultation with Director General at Fisheries Department, Lahore



Consultation with Deputy Secretary (Operations) at Punjab Irrigation Department, Lahore Consultation with XEN (operation) at Punjab Irrigation Department, Lahore



Consultation with Director HQ at Punjab Wildlife & Parks Department, Lahore



Consultation with Deputy Director (Planning) at Punjab Industries


Consultation with Director Pakistan Metrological Department



Consultation with Deputy Director Pakistan Geological Survey, Lahore



Consultation with Regional Director Pakistan Council of Research in Water Resources (PCRWR) Lahore



Consultation with Deputy Director Archaeology Department, Lahore

Annexure-P

FEEDBACK FORMS OF CONSULTATION WITH GOVERNMENT OFFICIALS AND RESPONSIBLE AUTHORITIES

	9	overnmen	it/Stakehol	der Consultation/Feedba	ick Form	
	Name	Designation	Address	Feedback	Contact No. & Email	Signature
100	M.N.ADEEM MNJUM	Deputy Director	Creekyred Lurvez 7 Pakistan	The phopophed site doesn't tall, in lugh home activity area sufficient measures should a be adopted in any disisters i would Homs.	333-4350 613 redeemet 1000	. Hered
	Zamin Ahme	Region	Regional A.	averter quality of proposed a differ is not up to Thumark clean drinking vater should be provided to avoid many intertions discass.	0 301 8686 745 ngrsaz C	23
C. and	Muhamad	Deputy Director (South)	Shahi	Pie levere - Aeron and Dioper design and layout noo should be phovided. At the	042-4933 2672	
	Magsood Murad	Deputy Driechor (NDTIR)	Shahi Gula	be at proper distance from all cultural s theritage sites. If all	0221-478 4084	
				Achoeology Dept. howe		

18an66-19a 042-99212379 18521279-240 DC1299240 Signature Contact No. GOVERNMENT STAKEHOLDER CONSULTATION FOR AIB- LWASA PROJECTS referred to Xerlop) (D) Letter for duscosico (D) formal sugrest formal sugrest formal sugrest formal sugrest formal sugrest formal sugrest Ploc 17/44 Require formul letter of introduction of the myest adversed to DG HINHLIP to process (purtain There the regult Feedback Binector SEN(9), 181, gotion DiG Designation 3 ruhammed Nacen Burtoi Punjul W19814 1 mpolin Byt Flisheries Dept. Department 13) Dr. Naman Murhlag Nauman Baug Name 1) Dr. Sikandar

		Gover	nment Official / Stake H	older Consultation Form	
Sr. No	Department	Contact Person	Designation	Feedback	Signature
Ч	PAKISTAN METEORODOGN DEPAKTMENT Reguind Contra	AR AJMARA AR AJMAR	DIRECTOR	CLIMATE VARLES NAY TO DAY MUD LOCATION TO LOCATION. WEATHER PORCASTING IS A TECHNICAL ASPECT PROPER ENVIEDNMENTAL	fue
7				M MUAGENTANT MEASURES SHOUL BE MOOPTED IN ALL PROJECTS	
m					
4					

				With Contrast No.	Signature
		Production 1	Feedback	III ID / C ORIGON / OII	
Name	Department	henginan	and the second second and the second se	schein dig mark com	
Muhammad Tariq Nascem Scanned Cam Sca	with DDer	(Planning)	Dr. Samia Satt. Exoton Expert 1035 66 Social Impact Assessment Expert along with her team visited my office along with her team visited my office. She informed about project titled she informed about project titled she informed about project titled she information system of treatment Plant, transmission mains, feeding mains & distribution system. The Surface Water Treatment Plant her sourtace water treatment Plant her construction of surface water treatment plant, transmission mains, feeding mains & distribution system. It is the dot of surface water treatment plant, transmission mains, feeding mains & distribution system. It is the duty of the construction of surface water treatment plant, transmission mains, feeding mains & distribution system. It is the duty of the consultant Firm to propose steps which will be helpful to save or technhitate original flora. & distribution system. It is the duty of the consultant Firm to propose steps which will be helpful to save or technhitate original flora. & distribution system in the stere ever green many be carried out in where ever green many be declared as Green Area where ever green many by Petkin may be plant. Annual form a step species with maximum follage like Plant. Annual flora is may be declared as Green Area where ever green many be plant.	6660024	The second se

	10			
s				
ASA PROJECI				
ERS CONSULTATION FOR AIIB-LW/	Punjab Forest Department has issued a Notification with the approval of Chief Minister. Punjab regarding deposit of "Replenishment Cost" (Annexure-I). According to the subject Notification. Client Department has to deposit Replenishment Cost equal to Rs.157525/acre for the land which will be used for development project.			
NT STAKEHOLD				
GOVERNME			nned with	nScanner
			Scar	Can

Annexure-Q

PICTORIAL PROFILE OF CONSULTATION WITH EXPERTS



Consultation with Environmental Expert: Dr. Kausar Jamal Cheema



Consultation with Waste Water Expert: Dr. Asim Mahmood



Consultation with Biological Expert: Dr. Aleem Chaudhary



Consultation with Environmental Expert: Dr. Saamia Saif



Consultation with Solid Waste Expert: Dr. Ali Kamran



Consultation with Hydrological Expert: Mr. Waqar Ahmad

Annexure-R

FEEDBACK FORM OF CONSULTATION WITH EXPERTS

1 Participation				
	Signature	M'M	the bound	- damp
Project	Contact Details	0300 8470712 Wychilsent 260	3300-4975506 alikamumyk (ya hosicom	0324-46643
Experts Feedback Form-LWASA	Feedback	The project site is not housed in flooded in flood prononce but sunitable measures should be adopted whe assessment of area should be can	sind waste generated from the site should be managed effectively. Waste generated from site should be disposed off according to TMA guidellines.	I The project will result in positive unpacts if the implementation of EMP is
vironmental]	Designation	Lectimer	Waste Momoya- ment Expert	Frulkohme Expert
En	Name	Muhammad Wulas/an	Dr. Ali Kemnom	DR. Smit
	Sr. No	Ð	20	63
				I. Carlos

Dr. Fariha Tagering papamenene Chlonination is not kooj Wolfer Berund an appropriate due to Wolfer wennene Sprant severe protection expart Sciences in productor terminetia expart sciences in the neuron wenneneer in the sciences of the sprant market and the sciences of the sprant productor and the process productor and the process productor and the process productor and the process proved environe the sprant of the sprant proved environe the sprant of t		Occupation	Address	Feedback	Signature	Number
Kroi Walter & Briver appropriate due to Arabine window, when we are served to the contract of	Dr. Fariha	Teaching.	Department	Chlorinadou is not		
expert version of productor formation. I shalp. Expert version so that should for the share of the should be the state of the shore of	(Javo)	W Sler	& Environ-	appropriale due to	otton	
Image: Structure of the		Expert-	ventral Scherce.	by productro formation.	1 25/38/49	
Important Important Important		1	was, lawat	so you showed for disnertion.	1 1 1	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
Vergrunden en fan en		0		oltrinoe project o		
Hue resident of the resident o				very unportand. For		
Meast membrance Relinelogy shoued Relinelogy shou			and the second	the residency of more !		
rection the transmission of transmission of the transmission of tr				Alleast weakprice		
le une for the préfication de une for the préfication de une and defailed innertiqué and defailed innertiqué and the conducted provent the conducted provent de conducted provent	and the second se			telhuelogy showed		
Puritication & varie and deteried innergiation de BDP canal water avairs must be conducted the cleek the adervary by Numtr be conducted theory proves theory and the proces proved environented impaces are appreciated				the used for the		
and detailed inversioner and detailed inversioner and detailed inversion and and and and and and and and and and				D. with militian of worked.		
E BOP comed verter quaitry must be conducted po cheller the adeques po white deserver power and the process two quart the process power the power t				and dotailed investight	2	
mur le conducted la claese tru adernage la nuite entrouser continuous monitoring continuous monitoring numb le conducted numb le conducted numb le conducted portuitly of water. mitigation measures to ouvoid environented impacto ac oppropriate				of RDD canal water and	ality	
trought deserver A there are a degreed a murphe conducted murphe conducted murph				must be conducted	0	
<u>A Murr deignn</u> <u>Continuer</u> <u>antioning</u> <u>antions maitoning</u> <u>antion be</u> <u>conducted</u> <u>through number</u> <u>through number</u> <u>ponability of unater</u> . <u>minigation nuegever to</u> <u>auoid environentep</u> <u>inpacto all oppropriate</u> .				to cheek the adequary		
imperes processing mussies conducted mussies processing porticite the providented minipadian measures to auorid environented imperes propriete				9. WWTP deserv. 0	and the second se	
must le conducted trivergrant the proces portentilles of water. Mitigation measures to avoid environented impaces ore apprepriete				antinent manitarive		
Through the process of the property of the process of the property of the property of the property of the process of the property of the process of the property of the process of the process of the property of the process of the pr				mint be conducted		
ponduille de valer. Ponduille de valer. Miligation measures to ovoid environentep importes are appropriate.		•		Harry ghand the procen		
ponduiter of water. Mingedian measures to avoid environentel impaces are appresente.				the chook His		
milligedian méasures to avoid environentel impacto are apprepriate				Portabilly of water		A State of the second s
avoir environentel impaces are apprepriete			y2	aligation weasures to		
impacto al appropriate				XIII ENVIROND NED	the state of	
and the market				N. M. C.		the second second
				made the and conduct	875	



Annexure-S

PICTORIAL PROFILE OF STAKEHOLDER ENGAGEMENT WORKSHOP



Pictorial Profile of Stakeholder Consultation Workshop



Pictorial Profile of Stakeholder Consultation Workshop



Pictorial Profile of Stakeholder Consultation Workshop



Pictorial Profile of Stakeholder Consultation Workshop

Annexure-T

ATTENDANCE SHEET OF STAKEHOLDER ENGAGEMENT WORKSHOP

Attendance Sheet of Stakeholder Consultation Workshop

ŀ			ATTENDENCE SHEET O	JE PARTICIPANTS		
S. No.	Name of Participant	Organization	Position	Address	Contact Number	Email Address
	Azmor Beg	duch	Emuricanial at	27. Empression	23334533562	ezmel. bez C
	DR. Kumun Geran	Dept 7 Fishing	Diver Forberi	2. Conto Roch	29434-1260	Walidtervaigozl
	IHGAN UL HAR FARDOGI	MM Parkislān	Social Development	27- Engress road	C764.4460	ihsanul. haque Omnpakistan com
	Imanat Ni	isrgelie-	500 Ravi Sypher	Canul bonk	0300609956	fegiamanato gnud.cor

	-	1	de r	t i	
	Email Address	Sam. Ezza 20 gmail- con	Starbalniceu.	ifti klocahneu 0738Ggnail.o	
	Contact Number	0331-425-8984	034-6642633	Eh79hh-0180	
JF PARTICIPANTS	Address	DA	Caroling Crown	Caraly Culound Lahore Cant.	
ATTENDENCE SHEET (Position		Pooject Manager	Environmental Engineer	
	Organization	Forman Christian college curiveria	ECO	ECO	
	Name of Participant	cter and	Shah Zu'b Ulvi	Ibtikher Ahned	•
	Sr. No.				

Email Address	Churchleybert Q Recardl. erg.	H)unezze When Q eco - Indl. cy J.			
Contact Number	2333-	-2120 014920L	0340-9316516	0321-7979	
Address		l			
Position	Envisonmentel Christopor	Jr. Environmentelist	XEN (WWT)	SDO(wwt)	5
Organization	63 Engineering	CJ Engineerig	WASA LDA Lure	LUAL LA	
Name of Participant	P. Chuch Vicebear	N) wn 9225 leh sm	WADAS NASEER	N.Unciv.Intias	
5 °					

		6	114 cont.uts upt cars. 15 conter	filmanda anta anta an	An Independent Andreas br>Andreas Andreas br>Andreas Andreas br>Andreas Andreas br>Andreas Andreas br>Andreas Andreas br>Andreas Andreas br>Andreas Andreas br>Andreas Andreas br>Andreas Andreas br>Andreas Andreas	99.
	Email Address	hydrologist 786	as laur syl train	imeen heider E mmpakistan . com	nulammed. Delinan Q etmail.com	576 ddre ppm
	Contact Number	03008470712	0345-	0317-510204	0334-1334400 2	18567-5550
OF PARTICIPANTS	Address	College of south and Envisionandal sciences Unitedaly of purgally	27-Eurpress	2) 337- and Uien Saviel
ATTENDENCE SHEET	Position	Lecturer	- raw - Leekd	ENGINEER	AD GES	Dir (fund
	Organization	puntado un versitut Ladore	JWW	AMM	W ASA	Impetio
	Name of Participant	Multumma d Wastar	Sifed Aslaw Sabzuieri	Syed Inkanu Haliser	Muhammad Rehman	Rav Zaknya Farriz
	Sr. No.		5.	à	G	\odot

	sa. Ananana ia	5 803	Log	41.1
Email Address	8 Shadiid. Semolo And	Zahideco-intr USA600 Cgmaille	druture Caro-in	3 Suncin-Clo-
Contact Number	0321 - 460071	0300-8044. 476	0333 4 768090	0307-707159.
Address		Careby gord	ECO Cavary from X Labor Count	ist Cavaty Cavaty Condo Latore
Position	Deput	Directer/ Sciellert	Environment	Junior Emiconnola
Organization	Imjedin Depti	RCO	4 ECD	Eco
Name of Participant	Shawid Habib	Zawid 1950	Je kausar Jawal Cheen	Suncina
Sr. No.		R	~	3

	Email Address	Buria anamesmui	adsiyatramin	Indedhussan Dficklege. edu. P.K.	annagesuid 19180g maillon
	Contact Number	0336888090	0337- 7802023	6345 4711162	0334- 40086078
F PARTICIPANTS	Address		MASA Maculas E Devison Directoria UN	FC	LSE Lorrohe
ATTENDENCE SHEET O	Position	AD(415)	(23d) (H	Acrictant	Itudent
	Organization	WASA, LOA	INIASA -LAR	Fcc	Ruc
	Name of Participant	BURIRA	Asis Anis	Imbed Hussain	Annal
-	Sr. No.				

	Email Address	S. Jmail 418	mune 2000 g y d L	soinunt 36	institutes of final in	
	Contact Number	03377800317	0321-468703	03344337196	hest-18h-1252	
OF PARTICIPANTS	Address		53-C-2 M. A. G. L. Ca	113/3 Grothi Shahn Allana Igbal ya	57-F Gursettau-E-retai	
- ATTENDENCE SHEET	Position	Dy. Délecter (Prewrennest)	Die Le (H.B) & 4.0	Assistant	Ą. D	
	Organization	lainth, Lahoce	180HB7 858M	LNWMP	DC-J WASH	
	Name of Participant	Sama fâllime	: SNAW BAZEUM	Saima Ashraf	Matterine (Ithmm Mt)	
- [ч З З					

21	Name of Participant	Organization	Position	Address	Contact Number	Email Address
	ACHAMMAD ASMACHAM	PAKISTAN NICTEOROLOGIE BEPARTMEN	AL DIRECTOR	Regional Matenologies Cantre Cantre Uplo-Jail Roud	85TILT HEREO	on an april she
2	Dr. Michaumand Ashing Bodla	M M Palisla	Cliff	1-77 E.I E WAPDA Town, Lature	0300473986	R. Malage Christen
3	Sadagut Loty	Inigetton	Executive Engineer	Canal Bank Mustefabad Lothne	0322448672	sadagat lat
3	Ukman Ali Khan	Isuçation.	sue Divisional	Lahoure Drainge Distrion.	0336 -748306	engresmand 1

				ATTENDENCE SHEET	OF PARTICIPANTS		
SZ	1.	Name of Participant	Organization	Position	Address	Contact Number	Email Address
1	5	Asy mitted	Landwilder)	19A, ST. Jetin Park, Lalure Cauli	030043822	Hzhagi a hutmail. ww
		nampured Haf	Le-d Lolde	1	village hoje find - 295]2 Sarwar Rd, Lalare Call.	0300-843923	MOJ-T MMAD TOMAN L-COM
		KAMIL KHAN MUMTA2		Architect	18-A, St. C, UPPER MALL SCHME	0309424150	ktwarchiteta Ogmeel . com
		Rana	Compart		297.A Nosintar Alawa 9 prol Torran	039526324	3 Saturantrout

	Email Address	ramere raputsod	engr. muhammaal immans Email. Com			
	Contact Number	0334-009418	7595409-4550	0364550913	0300 8026515	14 Contraction 14 Con
F PARTICIPANTS	Address	59-F Gullshave Ravi	59-F Gulshan e kan			
ATTENDENCE SHEET O	Position	SCE-V	JCEV	25/13)	11 2 5/20	
	Organization	WASA Labouro	WASA Lahore.	and the second s		
	Name of Participant	Engr. PAMEER	M. IMRAN	j'willight	212	
	Sr.	NO		19.30		

Email Address	2		fariha.onog () v.a. edu pe	avais.lurede was.edu ph.	difermants ect-in	
Contact Number	1907020		03331-550	-LIS 7747 44 50	0300-447532	
: PARTICIPANTS Address	in the .		outali Road, Uvan, Lathore.	outal Roal	kavalay grand	
ATTENDENCE SHEET OI Position	AP		Assistant Professor.	Leetarer	Envisonmental Compliance	informer
Organization		e.	university & verecimany and animal Sciences.	Winnunty of vitarian E Amanel Saianu, IHC	ECO.	
Name of Participant	12 al		Dr. Fariha Arooj	M-Avois Molid	Dr. Ali kamuan	
S.	ÖZ					Ţ

		.ई.न	8 8			ALL CONTRACTOR OF CONTRACTOR O
	Email Address	Mizuanaluta Phile Smar	Zubrik Suber	Hureb. Salan		
	Contact Number	4551550	estheteces	515£881-1620	0332	
: PARTICIPANTS	Address		Conja Sindhu	Genta Sindhu	1 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	
ATTENDENCE SHEET OF	Position	Priny Social	4 P			
	Organization	PSES	Attested	Affected		
	Name of Participant	Rimme	Zubaul Salean	Hajedo Saleum	RopagateAL	
	Sr.		ورود و و و و و و و و و و و و و و و و و و	an ann ann an	anan kasaman ni filo fananci di kasa ana da ana	

	Email Address	Comerce Comerce	the second	Jand Salp	heteen os so	
	Contact Number	-+ 580 7809 <i>0</i> 0	0337 - Fataat	0337- 7801261	0337- 7802444	
OF PAS TICIPANTS	Address	59-F, Gulsher -t-Ravi Labore	Gulter.	Guilte?	Cyubug Lahare	
ATTENDENCE SHEET	Position	Assitunt Director Procurement	Syceron (Cer)	A D(PYD)	(Ched) CH	
	Organization	cutts A	15711	WASA	N-SA	
•	Name of Participant	Arsadan Idrees	LEDue Matter	N. Jamad Prshid	Hassan-ullah ne. 121 m	
	S.	og <u>r-1</u>	σί	3	2	
: 0	Name of Participant	Organization	Position	Address	Contact Number	Email Address
-----	--------------------------	----------------------	------------------	--------------------------------	----------------	--------------------------
-	Syed Yarr	WASA, UN1401	(on lo of	WASA HEAD OFFICE	0333333041	Syarrengy C Junil. 6.
	Hold's Monsin Tanveer	PLRA	Adl. Dix Systems	2KM, Nain Multon Soad, LHR.	0221-1520	monsin-tamena
	CHIRDLAN CHIRDRAN	WhSA, LOA, Lakore	46 (DC-1)	59-1 WASA office Del	0321-691555	hashain Artha
	Topuas Goed	WARA, Lahor	MS-QH	WASA Head office	1342692-480	triver lotrail

-	Name of Participant	Organization	Dreition	A - 1 - 1 - 1 - 1		
1	المعارفة والمالية والمحالية والمحالية والمحالية والمحالية والمحالية والمحالية والمحالية والمحالية والمحالية وال			Address	Contact Number	Email Address
	Archere ogageral	Agricultorie	Londown	Will Ganga Smaken Bara purkakar	0321242. 1421290	
diversion of the second se	Zuljikar Moeen,	Planning Development Bocyd,	Zifrastructur Specialit	Palos.	0504-493	2 aguer voi
	Sheith Annun	MASA LDA.	DIRECTOR.	23 Marin . Bouteward, Gulleng-111	-1220 780031	disectormu
	Will wake ec	Arizaelo (J place	lane holder	159/E Aslazi X zotoru	0333 4086655	ad 1 waherd

	Name of Participant H. M. Jausa d Tayyal Malih	Organization WAS (A	Position AD, P + D DD(PS, D)	Address	Contact Numbe 0330 713252 0345-1103458	F Email Address F h n jawad 199 fa gmail.co
	Sardar Jahangir Wagar Sangad Nussain	Norgan	Technical	L'HR LHR	0322-7671 4281512 0339-7671 675	Jerhough Dezerra

Brief IV Att Director (740) Calvare (740) Abdul WASA Dwo(Engo) CI 43 O142 O142 O142 O142 O142 O143 O142 O142 O142 O143 O142 O143 O143 O142 O142 O142 O142 O142 O142 O142 O142 O142 O142 O142 O142 O142 O143 O143 O142 O142 O142 O142 O143 O142 O143 O142 O143 O142 O142 O143	OLYAIIIZAUO	n Position	Address	Contact Number	Email Address
Abdul WASA DMO(Engo) ir Lahm. DMO(Engo) O332-44 WASA Directer (PHE). (PHE).	W AZA	Director (740)		0333-333	Zeeshaubitale
Beber WASA Director 0321-4687	WASA Laton	Dwo(Eng)		0332-44550	۶«
	WASA LHR	Director (PtE)		0321-4687080	USman babarls @yalloo.com

	Email Address	Parquellae	hasaminitik Suint Car	Tanjurdhund 452 @ Small	
	Contact Number	0313-412200	8515 BEN-8550	0333-	
JF PARTICIPANTS	Address	95-6 fizzo storet Crahi Shahu Lahuose	11	2-Squeler Receled	
ATTENDENCE SHEET C	Position	Cooselinated	President	Distightion	
	Organization	PuRc	NEMANN	Dist wildlight	
	Name of Participant	Almad Scy ad	MILL HASSAL	Tannie Runad Dauger	
	Sr. No.				

			Am	th	
	Email Address	Khaid Uemari @ Waler vegime . Com	Samuelleco-1	1-003 Component	
	Contact Number	0300 842/33/	032446643	0333-43022	
F PARTICIPANTS	Address	130 R3 Johan Town LINK			
ATTENDENCE SHEET OI	Position	Divector	Environment	Enuconnect Specialist	
	Organization	Laberd Chamber StCommetee \$ 1 hodystrey	ESIA	ESIA Team	
	Name of Participant	Name Centry	IN. GAMIA	DR. PISIM MAHMODD	
	Sr. No.				

		ATTENDENCE SHEET OF	F PARTICIPANTS		
articipant	Organization	Position	Address	Contact Number	Email Address
21	anot	(nn (Pan)	Α	0300-0300-	Nya.di O iclop.pk
123		AP		0321	

Farticipant Organization Position Sarbaz & R.A. Inc Urbau SRA Urit r. "", "	Address	Contact Number 0336-71277696 2454768115	Email Address Sabasau Mau
Saufraz 8RA The Undan SRA Unit. """"""""""""""""""""""""""""""""""""		0336-7277696 211826426	Sabasau Kial-
" " " " " " " " " " " " " " " " " " "		SINBACHENE	agnall con
		- r 3	on groot con
	:		

Annexure-U

CALCULATIONS FOR POWER REQUIRMENT

Calculations

TOTAL POWER REQUIREMENT OF EXISTING TUBE WELLS AND PROPOSED SWTP

Power Requirement of SWTP

The total energy requirement of proposed SWTP would be 04 MW.

Power Requirement of Existing Tube wells

Currently 60 tube-wells are working in these four serving areas providing water with direct pumping. The summary of existing operational tube-wells in these four areas is as below:

	Tube wells	
Capacity	Number	Total Capacity (Cusecs)
2 cfs	19	38
4 cfs	41	164
Total	60	202

Following formula was utilized to calculate the total power (in KW) of each pump respective to their discharge capacity.

$$P = \frac{Qpgh}{3.6 \times 10^6}$$

P - kW (Power of pump)

Q - m3/h (Flow of Water)

ρ - kg/m3 (Density of Water)

g - m/s2 (Gravitation Constant)

h – m (Head of pump)

Annexure-U

Calculation of 2 cusec pumps:

 $P = (200 \text{ m}^3/\text{hr}) (1000 \text{ kg/m}^3) (9.81 \text{m/s}^2) (250 \text{m})$

3.6x10^{^6}

P=136.25kW

By this formula the kW power of the tube wells of 2 cusecs was measured. It was found that approximately around 0.13625MW per hour. As there are 19 tube wells having the discharge capacity of 2 cusecs, the total energy consumed by them would be 2.58MW in one hour.

Calculation of 4 cusec pumps:

 $P = (400 \text{ m}^3/\text{hr}) (1000 \text{ kg/m}^3) (9.81 \text{m/s}^2) (250 \text{m})$

3.6x10^{^6}

P=272.5 kW

Similar calculations were done in case of tube wells of 4 cusecs discharge capacity, and it was found that 41 tube wells of 4 cusecs each would consume 11.17 MW of electricity in one hour.

The total energy consumed by all of the tube wells already installed are equal to 13.75Mw.

Annexure-V

LABOUR CAMP MANAGEMENT PLAN

The scope of this plan covers the sitting, development, management and restoration of construction camps to minimize and mitigate impacts on the environment. Local and migrants both shall be employed in this project.

This plan is developed as per guidance provided in ESMP on labour camp sitting, management and labour accommodation.

The contractor once on the site would require to establish a construction and labour camp. The land for the establishment of camps will be decided after obtaining consent from local residents and land owners.

Most of the impacts arising from operation of the camp would be managed mainly by Construction Contractor. Responsibilities for managing these impacts have been clearly initiated as contractual commitment, with suitable mechanisms for addressing noncompliance.

The contractor would also be required to formulate specific labor management procedure and mitigation prior to start construction and monitor and update the labour management plan as and when needed during the project.

LWASA would also develop a separate training manual with the help of technical experts to build the capacity of LWASA Staff, supervision Consultants and contractors and subcontractors in developing and execution of this labour management plan. This plan would address detailed activities that will be undertaken to minimize the impact on all sensitive receptors present at site such as

- Communication and awareness plan on all national and provincial labour and women harassment laws and policies and its penal implications and allowances for workers benefit
- Labour codes of conduct with respect to child labour, manual scavenging, meeting with residents, nondiscrimination, harassment of colleagues including women and those belonging to other minority social groups
- Training sessions on HIV/AIDS and all other communicable diseases, etc.
- Compliant handling mechanism

Pre-Construction Stage

1. Siting

The contractor will work out arrangements for setting up his facilities during the duration of construction with the local residents and LWASA-PMU. These preparations shall be in the form of written agreement between the contractor and the local residents that would stipulate:

- Pictures of the proposed camp site in original condition;
- List the activities to be carried out at the site
- Environmental mitigation measures to be undertaken to avoid land, noise, air & water.
- Detailed layout plan for the establishment of the construction and labour camp that shall specify the various structures and facilities to be constructed in the camp including material storage and toilets.
- Detailed Site Restoration plan

All these arrangements will be verified by the LWASA-PMU to enable redressal of grievances at a later stage of the project.

1. Establishment of Labour and Construction Camps

During construction stage of the project, the contractor would establish and maintain necessary living accommodation, additional facilities for labour such that the supplies of food, healthcare and transport. The labour camp will be set up near or at the proposed site of STPs. The camp site should be selected keeping in mind that the site would not be located within or close to any sensitive receptor. The contractor should make sure that the camp site does not negatively affect local fauna and flora of the site. All activities should be carried out within the preidentified area.

The site supervisor should take attendance of each workers twice a day (morning and evening) and should maintain proper record. Furthermore, working hours of workers should be in accordance to the labour law.

All workers should be provided with proper ID cards. Site security guards should make sure that all workers entering to the site have their ID cards with them. No

unknown person should be allowed to enter at the site. Entry of outsiders should be maintained by the site security guard.

Living accommodation with all necessary facilities should be given to all the migrant workers employed for the complete duration of construction period. The rooms of workers shall be well ventilated and lighted. Transportation to the labour from the camp to the working site should also be provided (if possible).

- 1) Site barricading and safety
- 2) Clean Water Facility
- 3) Clean kitchen area
- 4) Clean Living Facilities
- 5) Sanitation Facilities
- 6) Waste Management Facilities
- 7) Provision of Rest Area Room and Emergency Assembly Point
- 8) Safe access road
- 9) Health Care Facilities
- 10)Crèche Facility
- 11)Storage of Construction
- 12) Firefighting Facility

1) Site Barricading and Safety

Site should be entirely barricaded from all the sides to avoid entry of outsiders into the site with adequate flags, marking & reflectors etc. for safety of pedestrians and general traffic movement. A proper board should be displayed at the site, name and capacity of the project, brief overview of financing & executing agency and contactor, estimated project time period, necessary safety and warning signs, sign related to restriction of entry without authorization & no smoking area. All machinery and equipment operation should be restricted to 6:00 AM to 6:00 PM.

2) Clean Water Facility

In order to provide clean water facility at the construction camp, the contractor shall ensure the provisions of the following

- Potable water shall be provided to constructor labour for drinking & cooking purpose. Clean water shall be provided for cleaning, washing and bathing purpose.
 Drinking water quality analysis should be carried out on monthly basis.
- Every water supply or storage source should be at a distance of not less than 15-20m from any sewage drain or other source of pollution. Water sources within 15-20m proximity of drain, toilet or any source of pollution should not be used as a source of drinking water in the project.
- If bore well used as drinking water source, it shall be properly covered, the door shall be kept locked and opened only for cleaning or inspection, which shall be done at least once a month. There shall be a motor installed for extraction of water from groundwater.
- In each site, suitable facilities for utensils and washing clothes shall be provided and maintained for the used contract labour living therein. Separate and adequate toilets should be provided for the use of male and female workers. Such facilities should be easily accessible and shall be kept in clean and hygienic conditions.

3) Clean Kitchen Area

An area should be designated at site for cooking and storage of eatables. Clean fuel such as shall be provided to workers for cooking purpose. Burning of garbage, paper firewood and any other material for cooking purposed shall be strictly prohibited at the site. all kitchen waste should be properly disposed off. Water storage container at kitchen should be covered and cleaned on monthly basis. Kitchen area should be away from toilets and bathing area.

4) Clean Living Facilities

Workers should be provided with bedding facility such as Charpai and long-lasting impregnated nets for mosquito and vector control.

Facilities for storage of personal belongings for workers should be provided in form of cupboard or locker.

A separate storage area should also be provided for the PPES & tools. Proper ventilation and lighting system should be ensured in construction camp.

5) Sanitation and Toilet Facilities

Appropriate sanitary arrangements shall be provided in every work place separately for male and female workers. The arrangements shall include:

- Every latrine shall be under covered area and partitioned enough to secure privacy with proper door and fastening
- All latrines shall be adequately lighted and shall be maintained in clean sanitary conditions
- All latrines should have a proper drainage system
- Appropriate water storage container shall be provided in all latrines.
- Good hygiene practices should be maintained in all camps.
- All the wastewater generated from these facilities should be disposed off properly through septic tanks

6) Waste and Wastewater Management in Labour Camp

A containerized sewage treatment plant (STP) can be installed for the duration of construction period which may treat water and make it reusable for green areas. After, the construction the same can be utilized for any other project

Provide appropriate dustbins for recyclable and non-recyclable waste in labour camp area. All recyclable waste shall be sold to authorized waste vendors and non-recyclable waste shall be disposed through EPA Certified waste vendor.

Dumping of waste and wastewater on surface/ground shall be strictly avoided or prohibited. Hazardous Waste shall not be stored in unlined ponds.

Wastewater generated from car washing/cleaning and maintenance area shall be passed through oil and grease trap and water shall be reused for sprinkling and wheel washing.

Wastewater generated at construction site should not be allowed to accumulate as standing water as the standing water may create breading places for mosquitos.

All wastewater from labour camps shall not be directed into Ravi River but should be treated and disposed through septic tanks.

A temporary storm water drainage system should be provided at site and accumulation of storm water at site should be avoided. Proper area-shall be designated for storage of oils, lubricants and machine oils. All these substances shall be stored with suitable secondary containment

7) Provision of Rest Area Room and Emergency Assembly Point

A suitable shed should be provided at site for rest of male and female workers. Sheds should be made separately for women and men. The height of the shed shall not be less than 3.0 m from the floor level to the lowest of the roof. Sheds should be kept clean all the time. Emergency assembly point/area shall be demarcated properly at the site where all workers can assemble in event of fire, earthquake and natural calamity at the site.

8) Safe Access Road

Temporary paved surface shall be constructed to approach camp site. Transportation vehicles carrying construction material should be adequately covered to prevent dust generation and to avoid material spillage.

9) Medical and First Aid Facilities

Medical facilities shall be provided at site for labour. Visits of the doctor shall be managed twice a month wherein routine checkups would be carried out for workers. A separate camp should be built for medical checkups. Some awareness posters should be displayed at the site on safety facilitation, hygiene and HIV/AIDS. Training should be given to site personal to administer first aid on time. Adequately stocked first aid kit should be provided at the site. The first aid kit/box shall contain the following

- Small, medium, large sterilized dressings
- Piodine
- Plasters in different sizes and shapes
- A pack of Sterilized Gloves
- Bottle of potassium permanganate crystals
- Ointment for burns
- A bottle of suitable surgical antiseptic solution
- 1 pair scissors
- Thermometer (preferably digital)
- A pack skin rash cream
- Pain Killer

• Cough Medicine

Ambulance availability should be ensured at the site for carrying injured to the nearby hospital. Links should be made with nearby hospital/clinic to handle emergency if any. Number of doctors, nearby hospitals and ambulance shall be displayed in the first aid room & labour camp. All emergency contact numbers such as fire brigade, bomb disposal & police should be displayed at camp site, first aid and security guard room.

10) Crèches Facility

In case more women workers are employed, there shall be a suitable room of reasonable size for use of children under the age of 6 years. The room should have proper light and ventilation. A caretaker is to be appointed to look after the workers children. The use of the room shall be limited to children, their mothers and the caretaker.

11) Storage of Construction Material in Construction Camps

- A proper area should be designated for storage of all construction material.
- All hazardous substances such as oil, lubricants, paints should be stored in proper area. All these material/substances shall be stored with secondary containment to avoid spills.
- Impervious surfaces should be used for refueling sites and other fluid transfer areas to avoid water and soil contamination due to spillage.
- Training should be provided to workers on correct transfer and handling of fuels and chemicals
- Spill kit should be available and accessible to site workers
- All hazardous materials shall be stored in a barricaded area. In case of electrical equipment, danger signs shall be posted.
- The batch and asphalt mixing plant are to be located away from the residential area and not in the direction of wind. Separate vehicles parking areas and also workshop areas need to be provided.

12) Firefighting facilities

- Adequate firefighting arrangement shall be made at the site. The following precautions need to be taken:
 - o Demarcation of area prone to fires with cautionary signage

- Portable fire extinguishers and/or sand baskets shall be provided at easily accessible locations
- Contractor shall educate the workers on usage of this equipment.

During Construction Activities

Keep and maintain construction camp free from litter/garbage and in good hygienic conditions. It should keep free from spillage of fuel, oil and lubricants. In case of accidental spillage, immediately clean the spill to avoid pollution of soil, water stored or adjacent water bodies. The following precautions need to be taken in construction camps.

- Adopt measures to ensure that no leaching of oil and grease into water bodies or underground water takes place
- Wastewater should not be discharged into water bodies.
- Regular collection of solid wastes should be ensured and should be disposed safely.
- All consumables as the first aid equipment for maintaining hygiene and sanitation should be recouped immediately.
- The scrap/debris generated during construction should be kept in a designated and barricaded area.
- The LWASA will monitor the cleanliness of construction campsites and ensure that the sites are properly maintained throughout the period of the contract.

A. Grievance Redressal System

A complaint box and complaint register should be provided at the site so any person from local resident can register their complaint, if any due of the camp, workers and other facilities. The grievance mechanism shall be communicated to local communities through consultations. Open house sessions/meetings should be conducted with workers on monthly basis to identify their concerns/problems and issues if any related to safety, comfort, health, hygiene and other issues.

Activities prohibited at site

- Those activities which should be strictly prohibited at site shall include
- Disturbance to local community

- Open burning of waste
- Adoption of unfair means or getting indulgence in any criminal activity
- Non-compliance of the safety rules as communicated by safety officers and during the trainings
- No fauna shall be harmed by any construction worker, except in self defense
- Cutting of tree without permission of project head
- No indigenous population shall be offended or teased

C. Post Construction/Decommissioning Stage

After the completion of construction work, all camp facilities shall be dismantled and removed from the site. The site shall be restored to original condition in no way inferior to the condition before to commencement of the work.

- All temporary structures should be removed and cleared from the site
- Waste generated during construction should be disposed suitably as per the construction waste management plan.
- All trenches should be filled in, disinfected and effectively sealed off
- All the areas within the camp site should be levelled and spread with stored top soil so as to aid faster rejuvenation.
- Residual topsoil, if any will be spread evenly in plantation sites or affected agricultural land adjacent to the proposed project site that has been impacted because of any accidental spillage.
- All fuel and oil contaminated soil shall be removed and transported and buried in waste disposal areas.
- Whole camp area should be left clean and tidy, in a manner keeping the adjacent lands neat and clear, to the entire satisfaction of LWASA
- Proper documentation of rehabilitation site shall be maintained. This shall include the following:
 - Pictures of rehabilitated site
 - Undertaking from contractor
 - Certification from project director of LWASA

Annexure-W

GHG EMISSIONS INVENTORY

-							Green Hou	se Gas Emissi	on Inventory	/ Package 03						
			Activity Data		Total Fuel Consumption	*CO2 Emission Factor of Diesel Fuel	*CH4 Emission Factors of Diesel Fuel	*N2O Emission Factors of Diesel Fuel				GHG Emission kgCo2	teq			Tonnage of CO2w
Machinery Type	Quantity	Fuel Consumption	Working Hours	Working Day						GWP of CO2		GWP of N2O		GWP of CH4	total kg/litres	TonsCo2e
		Diesel Liters	hr	days	litres	Liquid Basis Kg/litre	Liquid Basis Kg/litre	Liquid Basis Kg/litre	CO2 Kg/litre	100 yr GWP (AR4)1	N2O kg/litres	100 yr GWP (AR4)1	CH4 kg/litre	100 yr GWP (AR4)1		
Bulldozer (Rough Grading)	1	26	12	260	79560	2.676492	0.0003612	0.000021672	212941.7035	1	456.9194448	265	804.638016	28	214203.261	214.203261
Bulldozer (Stock Piling)	1	26	12	260	79560	2.676492	0.0003612	0.000021672	212941.7035	1	456.9194448	265	804.638016	28	214203.261	214.203261
Concrete Truck	3	26	12	260	238680	2.676492	0.0003612	0.000021672	638825.1106	1	1370.758334	265	2413.914048	28	642609.7829	642.6097829
Concrete Pump	2	26	12	260	159120	2.676492	0.0003612	0.000021672	425883.407	1	913.8388896	265	1609.276032	28	428406.522	428.406522
Crawler Crane	2	26	12	260	159120	2.676492	0.0003612	0.000021672	425883.407	1	913.8388896	265	1609.276032	28	428406.522	428.406522
Diesel Generator	1	26	12	260	79560	2.676492	0.0003612	0.000021672	212941.7035	1	456.9194448	265	804.638016	28	214203.261	214.203261
Excavator	1	26	12	260	79560	2.676492	0.0003612	0.000021672	212941.7035	1	456.9194448	265	804.638016	28	214203.261	214.203261
Grader	3	26	12	260	238680	2.676492	0.0003612	0.000021672	638825.1106	1	1370.758334	265	2413.914048	28	642609.7829	642.6097829
Hyfraulic Shovel	1	26	12	260	79560	2.676492	0.0003612	0.000021672	212941.7035	1	456.9194448	265	804.638016	28	214203.261	214.203261
Loader	1	26	12	260	79560	2.676492	0.0003612	0.000021672	212941.7035	1	456.9194448	265	804.638016	28	214203.261	214.203261
Off-Road Truck	3	26	12	260	238680	2.676492	0.0003612	0.000021672	638825.1106	1	1370.758334	265	2413.914048	28	642609.7829	642.6097829
Dump Truck	3	26	12	260	238680	2.676492	0.0003612	0.000021672	638825.1106	1	1370.758334	265	2413.914048	28	642609.7829	642.6097829
Water Truck	3	26	12	260	238680	2.676492	0.0003612	0.000021672	638825.1106	1	1370.758334	265	2413.914048	28	642609.7829	642.6097829
Wheel Loader	1	26	12	260	79560	2.676492	0.0003612	0.000021672	212941.7035	1	456.9194448	265	804.638016	28	214203.261	214.203261
Vibrating Compactor	2	26	12	260	159120	2.676492	0.0003612	0.000021672	425883.407	1	913.8388896	265	1609.276032	28	428406.522	428.406522
Compressor	1	26	12	260	79560	2.676492	0.0003612	0.000021672	212941.7035	1	456.9194448	265	804.638016	28	214203.261	214.203261
Batching Plant	1	26	12	260	79560	2.676492	0.0003612	0.000021672	212941.7035	1	456.9194448	265	804.638016	28	214203.261	214.203261
Asphalt Plant	1	26	12	260	79560	2.676492	0.0003612	0.000021672	212941.7035	1	456.9194448	265	804.638016	28	214203.261	214.203261
Grand Total					2466360				6601192.809		53.45095392		890.849232		6640301.09	6640.30109

Green House Gas Emission Inventory Package 04	Green	House	Gas	Emission	Inventory	Package 04
---	-------	-------	-----	----------	-----------	------------

			Activity Data		Total Fuel Consumption	*CO2 Emission Factor of Diesel Fuel	*CH4 Emission Factors of Diesel Fuel	*N2O Emission Factors of Diesel Fue			Gŀ	IG Emission k	gCo2eq			Tonnage of CO2w
Machinery Type	Quantity	Fuel Consumptior	Working Hours	Working Day						GWP of CO2		GWP of N2O		GWP of CH4		
		Diesel Liters/hr	hr	days	litres	Liquid Basis Kg/litre	Liquid Basis Kg/lit	e Liquid Basis Kg/litre	CO2 Kg/litre	100 yr GWP (AR4)1	N2O kg/litres	100 yr GWP (AR4)1	CH4 kg/litre	100 yr GWP (AR4)1	total kg/litres	TonsCo2e
Bulldozer (Rough Grading)	1	26	12	260	79560	2.676492	0.0003612	0.000021672	212941.7035	1	456.919445	265	804.638	28	214203.261	214.203261
Bulldozer (Stock Piling)	1	26	12	260	79560	2.676492	0.0003612	0.000021672	212941.7035	1	456.919445	265	804.638	28	214203.261	214.203261
Concrete Truck	3	26	12	260	238680	2.676492	0.0003612	0.000021672	638825.1106	1	1370.75833	265	2413.914	28	642609.7829	642.6097829
Concrete Pump	2	26	12	260	159120	2.676492	0.0003612	0.000021672	425883.407	1	913.83889	265	1609.276	28	428406.522	428.406522
Crawler Crane	2	26	12	260	159120	2.676492	0.0003612	0.000021672	425883.407	1	913.83889	265	1609.276	28	428406.522	428.406522
Diesel Generator	1	26	12	260	79560	2.676492	0.0003612	0.000021672	212941.7035	1	456.919445	265	804.638	28	214203.261	214.203261
Excavator	1	26	12	260	79560	2.676492	0.0003612	0.000021672	212941.7035	1	456.919445	265	804.638	28	214203.261	214.203261
Grader	3	26	12	260	238680	2.676492	0.0003612	0.000021672	638825.1106	1	1370.75833	265	2413.914	28	642609.7829	642.6097829
Hyfraulic Shovel	1	26	12	260	79560	2.676492	0.0003612	0.000021672	212941.7035	1	456.919445	265	804.638	28	214203.261	214.203261
Loader	1	26	12	260	79560	2.676492	0.0003612	0.000021672	212941.7035	1	456.919445	265	804.638	28	214203.261	214.203261
Off-Road Truck	3	26	12	260	238680	2.676492	0.0003612	0.000021672	638825.1106	1	1370.75833	265	2413.914	28	642609.7829	642.6097829
Dump Truck	3	26	12	260	238680	2.676492	0.0003612	0.000021672	638825.1106	1	1370.75833	265	2413.914	28	642609.7829	642.6097829
Water Truck	3	26	12	260	238680	2.676492	0.0003612	0.000021672	638825.1106	1	1370.75833	265	2413.914	28	642609.7829	642.6097829
Wheel Loader	1	26	12	260	79560	2.676492	0.0003612	0.000021672	212941.7035	1	456.919445	265	804.638	28	214203.261	214.203261
Vibrating Compactor	2	26	12	260	159120	2.676492	0.0003612	0.000021672	425883.407	1	913.83889	265	1609.276	28	428406.522	428.406522
Compressor	1	26	12	260	79560	2.676492	0.0003612	0.000021672	212941.7035	1	456.919445	265	804.638	28	214203.261	214.203261
Grand Total					2307240				6175309.402		13250.6639		23334.5		6211894.568	6211.894568

Per anum

Annexure-X

OCCUPATIONAL HEALTH AND SAFETY MANAGEMENT PLAN

OCCUPATIONAL HEALTH AND SAFETY MANAGEMENT PLAN

The contractor should conduct a Health Risk Assessment of all construction activities for all chemical, biological, physical, ergonomic, physiological health hazards and emergency situations associated with work at construction site. The risks should be evaluated as low, medium or high on the Risk Assessment Matrix based on which control measures should be selected and implemented. Onsite and Off-site emergency preparedness and response plan shall also be developed to effectively handle emergency situations on time.

The environmental, health and safety aspects and related emergency preparedness response can include incidence such as collapse of plant structure, trench, fire explosion and other occupational accidents.

The selection of controls should take into account hierarchy of control i.e. Elimination, Substitution, Engineering, Administrative and Personal Protective Equipment.

The Contractor shall develop the onsite emergency plan considering the significant environmental, occupational health and safety emergency at site and activities involved, and submit a copy of this plan to LWASA-PMU and Project Environmental Consultant before the start of work.

Construction staff shall be trained enough in the nature of handling occupational risk, hazards and relevant control and responses

All records of emergency preparedness plan along with emergency contact numbers, mock drills and corrective preventive action measure shall be maintained. All these records shall form part of quarterly report to the LWASA-PMU.

Contractor shall be responsible to handle emergency conditions and also be responsible to compensate damage against accident (if occurs at site)

1) Chemical Hazards

The Contractor shall identify, assess and control all hazardous material/substances involved in the construction including building materials, fumes, dust, proprietary chemical products and gases emitted because of cutting and welding activity at site.

2) Physical Hazards

The Contractor shall identify and evaluate the risks associated with physical hazards and eliminate them or control them as low as practicably possible by applying the principles stated below

Noise

The Contractor shall minimize noise from construction equipment by measures such as:

- Selecting less noise producing machinery
- Conducting regular maintenance of equipment
- Conducting periodic monitoring of sound pressure at least once each quarter

Vibration

Where exposure to vibration may affect any body part or full body e.g. during working with pneumatic drills, the Contractor shall ensure that exposures are assessed, eliminated or otherwise controlled.

Climate Stress

For operations under extreme weather/climatic conditions, The Contractor shall develop procedure in compliance with relevant standards.

3) Biological Hazards

Where bacteria, viruses, insects, mites and animals are present in the working environment, exposure to pathogenic biological agents shall be controlled.

Malaria

If the construction is taking place in such area where malaria is common disease, so contractor should prepare a comprehensive risk control program. Use of malaria prophylaxis is a must, similar is the case with wearing hard hats and wearing safety shoes. The four main components of malaria prophylaxis are:

Awareness

- Be alert and aware of the risk of malaria in the work sites
- Be informed of the signs and symptoms and know how long it will take to develop illness after being bitten by mosquitos.

Bite Prevention

Avoid being bitten by mosquitos by adopting following measures

- Use insect repellent
- Provide mosquito nets to workers at bedtime
- Wear long sleeves shirt and trousers when working outdoors

Chemoprophylaxis

- Preferably use when advised by competent health professional
- Take anti-malarial drugs (chemoprophylaxis) when needed to prevent infection from developing into clinical disease. Please note anti-malarial drugs don not guarantee 100% protection.
- Medications are safe to use when they are taken as per medical advice

Diagnosis and Treatment

- Early diagnosis and treatment can prevent death rate. Seek immediate diagnosis and treatment if fever like symptoms develop more than one week after entering and up to 3 months after leaving from the risk area.
- Notify your doctor of recent visit to malaria risk area
- Contractor should closely monitor performance of these Malaria Control Programs

Legionella Bacteria

Human made building water systems may support the growth of legionella bacteria thus causing Legionnaires disease. These bacteria can enter the human body when small droplets of water containing the bacteria are present in the air. The sources of legionella-contaminated water at construction sites which may lead to infection include:

- Domestic water storage tank
- Fire water tank
- Water storage tank used to suppress dust at site
- Pipe work and head
- Safety Showers

The Contractor shall appoint a competent person to evaluate the risk of legionella and to implement the control measures.

Aedes Aegypti

Dengue is a mosquito-borne viral infection causing a severe flu-like illness and, sometimes causing a potentially lethal complication called severe dengue. The mosquitoes prefer to breed in areas of stagnant water, such as uncovered barrels, buckets, and discarded tires, but the most dangerous areas are wet shower floors and toilet tanks, as they allow the mosquitos to breed in the residence.

Symptom

Mild symptoms of dengue can be confused with other illnesses that cause fever, aches and pains, or a rash. The most common symptom of dengue is fever with any of the following:

- Nausea, vomiting
- o Rash
- Aches and pains (eye pain, typically behind the eyes, muscle, joint, or bone pain)
- Any warning sign

Symptoms of dengue typically last 2–7 days. Most people will recover after about a week.

Diagnosis and Treatment

- Early diagnosis and treatment can prevent death rate. Seek healthcare provider if you develop a fever or have symptoms of dengue.
 - Rest as much as possible.
 - Take acetaminophen (also known as paracetamol outside of the United States) to control fever and relieve pain.
 - Do not take aspirin or ibuprofen!
 - Drink plenty of fluids such as water or drinks with added electrolytes to stay hydrated
 - Contractor should closely monitor performance of these dengue Control Programs

Bite Prevention

Avoid being bitten by mosquitos by adopting following measures

- Use insect repellent
- Provide mosquito nets to workers at bedtime
- Wear long sleeves shirt and trousers when working outdoors
- Avoid areas with standing water. Especially at times of high mosquito activity like dawn and dusk.
- Once a week, scrub off eggs sticking to wet containers, seal and/or discard them.

Awareness

- Be alert and aware of the risk of dengue in the work sites
- Conduct workshop on awareness of dengue and related precautionary measures
- Site workers be informed of the signs and symptoms and know how long it will take to develop illness after being bitten by mosquitos

Pest and Insect Control

Typical pests are mosquitos, snakes, rats and flies. Good cleaning and housekeeping of work sites is the basis of any pest control programme.

Furthermore, provide long lasting impregnated nets at the bedding time of workers. The Contractor shall take care of pest control services for the worksites and workers camp.

4. Ergonomic Hazard

The use of good manual handling and lifting techniques for construction work reduces back issues and other related injuries. The Contractor shall give training regarding correct posture and lifting techniques.

5. Psychological Hazards

The Contractor is required to be assured of all relevant and appropriate working practices that are being followed by the site workers.

Continuous and long working hours and shift can promote fatigue. Fatigue can lead to reduced mental function and attentiveness thus resulting in increased likelihood of accidents and ill health. As most construction activities hold safety risks so this shall not be provoked by fatigue because of unnecessary overtime. Contractor shall ensure local legislation and recommendations on maximum working hours. The Contractor shall ensure that sub-contractors follow the agreed working hours.

6. Health Performance Monitoring and Incident Reporting & Investigation

The Contractor shall have a proper health monitoring system. A medical file shall be kept for each worker.

This file should include their details regarding pre employment fitness to work assessment, details of having any first aid treatment and details of medical checkup. The Contractor shall monitor:

- Numbers of health-related trainings & Audits
- First Aid treatment cases
- Number of workers undergoing medical check ups
- Number of occupational illness cases and frequency

Contractors shall consider health incidents and non-accidental deaths, involving their staff in the same way as they are expected to examine and report safety incidents.

7) Fitness to Work

The Contractor shall classify all worker groups whose specific work or working conditions require a minimum fitness for duty standard.

8) Local Health Facilities and Medical Emergency Response

The Contractor shall provide access to appropriately equipped and staffed hospitals. The Contractor shall provide first aid arrangements at site.

Make sure that proper attention shall be paid to ensure that the required first aid response times are achieved and should be verified by drills.

The Contractor shall develop a site-specific plan based on health risk assessment, which outlines the response to various medical emergency scenarios and evacuation procedures. The Contractor shall arrange for regular drills to exercise and learn from the numerous emergency scenarios.

9) General Health & Safety

Drinking Water

The Contractor shall provide sufficient potable water calculated at 25 litres per person per day, plus at least five days' emergency supply.

Garbage Collection

The Contractor shall provide an appropriate system for garbage collection and disposal. Spillage of refuse should be strictly avoided. Arrangement shall be made for-a daily collection of wastes from construction sites

- Suitable skips or bins should be provided at strategic locations within the project area
- All bins shall be covered or cleaned immediately after being emptied.
- All waste shall be disposed off through approved waste vendor

10) Emergency Preparedness and Response Planning

The 'On-site emergency plan' to be developed by contractor and shall include minimum the following information:

- Site Locations
- Emergency Contact Numbers such as police, fire brigade, bomb disposal, rescue 1122, nearby hospitals and ambulance
- List of emergency equipment including fire extinguishers, fire suits etc.
- Layout maps mentioning the locations of emergency exit points/signs, emergency assembly area, emergency evacuation routes, locations of firefighting equipments and fire alarms
- Identification of Potential Emergency Situations, preventive, control & response measures
- Medical services / first aid

Annexure-Y

CHANCE FIND PROCEDURE

Purpose

The chance find procedure is a project-specific procedure that outlines actions required if previously unknown heritage resources, mainly archaeological resources, are encountered unexpectedly during project construction or operation.

The purpose of this document is to address the likelihood of archaeological deposits becoming visible during altering activities within the project area and to provide procedure to follow in the case of chance cultural and archaeological find to ensure that cultural and archaeological site are documented and protected as required.

Scope

This procedure is applicable to all activities done by the personnel, including contractors, that have the potential to expose a heritage object/site. The procedure outlines the actions to be taken when a previously unknown and potential heritage object/site is found during construction activities.

This Procedure outlines the roles and responsibilities and the response times obligatory from both project staff, and any relevant heritage authority/department.

Training

All personnel, particularly those working on earthwork and excavations, are to be trained on the identification of possible heritage object/sites and the appropriate actions for them with respect to this procedure during the Project briefings and regular toolbox talks.

Procedure

If any person notices a physical cultural resource, such as archaeological, cultural or historical sites, remains and objects, or a graveyard and/or individual graves during excavation or construction work, the following steps shall be taken:

- 1. Immediately stop all construction works in the area of chance find and quickly take photos of the find
- Inform the Contractor or site supervisor who in turn will inform the responsible local authorities or Directorate General of Archaeology, Government of The Punjab (within 24 hours or less)

- 2) Delineate the discovered site or area; secure the site to avert any damage or loss of removable objects. In cases of removable antiquities or sensitive remains are found, a night security guard shall be arranged until the responsible department/authority take over
- 3) Initial assessment of the findings should be done by archaeologists. The archaeologist must make a rapid assessment of the find to determine its importance. Based on this assessment the appropriate plan can be developed. The significance of the findings should be assessed according to the various criteria applicable to cultural heritage such as historic, aesthetic, scientific values of the find
- 4) Sites of minor significance should be recorded immediately by the archaeologist, thus causing a least disruption to the work plan of the Contractor. The results of all archaeological work must be informed to the relevant department, once completed.
- 5) In case of significant find the relevant department (department for protection of heritage hereby referred as heritage team) should be informed immediately and in writing within 7 days from the find
- 6) The onsite archaeologist provides the Heritage team with documents such as photos and information as relevant for identification and assessment of the importance of heritage items.
- **7)** The relevant department must investigate the fact within two weeks from the date of notification and deliver response in writing.
- 8) Decisions on how to handle the finding shall be taken by the responsible authorities. This could include changes in the layout (such as when finding an irremovable remain of archaeological or cultural importance) conservation, preservation and restoration
- **9)** Construction activities/work could recommence only after permission is granted from the responsible authorities.
- **10)**In case no response received from the relevant department/authority within the 2 weeks period mentioned above, this is considered as authorization to continue with suspended construction works.

Annexure-Y

One of the main requirements of the chance find procedure is record keeping. All finds must be registered and maintained by the contactor and LWASA-PMU. Photographs, copies of communication with decision making authorities, conclusions and recommendations must also be kept maintained.

Emergency Contacts

Directorate General of Archaeology, Government of The Punjab <u>archpunjab@gmail.com</u> Anjum Saleem Qureshi Deputy Director (Survey) Office: 04237661964
Annexure-Z

SOCIAL FRAMEWORK AGREEMENT (SFA)

Annexure-Z

SOCIAL FRAMEWORK AGREEMENT (SFA)

It is the commitment by the project proponent and the local community to work together for the successful completion of the project. It establishes bindings for both parties to minimize possible conflicts. SFA shall be considered as a "follow up" of the public consultation and public hearing and indicates that LWASA and the communities are mutually facilitating the construction surface water treatment plant.

Parties to Agreement

SFA will be signed through mutual open consent between the local village leaders and the project proponent. At least two leaders/elders will be chosen from each of the villages situated adjacent to the area where construction activity will be based. These leaders/elders will constitute a villagers committee, which will choose a Chairman among themselves.

SFA shall be signed by LWASA Resident Engineer (RE) representing the project proponent and by the Chairman of villagers' committee representing the local community before two month start of the construction work.

Agreement Contents

SFA shall be prepared in the form of a legal agreement in Urdu language on a stamp paper to be provided by LWASA Resident Engineer (RE) at the project cost. Three copies of the agreement shall be signed by both parties. All the mitigation measures described in EMP which are relevant to SFA shall be included in the agreement. The obligations of the LWASA and those of the community shall be listed clearly. Signed copies of SFA shall be kept by both parties.

Representative and LWASA agreed on that:

- Both parties i.e. LWASA/Contractor and Local representative will follow the terms of this document
- HSE executive will be hired for effective implementation of EM&MP
- Contractor/LWASA will be responsible for local hiring during project
- All work plan activity will be shared with local representative

- Notices will be issued in case of noisy activities
- Contractor/LWASA will be responsible for giving priority to locals for hiring and purchasing raw material
- Contractor/LWASA will be responsible for on time payments
- Contractor/LWASA will be responsible for establishing alternate routes for public in case of higher traffic flow during loading and unloading of raw material
- Contractor/LWASA will be responsible for completing proposed activity within given time
- A complaint cell will be established and a focal person will be appointed by LWASA/Contractor for effective grievance redress
- Contractor/LWASA will be responsible for organizing regular meeting with local representative to share proposed activities
- Contractor/LWASA will be responsible for giving notice to any worker/shopkeeper etc. before terminating its services
- LWASA will be responsible for appointing a person for assessment of overall performance of the contractor, workers and suppliers
- LWASA will be responsible for effective financial auditing

Annexure-AA

EMERGENCY RESPONSE PLAN

Table of Contents

1	SECTION I4				
	1.1		Loc	ation and General Description	4
1.2 Plan Availability			Plar	n Availability	5
	1.3		Eme	ergency Response Organization	5
	1	.3.1		Emergency Response Team Coordinators	5
1.3.2		2	Emergency Response Team Members	6	
1.3.3		3	Authority Level	7	
	1	.3.4	ŀ	Preplanning and Inspection	8
	1	.3.5	5	Emergency Alerting Procedures	8
2	S	EC	TIOI	N II	9
	2.1		Fac	ility Evacuation	9
	2	.1.1		Introduction	9
	2.2		Pers	sonnel Accountability System	9
	2.3		Eva	cuation Procedures	10
	2.4		Eva	cuation: Important Points	11
	2.5		Firs	t Aid & Emergency Medical	11
	2	.5.1		Provisions	11
	2.6		FIR	E	13
	2	.6.1		Pre-Emergency Actions	13
	2	.6.2	2	Associate Actions during a Fire	13
	2	.6.3	3	Manager /operators Actions during a Fire	14
	2.7		HAZ	ZARDOUS MATERIALS	15
	2	.7.1		Pre-Emergency Actions	15
	2	.7.2	2	Associate Actions during a Hazardous Materials Emergency	15
	2	.7.3	3	Supervisor Action during a Hazardous Materials Emergency	16
	2.8		DUS	ST STORM – SEVERE WEATHER	17
	2	.8.1		Pre-Emergency Actions	17
	2	.8.2	2	Actions during A Storm Warning	17
	2	.8.3	3	Actions after a Storm	18
	2	.8.4	ŀ	Manager/ Operator Actions During & After a Storm	18
	2	.8.5	5	Actions for Other Severe Weather Situations	19
	2.9		PO	NER OUTAGE	20
	2	.9.1		Pre-Emergency Actions	20
	2	.9.2	2	Actions during a Power Outage	20
	2	.9.3	3	Manager/ operators Actions during a Power Outage	20

2.10 BC	OMB THREATS	
2.10.1	General Information	
2.10.2	Actions for Personnel Receiving a Bomb Threat	
2.10.3	Associate Actions during a Bomb Threat:	
2.10.4	Manager / operator Actions during a Bomb Threat	
2.11 EA	RTHQUAKE	24
2.11.1	Pre-Emergency Actions	24
2.11.2	Actions During an Earthquake	24
2.11.3	Actions after an Earthquake	24
2.11.4	Manager / operators Actions After an Earthquake	
2.12 FL	OODS	
2.12.1	Pre-Emergency Actions	
2.12.2	Actions during Flooding	
2.12.3	Actions after the Flood	
2.12.4	Responsibilities of Manager/ operators	
3 SECTIO	DN III	
3.1 FL	OW CHARTS	
3.1.1	FIRE	
3.1.2	HAZARDOUS MATERIALS SPILL	
3.1.3	DUST STORM - SEVERE WEATHER	
3.1.4	POWER OUTAGE	
3.1.5	BOMB THREAT	
3.1.6	EARTHQUAKE	
3.1.7	FLOODS	

List of Figures

Figure 1 Fire Response Flow Chart	29
Figure 2 Hazardous Materials Spill Response Flow Chart	30
Figure 3 Dust Storm - Severe Weather Response Flow Chart	31
Figure 4 Power Outage Response Flow Chart	32
Figure 5 Bomb Threat Response Flow Chart	33
Figure 6 Earthquake Response Flow Chart	34
Figure 7 Floods Response Flow Chart	35

List of Tables

Table 1 Description of Manpower During Execution and Operations of the Project	. 4
Table 2 Emergency Response Team Coordinators	.6
Table 3 Emergency Response Team Members	. 6

1 SECTION I

1.1 Location and General Description

The SWTP is proposed at a distance of 4.5 km from BRBD canal towards Ring Road along Bhaini Road. Land in excess to 300 Acres required for SWTP is available at this location. Whole of the area is currently being used for cultivation purpose and no residential or commercial buildings are currently present. Another benefit of this location is that due to less traveling time of treated water the proposed UGT will not be required and single stage pumping will be used. This option may be most feasible as it does not require additional land for UGT and laying of Transmission Main meaning it will have least issues related to ESIA.

96 persons will be employed on contract for the operation of SWTP. The details are given in **Table 1** with their number of posts and designation.

Plant will be operated for specified time, but pumping will be done 24/7 to provide clean water supply to selected areas.

Sr. No.	No. of Posts	Designation
1.	1	Assistant Director Process
2.	1	Assistance Director Operation
3.	1	Assistant Director Maintenance
4.	4	Sub Engineer Civil/ Mechanical/ Electrical
5.	20	Operators
6.	6	Lab Technician
7.	6	Accountant and Account Assistant
8.	4	Electrician
9.	6	Electrician Assistance
10.	4	Mechanic
11.	6	Mechanic Assistance
12.	4	Instrument Technician
13.	6	Naib Qasid
14.	6	Security Guard
15.	2	Store Keeper
16.	6	Drivers
17.	12	Labour (Skilled, Unskilled)
18.	1	Plant Manager, Deputy Director
Total	96	

Table 1 Description of Manpower During Execution and Operations of the Project

This plan is required by the government of Pakistan Rule 18 of Civil Defence 1951.

The Employee Emergency Plan and Fire Prevention Plans standards. The objectives of the plan are to:

- 1. Prevent or reduce the occurrence of emergency at the Surface Water Treatment Plant (SWTP)
- 2. Provide SWTP associates with procedures to follow to prevent or reduce injuries or deaths.
- **3.** Provide SWTP associates with procedures to follow to prevent or reduce damage to property and environment.

The following procedures and explanations cover a wide range of potential emergency situations that could occur at the SWTP. This plan will be extended to include other programs and procedures as they are developed. The Safety, Environmental and Security Team headed by the Plant Manager shall review the entire Emergency Response Plan on an annual basis. Any changes will be recommended to the Team with an explanation as to why the change is needed. Following the approval by the Team revision to the plan will be made; revised copies will be disseminated to the members.

It is recommended to test the plan periodically. A total facility evacuation is recommended at least annually, Smaller drills such as fire in different manufacturing areas or chemical spill emergency drills are recommended on quarterly basis. These drills will prove valuable when conducting the annual plan review.

It must be understood that many emergencies create other emergencies. For example, a fire causes a hazardous materials problem, or hazardous materials may cause a fire. In cases, such as these sections of the plan must be used simultaneously. Finally, no plan can detail all unforeseen events and no plan can replace common sense.

SWTP associates must not panic, they must think clearly and rationally of how they must react. They will be able to do so only through studying, discussing, and rehearsing these emergency response plans.

1.2 Plan Availability

Members of the Team at the SWTP shall be provided a personal copy of the Emergency Response Plan.

1.3 Emergency Response Organization

1.3.1 Emergency Response Team Coordinators

The Emergency Response Team Coordinators will be made before commissioning of SWTP that will include Emergency Coordinator and Assistant Emergency Coordinator.

Emergency Coordinator				
Name				
Title				
Telephone No.				
Mobile No.				
Residence No.				
Assistant Emergency Coordinator				
Name				
Title				
Telephone No.				
Mobile No.				
Residence No.				

Table 2 Emergency Response Team Coordinators

The **Emergency Coordinator** is responsible for ensuring support and providing necessary funding, equipment, facilities and personnel to properly and safely cope with all emergency situations. He shall possess thorough knowledge of the physical layout of the facility and emergency response equipment location and use. The Emergency Coordinator shall direct, guide and supervise personnel involved in emergency response operations. The Emergency Coordinator is the primary contact person for anyone or any agency seeking information regarding Emergency Response Plan.

The **Assistant Emergency Coordinator** is responsible for ensuring that team members are trained in the areas of emergency response as required by this plan. He is also responsible for maintaining the resources needed for emergency response as required by this plan. The Assistant Emergency Coordinator shall possess thorough knowledge of the physical layout of the facility and emergency response equipment location and use. The Assistant Emergency Coordinator will assist the Emergency Coordinator during the emergency operation. In the absence of the Emergency Coordinator the Assistant Emergency Coordinator will have the same authority as the Emergency Coordinator and will direct the operations of emergency response team and shall be primary contact person for anyone or any agency seeking information regarding the Emergency Response Plan.

1.3.2 Emergency Response Team Members

Table 3 Emergency Response Team Members

Sr. No.	Name	Designation	Phone Number
1.			

Sr. No.	Name	Designation	Phone Number
2.			
3.			
4.			
5.			
6.			
7.			
8.			
9.			
10.			
11.			
12.			

Emergency Response Team Members at the SWTP will be trained to respond to specific emergencies. These emergencies include:

- Fires
- Hazardous materials emergencies
- Medical emergencies and injuries
- Confined space emergencies.

Team members will be thoroughly trained and will operate under the direction of the Emergency Coordinator or the Assistant Emergency Coordinator.

1.3.3 Authority Level

All emergency response operations at the SWTP shall be conducted through the use of Incident Command System. The Emergency Coordinator shall fill the role of Incident Commander, in the Emergency Coordinator's absence the role shall be filled by Assistant Emergency Coordinator. The Incident Commander has the authority to commit the resources necessary to safely mitigate the emergency situation. No other personnel may assume control of an incident. The primary command post is recommended to be the security guard's room near the main gate. The Emergency Coordinator shall be located there. A forward command post shall be established in a safe area near the location of the emergency and the Operational Sector shall be located there. During an emergency, the Incident Commander is to work with any public safety agency responding to the call of SWTP to bring the emergency to a safe, successful conclusion.

The Incident Commander shall be responsible for the dissemination of information to the media; public, and provincial, state, or federal authorities The Incident Commander shall follow

the IMCR program and / or utilize someone fulfilling the role of Public Information Officer (PIO) for this task.

1.3.4 Preplanning and Inspection

The Safety, Environmental and Security Coordinator will coordinate preplanning efforts with outside agencies, which may respond to emergencies at the SWTP. This preplanning and coordination may include but not be limited to:

- 1. Facility tours;
- 2. Review of potential emergencies which may occur;
- 3. Review of the SWTP Emergency Response Plan; and,
- 4. Joint training exercise.

To augment associate monitoring the Safety, Environmental and Security Coordinator shall conduct monthly inspections of the entire facility. The goal of these inspections will be to find initial evidence of an impending equipment or process failure that could create an emergency. The safety, Environmental and Security Coordinator shall make recommendations for any emergency response equipment needed to the Higher Management, repairs of equipment or processes shall be submitted through the usual plant procedures.

1.3.5 Emergency Alerting Procedures

SWTP personnel will be warned of an emergency situation by one or combination of the following:

- 1. Microphone
- 2. Smoke detector alarms (located at different points of the production facility);
- 3. Activation of the facility alarm system;
- 4. Verbal warning.

To report emergencies associates should:

- 1. Notify their supervisor or a member of management, whichever is easier or faster; or,
- 2. Notify the security office; or,
- 3. Call 16 (Fire Brigade), 04235850339& 04235850334.
- 4. Call Civil Defence 04239212109 or anti bomb squad 04239212111(if required).
- 5. Activate any one or a combination of the methods listed above; and,
- **6.** If medical assistance is required call Services Hospital 37561351 or Edhi Welfare Trust 37848324, or Rescue 1122, and give the address of SWTP.

2 SECTION II

2.1 Facility Evacuation

2.1.1 Introduction

Evacuation of the SWTP facility is a serious operation in that if handled improperly personnel may become injured or left behind and injured or killed as a result of the emergency. Personnel shall be notified to evacuate the facility by any one or a combination of the methods or devises listed in Section I, under Emergency Alerting Procedures.

Sr. No.	Situation	Action
1.	Fire	Associate discovering a fire, operator and Management at
		their discretion
2.	Hazardous	Any associate in cases of a severe or large spill operators
	materials spill	and management at their discretion
3.	Severe weather	Management;
4.	Floods	Management;
5.	Earthquake	Management;
6.	Power outage	Plant technician Operator and management;
7.	Bomb threat	Operator and management;

The personnel listed shall call for evacuation of the facility in the following situations:

2.2 Personnel Accountability System

At the beginning of shift operators shall make a count of employees in their department or under their supervision. The result of this count will be forwarded to the security office. Security shall post the totals on the personnel accountability roster. This roster shall be updated, as necessary. Also, security personnel shall keep a current count of contractors, visitors, etc. that are on site. This total shall be listed in the appropriate location on the personnel accountability roster.

When an evacuation is called for this personnel accountability roster shall be used to validate the head count, insuring that all persons have evacuated the facility and are accounted for.

The primary assembly area for all persons evacuating the facility will be properly marked.

2.3 Evacuation Procedures

- 1. When personnel are notified to evacuate, they shall immediately proceed to the nearest Emergency exit and leave the building. If the Emergency exit is inaccessible, they should then proceed to the Main and leave the building.
- 2. Movement to exist shall be in an orderly fashion, no one is to run but personnel shall exit without delay. If at all possible, and it will not unduly delay evacuation, personnel operating machinery shall turn the machinery off and /or stop processes in their work area before evacuating.
- 3. While leaving the facility personnel are to assure that no fellow workers, visitors, contractors, etc. are left behind. All offices, work areas, restrooms, break rooms, etc. shall be searched to assure that persons do not remain there. Operators are ultimately responsible for ensuring this is accomplished.
- 4. After leaving the facility all personnel are to report to the Primary Assembly Area. Personnel are to group according to their department assignment at the location marked by sign. Personnel shall remain in this area and shall leave areas of traffic movement clear. If the Primary Assembly Area is not safe for evacuees (due to smoke, vapours, etc.) then personnel should be directed to the Secondary Assembly Area, which shall be the outside facility at the road.
- 5. Operators shall get a head count of personnel in their department and shall report the findings of this head count to the security guard.
- 6. The security guard shall compare the evacuation head count with the personnel accountability roster totals. Any discrepancy will be made known to the Emergency Coordinator, and/or the Assistant Emergency Coordinator, and the person in-charge of responding public safety agencies.
- 7. Operators shall dismiss their personnel from the assembly area only after being informed to do so by the Emergency Coordinator or Assistant Emergency Coordinator. Personnel shall re-enter the facility only when the Emergency Coordinator or Assistant Emergency Coordinator has given an all clear signal.
- 8. The Emergency Coordinator or the Assistant Emergency Coordinator shall assure that public safety assistance has been summoned by calling 16 or 35850339, 35850334 or 36361450, Rescue 1122.
- 9. First aid, if needed, shall be provided by first aid trained personnel.
- **10.** In the event that an evacuation takes place after normal business hours:
 - A. Security shall notify the Emergency Coordinator or Assistant Emergency coordinator;
 - **B.** Security shall notify the country office.

11. Under no circumstances shall any evacuated personnel that are not part of the emergency response operations re-enter the facility until after the all clear is given.

2.4 Evacuation: Important Points

Always remain alert. Emergencies can occur at any time. Wherever you are located in the facility always keep in mind where the nearest exit is located.

Dock doors should never be thought of as exits during emergencies as these doors may be of personnel door type.

All aisles and exit doors are to remain clear at all times. If at any time aisles, exit doors, etc. are found to be obstructed the Safety, Environmental and Security Coordinator is to be notified if the obstruction is not immediately removed.

No plan can take the place of common sense. If you encounter a situation that could cause you harm immediately move to an area of safety and sound an emergency alarm device. Remain alert for:

- Fire
- Smoke
- Chemical vapours or liquids
- Explosions
- Unstable areas or buildings.

If you encounter smoke or chemical vapours always try to move uphill and/or upwind of the material.

Once you have reached the assembly area report to your designed point and remain there for a head count. Never leave this area until told to do so.

Management / Operator: If an evacuation has taken place during inclement weather you must get all evacuated personnel to shelter as soon as possible.

NEVER PANIC DURING AN EMERGENCY!

2.5 First Aid & Emergency Medical

2.5.1 Provisions

Injuries and medical emergencies can occur at any moment and their effects can have profound consequences, even death. Especially if emergency care is applied inappropriately or if it is delayed. Therefore, only trained personnel shall perform first aid measures and they shall be notified immediately when a SWTP associate suffers an injury or medical emergency.

First aid and emergency medical care must be available during hazardous materials; incidents confined space emergencies and are highly recommended to be immediately available during fires.

The SWTP should have trained personnel to provide first aid and CPR in emergency situations. If additional services (i.e. transport to a hospital) or more advanced medical care is needed the Management will request assistance from nearest hospital.

Personnel from local public safety agencies (Civil Defence, Fire Brigade) are not to enter hazardous areas (confined spaces, hazardous materials, spills, etc.) unless they are properly trained and equipped in accordance with applicable regulations.

SWTP personnel that are trained in first aid/CPR shall perform rescue of victims and will remove the victim from the hazardous area. Life saving techniques will not be performed while the victim and rescuer are located in immediately dangerous to life and health (IDLH) environments. Once the victim has been removed from the IDLH area the victim will be moved to the Decontamination Sector (if needed) that the victim will be placed under the care of Hospital.

Should any SWTP associate suffer injuries during normal plant operations? The first aid trained personnel shall be summoned to this person's location to render assistance. If the first aid provider or Management believes it necessary, the EMS will be summoned for further assistance.

If first aid supplies located in strategic areas throughout the facility. Their locations will be marked with stickers. For additional information contact Plant Manager.

2.6 **FIRE**

The purpose of this plan is to give associates procedures to follow, to prevent fires and to follow in case a fire occurs.

2.6.1 Pre-Emergency Actions

- 1. All personnel are to follow fire safety and prevention rules and procedures, and report fire hazards to the operator of the relevant section.
- 2. All personnel are to know the location of the fire extinguisher(s) and fire alarms stations in their work area. Fire extinguisher location is indicated by sticker.
- 3. All personnel are to know the location of the primary fire exit(s) and secondary fire exit(s) nearest their workstation, break room, or other areas they frequent.
- 4. All personnel are to know the location of the Primary Assembly Area and their responsibilities when reporting there.
- 5. All personnel are to know what signals an evacuation and how to call for evacuation of the facility.

2.6.2 Associate Actions during a Fire

2.6.2.1 Small Fire

- 1. If you are trained, promptly direct the discharge of a fire extinguisher at the base of the fire. If you are not trained immediately notify Plant Manager or operator about the fire.
- 2. Notify Plant Manager or operator of the section, follow his instructions.

2.6.2.2 Large or Uncontrolled Small Fires

- 1. Notify Plant Manager or operators immediately.
- 2. Initiate the facility evacuation plan if directed or if no operator is available.
- **3.** If directed to do so, or if no operator is available, from a safe location call 16 or 35850339 or 36361450, Rescue 1122 to report the fire. Notify security that the call to fire brigade has been made or that security should make the call if you were unable to do so. Be prepared to tell 16 or 35850339,35850334 or 36361450

The name of the plant and its location;

- The type of the emergency;
- Your name and the number you are calling from; and
- hang up only when told to do so. •

Remember: Always summon help from safe area.

4. As you are evacuating the facility make sure to check restrooms, offices, break rooms, or other areas where persons may be found that did not hear the call to evacuate or the effects of the fire may have already incapacitated that. Report to the Primary Assembly Area for a head count. Remain in the assembly area, out of the traffic flow areas, until you are given permission to leave.

- 5. Always follow these safety rules for evacuation:
 - Never use an elevator, always use stairs;
 - If smoke is encountered stay close to the ground or floor and crawl to the nearest exit,
 - Test doors with the back of your hand before opening, if stuck, go to another exit;
 - Close doors behind you to contain the fore.

2.6.3 Manager /operators Actions during a Fire

2.6.3.1 Small Fire

- **1.** If you are trained, promptly direct the discharge of a fire extinguisher at the base of the fire. If you are not trained initiate facility evacuation.
- 2. Initiate the facility evacuation plan if necessary. Ensure that all occupants of the facility are evacuating to the Primary Assembly Area. Make sure that no one has been left behind in restrooms, offices, break rooms, etc.
- **3.** Call 16 or 35850339, 35850334 or 36361450, Rescue 1122 from a safe Location to report the fire. If you are unable to place this call notify security to do so.
- 4. Report to the assembly area and take a head count of your personnel. Report the result of your head count to security. Keep all associates in the assembly area until instructed otherwise.

2.6.3.2 Large or Uncontrolled Small Fire.

- 1. Initiate facility evacuation immediately. Ensure that all personnel are evacuating the facility and that no one has been left behind in restrooms, office break rooms, etc.
- **2.** Report to the Primary Assembly Area instruct security to call 16 or 35850339,35850334 or 36361450 to report the fire Take a head count of your personnel and report the result of the head count to security.
- 3. Keep all personnel in the assembly area, out of traffic flow areas, until instructed otherwise.

2.7 HAZARDOUS MATERIALS

Exposure to hazardous materials can cause serious injuries, property and environmental damage. For these reasons it is important to follow established response procedures.

If a spill occurs or is discovered report it to Manager/ Operator and warn others immediately.

Some personnel at the SWTP will be trained in hazardous materials spill response while others have not. Therefore, only personnel that will been trained in hazardous material spill emergency response shall respond to emergency incidents. Personnel that work with chemicals in their normal course of duties may clean up small, non-emergency spills, but then only when wearing appropriate personal protective equipment. A non-emergency spill is one in which assistance from personnel outside of the work area or specialized clean-up equipment is not required to render the situation safe.

To fully protect all SWTP personnel, the facility and the environment, our emphasis will be on spill prevention.

2.7.1 **Pre-Emergency Actions**

- **1.** All personnel shall follow safety procedures and plans when conducting operations involving hazardous materials.
- **2.** All personnel shall complete hazard communication and personnel protective equipment training prior to working with hazardous materials.
- 3. Should question arise involving safety guidance while working with hazardous materials personnel shall seek the assistance of Manager/ Operator? Information can be obtained from the material safety data sheets (MSDS) located in your work area. Any additional information needed can be obtained from the Safety, Environmental and Security head / incharge.

2.7.2 Associate Actions during a Hazardous Materials Emergency

- 1. Do not attempt spill response, containment, or clean up. Notify Manager/ Operator immediately and if necessary, activate the facility evacuation plan. Unless you are authorized to do so, do not go near a chemical spill. But if you can safely control the spill (cut off a valve or switch) from an uninvolved location do so. If the evacuation plan is activated security shall be directed to call 16 or 35850339, 35850334 or 36361450 immediately for public safety assistance.
- 2. If evacuation of the facility is ordered, and you are not trained in hazardous materials spill response, proceed to the nearest exit and go to the Primary Assembly Area. When leaving your work area insure that no one is left behind in rest room, break rooms, etc. Make sure that all personnel, including visitors and contractors are evacuating. Remain at the Primary

Assembly Area for a head count and until you receive further orders. Stay out of traffic flow areas.

- **3.** If you are a member of the Hazardous Materials Response Team respond to the Incident Command Post and await instructions from the Incident Commander.
- 4. If you or a fellow associate has been contaminated by a hazardous material immediately go to the nearest safety shower and activate it. While flushing the contaminated area remove any and all clothing, jewellery, etc. In-plant first aid providers shall be immediately notified, and security shall be directed to call 16 or 35850339, 35850334 or 36361450 for emergency medical assistance. Continue flushing the contaminated area with water for 15-30 minutes or until emergency medical assistance arrives.

2.7.3 Supervisor Action during a Hazardous Materials Emergency

- If the spill is an incidental release (small spills, less than the reportable quantity, that can be cleaned up immediately by area personnel that do not need special equipment or assistance) direct clean-up operations as needed following all recommendations for safe operations and personal protection.
- 2. If the spill is beyond the control of immediately available personnel and resources, activate the facility evacuation plan and direct security personnel to call 16 or 35850339 or 36361450 for public safety assistance. Notify the facility Emergency Coordinator and/or the Assistant Emergency Coordinator. If at all possible, and it is safe to do so, positively identify the spilled material before leaving the area.
- **3.** During evacuation ensure that all personnel, including visitors and contractors, are moving to the primary assembly area. If safe and if it will not delay the evacuation ensures that all machinery is shut down.
- 4. If you are not a member of Hazardous Materials Response Team proceed to the primary assembly area, get a head count of your personnel and report the total to security. Keep all personnel in the primary assembly area, out of traffic flow areas, until instructed otherwise. Remain ready to assist responding public safety agencies.
- **5.** If you are a member of Hazardous Materials Response Team appoint an alternate to perform your duties at the primary assembly area. Report to the incident commander and at the incident command post and await further instruction.

2.8 DUST STORM – SEVERE WEATHER

During severe thunderstorm, the following weather advisories may be issued:

Dust Storm Watch: condition is right for a Dust Storm to occur.

Dust Storm Warning: a Dust Storm has been forecasted by Meteorology Department In case of thunder/ dust storm sign, the Emergency Coordinator, Assistant Emergency Coordinator, managers, and operators on duty shall be notified by the security office via, telephone, or in person.

The Emergency Coordinator and/or Assistant Emergency Coordinator are responsible for ensuring that this plan is enacted. Managers and operators are to advise all associates under their direction, and contractors or visitors in their area, about the weather advisory. At the time of notification everyone must be prepared to take immediate action.

For many weather emergencies there will be ample warning time, for example hale storms, extreme heat or cold, etc. Exceptions are severe thunderstorms and dust storm; current weather forecasting systems offer very little if any warning (no warning will be observed if there is no radio/television monitoring). Therefore, primary emphasis will be placed on these emergencies.

2.8.1 **Pre-Emergency Actions**

- **1.** All personnel shall pre-plan their most frequent work areas so that locations of substantial shelter are noted.
- **2.** All emergency supplies are to be regularly inventoried to maintain adequate amounts. Examples are first aid kits, fire exitnguishers, flashlights, etc.
- 3. Security guard should monitor the weather emergency alert radio (the regular radio) at his post. In the event the Meteorology Department announces that severe weather is in the Lahore area the security guards are to notify the Emergency Coordinator, Assistant Emergency Coordinator, managers, and operator via telephone, or in person.
- 4. Upon receiving this information these persons are to initiate appropriate actions.

2.8.2 Actions during A Storm Warning

- **1.** If possible, shut down any equipment that may be operating, especially operations that involve hazardous materials.
- 2. If you are indoors stay there, but away from windows and glass doors.
- **3.** Immediately proceed to a shelter. If one is not available move to the central or inner-most portion of the building on the lowest floor.

- **4.** Protect yourself by getting under heavy objects like tables, desks, machinery that is bolted to the floor, etc. If no protection is available lay flat and put your hands over your head. If possible, cover your head with a blanket, towel, coat, etc.
- 5. If you are outdoors or in a building of light construction take shelter in a nearby, heavily constructed building if at all possible. If no such buildings are nearby seek shelter in a ditch or ravine. Protect your head and body with anything available. <u>DO NOT TAKE REFUGE</u> NEAR TREES OR UNDER A VEHICLE!

2.8.3 Actions after a Storm

- **1.** Do not re-enter damaged buildings.
- 2. Assist any slight injured personnel to the Primary Assembly Area (parking lot on the East Side of the facility). Personnel with first aid training shall assist the injured. If someone is found to have severe injuries, do not move them unless they are in an area of danger (fire, hazardous materials, structural instability, etc.) and treat their injuries where the injured person is found. Assure that security has called 16 or 850339 or 6361450 and EMS for emergency assistance. Be prepared for this assistance to be delayed as these types incidents can cause wide-spread damage and injuries, thereby over-extending local emergency services.
- **3.** Move to the Primary assembly area. Remain there for a head count and to receive instructions. Stay out of the traffic flow areas. Do not leave the assembly area until you are instructed to do so.
- 4. Do not use the telephone unless absolutely necessary to report emergencies.
- 5. Monitor radio and television broadcasts for emergency information.
- **6.** Cooperate with company and local emergency services officials in returning the facility to working order.

2.8.4 Manager/ Operator Actions During & After a Storm

- 1. If severe weather warnings have been posted ensure the following:
 - A. That all personnel have been notified of this warning;
 - B. That all emergency equipment is in place and operable;
 - C. That all operators have flashlights;
 - **D.** That starting of any operations that would be adversely affected by severe weather have been delayed;
 - E. If Storm **WARNINGS** are in effect for the immediate area have all personnel move immediately to areas of protection.
- 2. If Storm occurs ensure that all personnel evacuate to the Primary Assembly Area after the Storm if the facility suffers any damage. Make sure that this evacuation is done in an

orderly and timely fashion to prevent further injury. If severe weather is continuing and shelter is needed, assemble personnel in a structurally sound building. As you leave your area ensure that machinery has been placed in the off position, and that all personnel (including visitors and contractors) have moved to the Primary Assembly Area.

- **3.** Report to the Primary Assembly Area and get a head count of all personnel under your supervision. Report the result of the head count to security personnel.
- 4. Ensure that the security officer has called 16 or 35850339, 35850334, 36361450 or Rescue 1122 to report the emergency. If the telephones do not work make attempts to call 16 or 35850339, 35850334 or 36361450, Rescue 1122 via a mobile phone or assign someone to report to other neighbouring factory or nearest pay telephone (located at Gulberg main market). Should these systems be inoperable dispatch someone to notify local public safety agencies by reporting to Lahore Fire brigade or Civil Defence Department. If no one is in the fire station this person shall go to the nearest pay telephone and call 16 or 35850339,35850334, 36361450 or Rescue 1122.
- 5. Treat injured personnel as listed above in Actions after a Storm, Bullet No. 2.

2.8.5 Actions for Other Severe Weather Situations

2.8.5.1 Hale storm

- **1.** Stay tuned to local radio and television reports to assess how the problem may be. If reports indicate severe hale storm contact facility management for directions.
- 2. If instructed to dismiss personnel, attempt to assess area road conditions by calling local public safety agencies. See the Emergency Notification List in the appendix of the plan description for the appropriate numbers. Before personnel are dismissed follow proper facility shut down procedures.

2.8.5.2 Rain

1. Refer to the emergency response plan for flooding if necessary.

2.8.5.3 High Winds

1. Refer to items listed above for dust storm if damage occurs to facility property.

2.9 POWER OUTAGE

Many emergencies may cause power outage without warning, but most power outage accompanies severe weather. During periods of severe weather (thunderstorms, hale storms, high winds, etc.) you should anticipate power outages.

2.9.1 **Pre-Emergency Actions**

- **1.** All emergency equipment (Emergency lights, generators, exit signs, emergency lighting systems, first aid kits, etc.) shall be regularly inspected and inventories kept complete.
- **2.** All personnel shall pre-plan their main work areas so that they are familiar with evacuation routes.
- **3.** If severe weather warnings have been issued, starting any operation that would be adversely affected by a power outage should be delayed.

2.9.2 Actions during a Power Outage

- **1.** If the severe weather is in the area, Manager/operators shall retrieve emergency lights from their offices so that they will be capable of assisting with evacuation.
- 2. If a power outage occurs remain calm as emergency lighting should activate almost immediately. If emergency lighting does not activate or if your area is not adequately illuminated, remain at your present location. Do not move, wait for evacuation assistance.
- **3.** Once emergency lighting activates or assistance arrives, place machinery operating switches in the off position before leaving your work station or area.
- **4.** Evacuate, assisting other persons as you go, and report to the Primary Assembly Area (associate parking lot on the south side of the facility)/ Remain in the assembly area, out of traffic flow areas, for a head count and further instructions.

2.9.3 Manager/ operators Actions during a Power Outage

- 1. When severe weather warnings have been issued ensure the following:
 - A. That all personnel have been notified of this warning.
 - **B.** That all emergency equipment is in place and operable.
 - **C.** That all operators have emergency lights and spare batteries.
 - **D.** That the starting of any operations that would be adversely affected by a power outage has been delayed.
- 2. If a power outage occurs, ensure that all personnel are evacuated to the Primary Assembly Area in a timely and orderly fashion. If severe weather is continuing and shelter is needed assemble personnel in a structurally sound building. As you leave your work area ensure that all machinery switches are in the off position.

- **3.** Report to the assembly area and get a head count of your personnel. Report the results of your head count to security personnel.
- **4.** Ensure that the security officer has reported the power outage to the local authorities and be prepared to assist them once they arrive.
- **5.** Dismiss your personnel or allow them back into the facility only when it is safe, and you have been instructed to do so.

2.10 BOMB THREATS

Bombing and the threat of being bombed are harsh realities in today's world. The public is becoming more aware of those incidents of violence that are perpetrated through the illegal use of explosive and other agents. Law enforcement agencies are charged with providing protection for life and properties, but law enforcement alone cannot be held responsible. Every citizen must do his or her part to ensure a safe environment.

This information is designed to help personnel at the SWTP prepare for the potential threat of bomb threats and bombings. While this information is applicable in most cases it cannot be emphasized enough the two most important points when dealing with bomb threats:

- **1.** Be prepared; and,
- 2. Maintain strict access control to all areas of the facility.

2.10.1 General Information

- 1. Develop and maintain strict building access to prevent unauthorized persons from entering the facility. Examples of access control are:
 - A. Security gate access for vehicles.
 - B. Identification badges for all employees, visitors, contractors, etc.
 - C. Security enforce visitor check-in and check-out procedures
 - **D.** Keep all points of entry and exit secured.
- 2. If the assistance of local public safety agencies is requested, they may ask for help from the facility once they arrive, an example would be for search operations. If it is determined safe to do so, and management gives permission, assign personnel that volunteer to assist in the search. Assign associates to specific areas that they will be familiar with, such as areas in which they normally work. Persons that may be of particular assistance are maintenance, engineering, and supervisory personnel.
- **3.** If you volunteer to participate in the search operation and are selected, you must absolutely follow the instructions of management or public safety officials. If a suspicious object is found do not touch or remove it. Immediately report the location of the object to the person in charge of your search area.
- 4. Do not utilize radio/cell phone communication within 1000 feet of the bomb threat location.

2.10.2 Actions for Personnel Receiving a Bomb Threat

If you receive a bomb threat by telephone keeps the caller on the line for as long as possible. Attempt to get as much information as you can use the "Bomb threat Call guidelines." Try to contact someone to monitor the call with you. After the bomb threat caller terminates the call contact one of the following persons:

- Emergency Coordinator;
- Assistant Emergency Coordinator; or,
- Your supervisor.

2.10.3 Associate Actions during a Bomb Threat:

- 1. If ordered to evacuate do so in an orderly manner, report to the Primary Assembly Area (the associate parking lot on the south side of the facility) for a head count. Remain in this area, out of traffic flow areas, until you receive further instructions.
- 2. If you notice anyone in your work area that should not be there notify your supervisor.
- **3.** Keep your area clear of unnecessary packaging, boxes, or trash. This will make it more difficult for someone to leave a bomb device and it go unnoticed.
- 4. Keep all areas of the facility secured as much as possible to prevent unauthorized access.
- If you find a suspicious object or package in any area of the facility <u>DO NOT TOUCH IT!</u> Notify your operator immediately.

2.10.4 Manager / operator Actions during a Bomb Threat

- If evacuation of the facility is initiated make sure your personnel leave the building in an orderly, but swift, manner. Check all locations of your work area to ensure that no one was left behind. Report to the Primary Assembly Area (the parking lot on the East Side of the facility) and get a head count of your personnel. Report the results of the head count to security. Keep all personnel in the assembly area, out of traffic flow areas, until you receive further instructions.
- **2.** Insist that your personnel keep their work areas clear of trash, debris, and unnecessary packaging and boxes.
- **3.** Remain alert for suspicious persons in the facility. If any are noticed, or if a former employee that has been terminated is seen, call security
- 4. Enforce the policy of personnel doors remaining closed and secured when not in use. Periodically check personnel doors in your work area. If dock doors are left open watch for any unauthorized persons entering through them. If an unauthorized person is seen entering the facility notifies security.
- 5. If your personnel find a suspicious object or package evacuate the area and notify the Emergency Coordinator or Assistant Emergency Coordinator. If they are not available, and you decide it is necessary, have security call 16 or 35850339, 35850334, 36361450, anti-bomb squad 9212111 or Civil Defense 9212109 for assistance and initiate this action plan.
- **6.** Assist public safety officials as needed in search operations or investigations. Only personnel who volunteer may be used for search operations.

2.11 EARTHQUAKE

Earthquakes occur without warning. That is why being prepared is so important.

The following plan will help personnel protect themselves and the facility should an earthquake occur.

2.11.1 Pre-Emergency Actions

- 1. Have emergency supplies on hand at all times. Check emergency supplies (i.e. flashlights, batteries, first aid kits, fire extinguishers, etc.). Also, a good inventory of hand tools will prove valuable.
- 2. Know how and where to cut off electricity, gas and water at the facility.
- **3.** Look for heavy equipment or furniture that could topple over on top of you or glass container that could fall and cause injury. In areas where they are used check for flammable liquids that should be kept in flammable liquid storage cabinets. Make sure your fellow associates know where hazardous areas are and how to avoid them.
- 4. Plan and practice what to do if an earthquake should strike.

2.11.2 Actions During an Earthquake

- 1. If time and conditions permit shut down any equipment in your immediate work area.
- 2. If indoors stay there and take cover under sturdy, stationary furniture and equipment such as work tables or desks, or heavy machinery that is immovable. Standing in doorways or in a corner of a room may also provide some protection.
- **3.** Stay away from glass windows and doors that may shatter. Also stay clear of tall bookcases, cabinets and appliances that may shift and fall over. Most casualties in earthquakes that occur due to falling materials.
- **4.** If outdoors stay in open, away from buildings, trees and power-lines, do not near anything, there is danger of falling debris.
- **5.** If driving stop and stay with your vehicle, but make sure that you are not positioned under or on a bridge. Move as far as possible out of the normal traffic pattern. Make sure not to park under trees, power lines, utility poles, signs, etc.

2.11.3 Actions after an Earthquake

 Evacuate the facility as soon as it is safe to do so and report to the Primary Assembly Area for a head count. Assist other personnel as you leave the building. Check personnel for injuries follow first aid procedures and assist disabled persons. Do not leave the assembly area until you are told to do so.

- 2. Be prepared for aftershocks. Earthquakes sometimes occur in a series over a period of several days. Aftershocks may last from a few seconds to as long as five minutes and can occur for months after the original earthquake.
- 3. Do not re-enter damage buildings. Aftershocks can cause the building to collapse.
- 4. Do not use the telephone unless absolutely necessary to report fires, injuries, etc.
- 5. Monitor the radio and television for emergency broadcasts. Cooperate with company and public safety officials. Be prepared for increased response times for local public safety agencies. Damage and injuries can be created in an extensive area during an earthquake and this will overwhelm emergency service agencies.
- 6. Remain alert for gas and water leaks, electrical hazards, and broken sewer lines. Whenever possible turn the utilities off at the source. If you do enter a building do not use open flames for lighting. If you smell gas, ventilate the area, leave quickly and notify your Manager/ operator. Attempt to turn the gas off at a location remote from the leak. Do not re-enter that building until it is safe.

2.11.4 Manager / operators Actions After an Earthquake

- 1. Initiate evacuation of the facility as soon as it is safe to do so. Insure that your work area/department is clear of all persons. Make sure to check offices, break rooms, and restrooms for injured or trapped persons that cannot evacuate unassisted. Insure that all visitors and contractors are evacuating. Instruct all persons to move to the Primary Assembly Area (associate parking lot on the south side of the facility). Report to the results of the head count to the security officer. If someone is missing interview others to try and determine the missing person's last known location. Forward this information to rescue teams.
- 2. Direct or provide first aid services to the injured.
- **3.** Ensure that security has called 16 or 850339 or 6361450 for emergency assistance and that management personnel have been notified. If the telephone system is inoperable attempt to notify local public safety by using a mobile phone. Attempts should be made utilizing both mobile systems If the mobile system is inoperable, assign someone to go to the pay telephones at the Gulberg main market to report the emergency. If these phones are not working this person should have been instructed to go to Fire brigade or civil defence department to report the emergency. If no one is in the fire station instruct this person to use the first available telephone to call 16 or 850339 or 6361450.
- **4.** If it is confirmed that emergency service crews cannot respond, and management gives permission to do so, you may initiate search and rescue operation with volunteer personnel to locate missing associates.

5. During the search and call verbally for the missing person. If someone is located relay this information to local emergency service agencies and request immediate assistance.

2.12 FLOODS

Although the possibility of flooding at this facility is remote, the following plan will help associates protect themselves and the facility should a flood occur.

Some flooding is seasonal, and this can allow for advanced preparation. At other times flooding can occur rapidly (sometimes referred to as flash flooding) and can wash out roads and strand persons with little or no warning. Do not underestimate the power of floodwaters, no matter how shallow or calm the water looks. They can easily kill, injure, and cause great property damage. It is important to use extreme caution during all stages of flooding.

2.12.1 Pre-Emergency Actions

- 1. Secure your work area.
- 2. Secure files and lock up confidential documents. Move these materials to higher ground or floors when possible. Also, important business records in files or on computer disk must also be included.
- 3. Turn off machinery and equipment.
- **4.** Secure hazardous materials and operations according to instructions. Delay starting any operation that could be adversely affected by flooding.
- 5. Protect your equipment to minimize damage.
- 6. Close windows and tape them if possible.
- **7.** Secure any equipment that must be left outside. Of critical importance in containers of hazardous materials. Drums, tanks, etc. can be moved great distances by flood waters.
- 8. Move to higher ground, moving high and try to get away from flood waters. Remember; do not move to areas where you are without and avenue of escape. Do not get near tall trees as lightening could strike. Listen to the radio or television for updates on the flood and for evacuation instructions.
- Regularly check emergency supplies and equipment (i.e., flashlights, first aid kits, etc.).
 For emergency waterproofing gather materials such as plastic sheeting, lumber, and sandbags.
- **10.** Keep company vehicles fuelled. If electrical service is interrupted fuel may not be available.

2.12.2 Actions during Flooding

- 1. Avoid contact with electrical devices, sources, and carriers. While standing in water you are electrically grounded and can be killed with less current than a light bulb uses. Leave utility repairs to the experts.
- **2.** If you are directed to evacuate do not hesitate. Go immediately to the Primary Assembly Area (parking lot on the East side of the facility). Remain there for a head count and further

instructions. Stay out of traffic flow areas. Be extremely cautious if evacuating at night as it will be more difficult to see areas that are flooded. Manager/ operators are to ensure that the facility is swiftly but safely, and completely evacuated.

- **3.** If you are dismissed from the assembly area, return to your vehicle and drive from the area. Remain alert for emergency vehicles in the area. Avoid areas with rivers, streams or other low-laying areas. Do not attempt to drive where water is already over bridges or roads. If walking, do not attempt to cross-areas where the water is above your knees. Do not venture into water without an approved floatation device.
- 4. Continuously monitor news and weather reports.

2.12.3 Actions after the Flood

- 1. Report to the Primary Assembly Area and await directions from management or your operator in charge
- 2. Do not touch electrical equipment in wet areas.
- 3. Report broken utilities to your Manager/ operator.
- **4.** Use only flash lights to examine damaged areas. Remain alert for flammable gas or liquid leaks.

2.12.4 Responsibilities of Manager/ operators

- 1. Stay informed concerning weather systems that may be bringing heavy rains into the Lahore area. If heavy rains are forecasted review emergency actions with associates under your supervision.
- 2. Follow Pre-Emergency Actions as listed in this plan. As associates report to you that precautionary steps are complete inspects those areas to ensure that all direction has been followed.
- **3.** Ensure that emergency equipment in you work area has been inspected and is in adequate supply. Keep emergency light and spare batteries with you.
- **4.** Ensure that all personnel adhere to safety rules regarding actions to take during flood emergencies.
- 5. If evacuation is called for report to the Primary Assembly Area and get a head count of your personnel. Report the results of the head count to security. If necessary, move all personnel to a sheltered area of safety. Keep all personnel out of traffic flow areas.
- **6.** If associated as dismissed and are to leave the facility inform them of any areas known to be flooded and advise them to avoid these areas.
- 7. Cooperate with local public safety agencies.
- **8.** After flood water subside and personnel are allowed back into the facility brief them on actions to take as listed in this plan. Report any utility systems disruption to management.

3 SECTION III

3.1 FLOW CHARTS

3.1.1 FIRE



Figure 1 Fire Response Flow Chart

3.1.2 HAZARDOUS MATERIALS SPILL



Figure 2 Hazardous Materials Spill Response Flow Chart

3.1.3 DUST STORM - SEVERE WEATHER



Figure 3 Dust Storm - Severe Weather Response Flow Chart

3.1.4 POWER OUTAGE




3.1.5 BOMB THREAT



Figure 5 Bomb Threat Response Flow Chart

3.1.6 EARTHQUAKE





3.1.7 FLOODS



Figure 7 Floods Response Flow Chart

Annexure-BB

ENVIRONMENTAL ISSUES TRACKING REPORT

Responsibility Target Tracking No. Log Source Location Issue Action **Completion Status** Date Required date

Environmental Issues Tracking Report

Annexure-CC

SAMPLE: GRIEVANCE LOGGING AND INITIAL RESPONSE FORM

Sample: Grievance Logging and Initial Response Form

Date of Receiving Concern/Grievance						
Mode of Receiving:						
Name of Aggrieved Person/Party						
Name of Organization/Status:						
Position:						
Address:						
Telephone/Fax and Email Address:						
Most effective means to send a response Mail Email Phone						
location of Comment/Grievance						
Nature						
Received by						
Date of initial response						
Initial Response details and sent by						
Resolved/Addressed by						
Nature of Resolution						
Date of Resolution						
Signed by PMU ESS						

Annexure-DD

TOOLS FOR CONDUCTING ESIA (PACKAGES-03 AND 04)

Screening Checklist for Surface Water Supply Network

Sr#	Screening questions	Yes	No	Remarks/Risk severity
				(major, minor, moderate, variable, short or long term)
	PRE-CONSTRU	CTION	PHASE	2
1.	Project Siting			
	Is the project area			
	 Densely populated? 			
	 Heavy with development activities? 			
	 Adjacent to or within any environmentally sensitive areas? 			
	Cultural heritage site			
	Protected Area			
	Wetland			
	 Buffer zone of protected area 			
	 Special area for protecting biodiversity 			
2.	Potential Environmental Impacts of SWTP			
	Will the Project cause			
	 Impairment of historical/cultural monuments/areas and loss/damage to these sites? 			
	 Interference with other utilities and blocking of access to buildings; nuisance to neighbouring 			

	areas due to noise, smell, and influx of insects,		
	rodents, etc.?		
•	Dislocation or involuntary resettlement of		
	people		
•	Impairment of downstream water quality due to		
	inadequate sewage treatment or release of		
	untreated sewage?		
•	Overflows and flooding of neighbouring		
	properties with raw sewage?		
•	Environmental pollution due to inadequate		
	sludge disposal in sewers?		
•	Noise and vibration due to blasting and other		
	civil works?		
•	Discharge of hazardous materials into sewers,		
	resulting in damage to sewer system and danger		
	to workers?		
•	Inadequate buffer zone around pumping and		
	treatment plants to alleviate noise and other		
	possible nuisances, and protect facilities?		
•	Social conflicts between construction workers		
	from other areas and community workers?		
•	Road blocking and temporary flooding due to		
	land excavation during the rainy season?		
•	Noise and dust from construction activities?		
•	Traffic disturbances due to construction material		
	transport		
•	Temporary silt runoff due to construction?		
•	Hazards to public health due to overflow		
	flooding, and groundwater pollution due to		
	failure of sewerage system?		
		1	

	 Deterioration of water quality due to inadequate 			
	sludge disposal or direct discharge of untreated			
	sewage water?			
	 Contamination of surface and ground waters due 			
	to sludge disposal on land?			
	 Health and safety hazards to workers from toxic 			
	gases			
	5			
	CONSTRUCT	ION PH	IASE	
3.	Potential Impacts of Construction of SWTP			
	-			
	a. Existing Communication			
	Disruption to communication routes			
	 Disruption of public access 			
	b. Public Utilities			
	 Interruption of supply, danger and cost 			
	c. Tourism			
	 Imposition of unattractive activities 			
	d. Soil and Water Pollution			
	 Pollution due to temporary activities 			
	 Pollution at the construction camp 			
	e. Drainage, Erosion and Sediment Load			
	 Dispution of aviating drainage networks 			
	- Distuption of existing drainage networks			
	 Erosion from spoil heaps, stock piles and 			
	other loose materials			
			1	

 Increased sediment loading in watercourses 		
f. Noise and Air		
Noise pollution from construction machinery		
Air pollution from construction machinery		
 Mud on public roads 		
g. Demolition		
 Public and Worker's safety 		
h. Use of Explosives		
 Public and Worker's safety 		
i. Surplus Spoil		
Excess fill from pipeline trenches		
j. Employment		
 Temporary local job opportunities for construction workers 		
k. Public Safety		
 General construction activity 		
 Traffic at construction camps 		
 Heavy equipment movement and operation in public areas 		
 Changes in existing traffic circulation 		
l. Worker's Safety		

 Accidents common on construction sites 			
m. Other Sites			
 Increased Heavy Goods Vehicles (HGV) turning movements at sites 			
 Mud and chippings on roads 			
n. Resource Consumption			
 Water use at construction camps 			
 Use of aggregate resources 			
 Water use for construction activities 			
 Haulage (transport) 			
OPERATION	NAL PH	ASE	
4. Potential impacts of Operation of SWTP	Τ		
(Temporary)			
a. Water and Sewage Overflows			
 Raw sewage leakage and due to pipe breakage 			
 Overflow from blocked pumping stations 			
 Overflow from treatment ponds during heavy rain 			
b. Noise and Vibration			
 Noise created during the excavation of pipes 			
for repair			
c. Air Quality			
 Dust from excavations for pipeline repair 			
Dust from excavations for pipeline repair d. Odor			
Dust from excavations for pipeline repair d. Odor Odor from sewers			

	 Overflow from broken pipelines and 		
	blocked manholes		
	f. Traffic		
	 Vehicular movements of operational staff 		
	Septage tankers		
	 Disruptions during network repairs 		
	g. Solid Waste		
	 Broken road surfacing and soil from 		
	pipeline repairs		
	 Sludge 		
	h. Public and Workers Health and Safety		
	 Accidents due to unimpeded public access 		
5.	Potential Impacts of Operation of SWTP		
	(Permanent)		
	a. Public Health		
	 Provision of safe and sustainable water 		
	b. Induced Development		
	 Unplanned development in the vicinity of 		
	water and sewerage services		

Provisional Scoping Matrix

		Scoping Result		Result	Rational of Assessment
No.	Item	Р	С	0	
1. N	Vatural Environment	1	1	1	
1.1	Climate/				
	Meteorological				
	Phenomena				
1.2	Topography				
1.3	Geology				
1.4	Soil Erosion				
1.5	Hydrology				
1.6	Groundwater				
1.7	Ecosystem, Flora,				
	Fauna and Biodiversity				
1.8	Protected area/Forest				

1.9	Coastal Zone				
1.10	Landscape				
1.11	N. ID:				
1.11	Natural Disaster				
2.					
2.1	Air Pollution				
2.2	Offensive Odor				
2.3	Water Pollution				
2.4	Bottom Sediment				
	Contamination				
2.5	Soil Contamination				
2.6	Land Subsidence				
2.7	Noise/Vibration				
2.8	Sunshine Obstruction				

2.9	Waste/Hazardous		
	Materials		

3. S	3. Social Environment					
3.1	Involuntary					
	Resettlement					
3.2	Land Acquisition					
3.3	Utilization of					
	Local Resources					
3.4	General,					
	Regional/City Plans					
3.5	Social Institutions					
3.6	Social					
	Services					
3.7	Local Economy					

3.8	Unequal Distribution				
	of Benefit and				
	Damage				
3.9	Local Conflict				
	and Inequity				
3.10	Water Usage, Water				
	Rights		I		
	rugius		I		
			I		
			I		
3.11	Cultural and				
	Historical Heritage	1			
2.12	Daligious Equilities				
3.12	Religious Facilities	1			
			I		
			I		
			I		
			I		
3 1 3	Sansitiva Facilitias (av				
5.15	Heapitel ashaal		I		
	Hospital, school,		I		
	precision machine		I		
	factory)			ļ	
3.14	Poor People		I		
			I		
			I		
			I		
3.15	Ethnic Minorities				
	/Indigenous People		I		
3.16	Children's Rights			1	
			I		
			I		

3.17	Public Health		
3.19	Occupational		
	Health and Safety		
	(OHS)		

4. C	. Others						
4.1	Accidents						
4.2	Greenhouse Effect Gas						
	(GHG) Emissions						

Note: P: Pre-Construction, C: Construction, O: Operation

Significant impact is expected (+: Positive impact, Negative impact)

Some impact is expected (+: Positive impact, -: Negative impact)

Extent of impact is unknown, further examination will be required (+: Positive impact, -: Negative impact)

No impact is expected

	Rapid Environmental Assessment of P	roposed	Grid S	tation
	Screening Questions	Yes	No	Remarks
	a. Project Sitir	ng		-
•	Is the Project area adjacent to or within any of the following			
	environmentally sensitive areas?			
	Cultural heritage site			
	Protected Area			
	• Wetland			
	• Mangrove			
	• Estuarine			
	Buffer zone of protected area			
	Special area for protecting biodiversity			
	b. Potential Environmen	tal Imp	acts	
•	Will the Project cause			
	✓ encroachment on historical/cultural areas, disfiguration			
	of landscape and increased waste generation?			
	✓ encroachment on precious ecosystem (e.g. sensitive or			
	protected areas)?			
	\checkmark alteration of surface water hydrology of waterways			
	crossed by roads and resulting in increased sediment in			
	streams affected by increased soil erosion at the			
	construction site?			
	✓ damage to sensitive coastal/marine habitats by			
	deterioration of surface water quality due to silt runoff			
	• deterioration of surface water quality due to shi funori, sanitary wastes from worker-based camps and chemicals			
	used in construction?			
	 increased local air pollution due to rock crushing, cutting 			
	and filling?			
	\checkmark chemical pollution resulting from chemical clearing of			
	vegetation for construction site?			
	\checkmark noise and vibration due to blasting and other civil			
	works?			
	\checkmark dislocation or involuntary resettlement of people			
	\checkmark social conflicts relating to inconveniences in living			
	conditions where construction interferes with pre existing			
	roads?			
	 hazardous driving conditions where construction interforce with one evicting reads? 			
	merieres with pre-existing roads?			
	· poor samation and solid waste disposal in construction			
	communicable diseases from workers to local			
	populations?			

v	creation of temporary breeding habitats for mosquito			
	vectors of disease?			
×	in right-of-way of the power transmission lines?			
v	environmental disturbances associated with the			
	maintenance of lines (e.g. routine control of vegetative			
	height under the lines)?			
v	facilitation of access to protected areas in case corridors			
	traverse protected areas?			
v	accident risks associated with maintenance of lines and			
	related facilities?			
	health hazards due to electromagnetic fields, land			
	subsidence, lowered groundwater table, and salinization?			
	disturbances (e.g. noise and chemical pollutants) if			
	herbicides are used to control vegetative height?			
	c. Design Phase Consi	deratio	ns	
•	Site selection for grid stations			
	✓ Poor site selection;			
	✓ unstable soils.			
•	Route selection for transmission lines			
•	Type of equipment.			
•	Soil and water contamination			
	✓ Absence of appropriate waste (solid and liquid)			
	disposal arrangements/systems			
	✓ Using transformers with PCB-containing oil.			
•	Loss of natural Vegetation and threat to wildlife			
	\checkmark Routing the transmission lines through forested and			
	wildlife-sensitive areas			
	d. Construction Phase	Impac	ts	
• •	hysical Environment			
	Land and soil			
	\checkmark Erosion due to excavation			
	✓ Formation of pits due to improper backfilling	_	_	
C	Air and Dust			
	✓ Chronic health affects			
	✓ Reduced visibility on roads			
	, and the second s			
C	Water contamination			
	✓ Wastage and misuse of water			
C	Noise			
	✓ Stress			
	✓ Hypertension			
	✓ Hearing loss			

	✓ Headache		
	• Construction debris		
	 ✓ Formation of heaps ✓ Remaining concrete material results in hardening of 		
	ground surface		
•	Biological Environment		
	• Loss of/damage to the floral 'resources (natural		
	vegetation) of the area		
	✓ Cutting of trees		
	• Loss of/damage to faunal resources (wildlife) of the area.		
•	Social Environment		
	✓ Disturbance to routine market and local business		
	activities		
	✓ Conflicts between laborers and local communities		
٠	Roads and networks		
	✓ Traffic congestion		
	✓ Night time visibility of drivers is reduced		
•	Health and safety		
	✓ Lack of awareness to general public about safety may		
	lead to accidents		
	\checkmark Incompetent and untrained workers might cause harm		
	to themselves and others		
	\checkmark Construction works may include many risks and		
	hazards that may lead to injuries or even death		
	e. Operation phase i	mpacts	 1
•	Soil Contamination		
٠	Water Contamination		
٠	Metrological conditions		
	✓ Heavy rainfall may break damaged overhead		
	transmission lines which may lead to electrical shock		
	hazards		
•	Electric and magnetic field		
	\checkmark Human health impacts such as, neuropsychological		
	disorders or cardiovascular diseases		
•	Transformer oil spillage		
	✓ Contamination of soil and water bodies		

Potential Impacts of Water Treatment works

Key	
Impact Type	Direct, Indirect
Rating Minor, Moderate, Major	
Extent	Limited, wide
Duration Temporary, Short to Long term, Long term,	
	Permanent

Project componen	t: Water Treatment works			
Phase: Construction	on la			
Issue	Potential Impact	Impact Type and Rating	Extent	Duration
Air pollution	 Emissions from construction equipment Emissions from project vehicles. 			
Noise pollution	• Intermittent noise from construction equipment and heavy project vehicles.			
Water pollution	 Water pollution from dredging activities Aaccidental spillage of fuel and lubricants. 			
Water levels	• Water levels may be affected by construction of the impoundment weir and reservoir.			
Soil erosion and contamination	 Inappropriate construction practices Inappropriate soil protection measures which may induce or accelerate soil erosion with possible pollution and siltation of downstream water sources; Removal of top soil may lead to loss of soil fertility 			
Solid waste generation	 Domestic waste from camps may be an eye sore It may contaminate soil and water resources. 			
Impacts on flora and fauna	 Loss of wetland plants and associated fauna; Cleared vegetation may compromise aesthetic value of the sites. 			

Public Safety including accidents as a result of increased vehicular traffic	 Excavations and transportation of equipment, site workers and debris and movement of heavy equipment may pose a safety risk to the general public; Increase in the likelihood of accidents within and around the vicinity of water works area from possible careless driving of project vehicles. Creation of quarries and borrow pits may be a potential for accidents as people and animals can fall in them. Pools of stagnant water may form in
problems	 pits, holes and excavated ditches during the wet season and create suitable habitats for disease vectors such as mosquitoes. Poor hygiene in workers camps.
Occupational health and safety	 Exposure of workers to occupational health and safety hazards from activities such as: excavations; working with heavy equipment; working under noisy conditions, working in confined spaces; lifting of heavy objects; storage, handling and use of hazardous substances and wastes; Poor hygiene and sanitation in workers camps.
Disturbance and interruption of commercial and social activities	Interference with economic livelihoods such as commercial and social activities.
Disruption of social order	 Influx of people in the area which may affect the local economy, cause alteration of culture and introduce undesirable behavioural changes.
Raw material use	 Large quantities of construction material will be involved, for example, cement, steel, oil fuel, pipe materials (e.g. PVC, uPVC, concrete and/or steel). Also, large quantities of local materials, e.g. sand, gravel will be involved. Additional impacts include wet season excavation, creation of quarry sites and borrow pits. If excavated areas are not reinstated and if materials are not well stored and utilized, as well as instituting management measures for waste materials,

	occur.		
Visual amenities •	• Construction sites e.g. creation of pits during excavations, if not well managed, may have impacts on aesthetics of the surroundings with the possibility to affect the neighbouring residents to the SWTP with moderate view point.		

Phase: Operation and maintenance					
Issue	Potential Impact	Impact Type and Rating	Extent	Duration	
Air pollution	• Emissions from generators.				
Noise pollution	• Intermittent noise from generators.				
Water pollution	 Water pollution from discharge of sludge from sedimentation tanks, containing alum; backwash water which may contain silt and dirt. 				
Water levels	• Water levels may be affected by operating the impoundment weir and reservoir.				
Solid waste generation	• Wastes, for example, used containers and packaging materials of alum and chlorine.				
Impacts on flora and fauna	• Discharge of sludge and back wash water.				
Storage and handling of chemicals	• Storage of alum and especially chlorine may induce rusting of holding metallic containers, and even rooftops, if they are made of iron.				
Occupational health and safety	• Exposure of workers to occupational health and safety hazards while working with chemicals, cleaning and disposal, closing and opening of valves.				
Local incapacity/ inexperience to manage the facilities.	• This will lead to poor operation and maintenance as well as deterioration of infrastructure and inadequate monitoring of environmental impacts of project activities.				
Water access	• The poor people within the project area may not afford to pay for the water.				
Conflicts	 Potential for conflicts arising from protection and management of BRBD and its banks; land acquisition. 				

Potential Impacts of Laying of Transmission Main

Key		
Impact Type	Direct, Indirect	
Rating Minor, Moderate, Major		
Extent	Limited, local, wide	
Duration Temporary, Short to Long term, Long term,		
	Permanent	

Project component:	Laying of Transmission Main			
Impact type	Potential Impact	Impact Type and Rating	Extent	Duration
Air pollution	• Emissions from construction vehicles and equipment.			
Noise pollution	Noise pollution from heavy vehicles and construction equipment may cause nuisances to neighbouring communities and their livestock.			
Water pollution	 Water pollution may result from: wastewater from construction camps. accidental spillage of fuels, lubricants and other chemicals. siltation of water courses from runoff laden with sediment and dust. high suspended solids from soil eroded from trenches, poorly constructed tracks. 			
Soil erosion and contamination	 Site clearance of vegetation and excavation works using heavy equipment may induce/accelerate soil erosion and siltation of water courses and gardens. Contamination may occur as a result of accidental or structural spillage of fuels, lubricant chemicals, sanitary wastewater, etc., as well as from leakage from inadequately protected solid waste storage facilities and sites. Soil may lose its fertility because of ramoval of topsoil 			

Solid waste generation	• Vegetation and soil from excavation, as well as waste from contractor's camps, construction waste material, pipe off-cuts and
	packaging material may produce large quantities of waste.
Impacts on flora and fauna	Removal of natural vegetation may lead to potential habitat loss of its associated fauna.
Public health problems	 Public health problems may occur in the case of badly managed construction camps and work sites. These include: Pools of stagnant water may be a source of water borne diseases. Poor hygiene in camps.
Public Safety	 Safety problems at the construction sites may arise from excavations, transportation and movement of heavy equipment. Manually executed works expected to dominate the pipeline laying will take a longer construction time leading to prolonged safety risks such as falling into trenches.
Visual amenities	• Laying of pipelines may have a negative impact on aesthetics of the surroundings such as the soils from the trenches that will be dumped along the trenches
Disturbance and interruption of commercial and social activities	 Improper laying of pipelines may cause traffic disruptions and congestion, resulting in temporary disturbance and interruption of commercial and social activities. It may also cause damage to infrastructure (roads, utility lines) and disruption of public services.
Socio- economic disruption	 Trenches for the pipelines may be dug through peoples" farms destroying crops, in front of shops, displacing stalls along road reserves and other properties which will affect their livelihood and incomes. Furthermore, influx of people in the area may cause alteration of

	culture and introduce behavioral changes.		
Socio- economic disruption	• Trenches for the pipelines will involve some land acquisition.		
Occupational health and safety	 Workers may be exposed to occupational health and safety hazards from project activities such as: accidents in excavations; working with heavy equipment; working under noisy conditions. working in confined spaces; lifting of heavy objects; storage, handling and use of dangerous substances and wastes. 		

Phase: Operation and Maintenance

Issue	Potential Impact	Impact Type and Rating	Extent	Duration
Alteration of natural drainage patterns	• Drainage patterns where pipes cross may be altered by laying of the pipelines, for drainage channels and is blocked at the pipe crossing, it may block or alter the water flow.			
Water pollution	 Water pollution may result from spillage of fuel and lubricants during maintenance; waste disposal along damaged lines may also cause pollution For sewer lines that will be crossing, pollution may arise from leakage of sewage in case the pipes get damaged. 			
Noise pollution	• Noise generated from vehicles used during maintenance or from generators in case they are used to pump the water can be a nuisance to sensitive receptors.			
Air pollution	• This could be in form of emissions from maintenance vehicles.			

Solid waste generation	Solid wastes may be produced by maintenance works, especially where sections of pipelines are replaced.
Soil erosion and contamination	Inspection and maintenance works for the pipelines may require clearance of sites of vegetation, as well as the execution of excavation works, possibly using heavy equipment. This may induce or accelerate erosion.
Impacts on flora and fauna	Inspection and maintenance works may require the removal of the natural vegetation, leading to potential habitat loss of its associated fauna.
Nuisances and public health risks as a result of operational failures of the distribution network	 Accidental ruptures and structural degradation of pipelines that may accrue from ageing and poor maintenance, accompanied by low pressure in the pipes may allow the intrusion of potentially polluted groundwater into the drinking water distribution system. Ruptured pipes may also cause flooding and if the water stagnates, this may pose a risk of water-borne diseases.
Energy consumption	Operation of the water distribution system may involve the use of energy for pumping which will cause a relative increase in energy demand.
Occupational health and safety	 Occupational health and safety problems may arise during maintenance of the pipelines. These may include: lifting of heavy and sharp objects and transportation of materials for maintenance, storage as well as handling and use of dangerous substances.
Local incapacity/ Inexperience to manage the facilities	This will lead to poor operation and maintenance as well as deterioration of infrastructure as well as accidents due to lack of

	 enough technical knowledge in safety requirements for equipment/machinery operation. Inadequate monitoring of environmental impacts of project activities. 	
Disturbance and interruption of commercial and social activities	• Interference with commercial and social activities will be very low.	
Disturbance and interruption of commercial and social activities	 Maintenance activities for the water distribution network may cause traffic disruptions and congestion, resulting in disturbance and interruption of commercial and social activities. Other infrastructure e.g. roads, sewer lines, drains may also be disrupted. 	

Potential Impacts of Disruption to Public Utilities

	Utility	Nature of Impact	Severity
1.	High Voltage	Interruption of Supply	
	Electricity Cables	Personal Injury	
		Cost of Repair/Delay to Works	
2.	Medium Voltage	Interruption of Supply	
	Electricity Cables	Personal Injury	
		Cost of Repair/Delay to Works	
3.	Low Voltage	Interruption of Supply	
	Electricity Cables	Personal Injury	
		Cost of Repair/Delay to Works	
4.	Trunk	Interruption of Supply	
	Distribution	Personal Injury	
	Pipelines	Cost of Repair/Delay to Works	
5.	Local Water	Interruption of Supply	
	Networks	Personal Injury	
		Cost of Repair/Delay to Works	
6.	Telephone Cables	Interruption of Supply	
		Personal Injury	
		Cost of Repair/Delay to Works	
7.	Telecom Cables	Interruption of Supply	
		Personal Injury	
		Cost of Repair/Delay to Works	

Sensitive Receptors Survey Form

A. Identify any sensitive populations/uses that are currently on-site or	On-site	Off-site		
surrounding property usage within 200 - 500 feet of the site property				
boundary				
1. Residences or residential property				
2. Public or Private Schools				
3. Childcare centres.				
4. Public parks, playgrounds or other recreation areas				
5. Religious centres (madrassa, mazaar, mosque etc.)				
6. Other sensitive population use(s)				
7. None of the above				
Note: If any of the above applies, attach a list of addresses, facility names, type of use, and a map depicting				

each location relative to the site

В.	3. Ecological Receptors		Yes	No
	1.	Has an Ecological Evaluation (EE) been conducted		
	2.	Are any site-related contaminants above any Ecological Screening Criteria?		
	3.	Are there any Environmentally Sensitive Natural Resources (ESNRs) on or adjacent to the site, or potentially impacted by site related contamination?		
	4.	Do available data indicate an impact to Ecological Receptor(s)		
	5.	Has an Ecological Risk Assessment been conducted?		

C. Current site uses (check all that apply)

□ Industrial	□ Residential	
□ School or child-care	□ Government	□ Park or recreational use
□ Vacant	□ Agricultural	□ Other:

D.	Planned future on-site uses and off-site uses	On-site	Off-site

1. Industrial	
2. Residential	
3. Commercial	
4. School and Child-care	
5. Government	
6. Park or recreational Use	
7. Vacant	
8. Agriculture	
9. Other	

E. Water Well Inventory			
Summary of Water Wells Within 0.5 Mile Rad	ius of The Site. (DG = Down gradie	nt)	
Nature	Total No.:	Active No.:	
1. Industrial			
2. Domestic			
3. Agricultural			
F. Potential Receptor Points	·		
1. Well No./Designation			
2. Distance from Site (ft.)			
3. Total Well Depth (ft.)			
4. Current use of Water			
5. Screened Interval Below			
Ground:			
6. Year Constructed:			
G. Underground Utility Survey (within 500-f	oot radius)		
1. Nearest Underground Utility			
(Include Name, Type, Depth of Utility,			
Distance and Direction from Affected Zone)			
2. Nearest Down gradient Underground			
Utility			
(Include Name, Type, Depth of Utility,			
Distance and Direction from Affected Zone)			
H. Building/Confined Space Survey (within 500-feet radius)			

1. Nearest Building/Confined Space			
(Include Name, Type, Distance and Direction			
from Affected Zone)			
2. Nearest Down gradient			
Building/Confined Space			
(Include Name, Type, Distance and Direction			
from Affected Zone)			
I. Surface Water Survey (within 500-foot radius)			
1. Nearest Surface Water			
(Include Name, Type, Distance and Direction			
from Affected Zone)			
2. Nearest Down gradient Surface Water			
3. Impacted Surface Water			
(Include Name, Type, Distance and Direction fro			
source area)			
J. Sensitive or Protected Habitat Survey (within 500-foot radius)			
4. Nearest Sensitive or Protected Habitat			
(Include Name, Type, Distance and Direction			
from Affected Zone)			
5. Nearest Down gradient Sensitive or			
Protected Habitat			
K. Current Area Land Use and Zoning			
1. Source property current land use and			
zoning information			
2. Surrounding property current land use and			
zoning within 500' of site (indicate			
direction)			
3. Source of land use and zoning information			

Assessment of Cumulative and Induced Impacts

Questions		Yes	No	Remarks
1.	Is the proposed project within a relatively undisturbed landscape or an already disturbed landscape?			
2.	Do topographic or other constraints spatially limit the impact that the project may have on Valued Environmental Components (VECs)?			
3.	Are there any unmitigated direct impacts (i.e., impacts only of the proposed project)?			
4.	Is there any ongoing significant impact of past actions?			
5.	Do the nearest existing projects to the proposed action have an impact on the same VECs?			
6.	Have any actions been officially announced by other project proponents in the same region with the intent to start the EIA process?			
7.	Have any issues or VECs already been identified in the EIA or by local stakeholders that maybe			
	of concern beyond the footprint of the proposed project?			
8.	Are any ecological species locally or regionally rare?			
9.	Are there any environmentally sensitive areas that may be disturbed?			
10	Would the proposed project contribute to a loss of habitat (terrestrial or aquatic) that may affect the VECs in the study area?			
11	Is there reliable information that describes the VECs and their habitats?			
12	Is there adequate information available about other actions to determine if they are contributing to other than negligible impacts on the same VECs?			
13	Are indicators available to assess impacts on VECs?			
14	Are there indicators of significance, other than thresholds, that should be considered?			
15	Could the action induce other actions to occur (such as road access)?			

16. Can a historical baseline be described against which consecutive changes can be compared?		
17. Are certain analytical approaches mandatory for assessing impacts on some VECs?		
18. Are quantitative thresholds available for any of the VECs?		
19. Are qualitative thresholds available that describe intended land use (e.g., land use plans)?		
20. Is the standard application of mitigation adequate to mitigate significant impacts?		
21. Can reclamation reduce the duration of land disturbance and hasten the recovery of		
environmental components to pre-disturbance conditions?		
22. Is habitat of equivalent capability available elsewhere to compensate for lost habitat?		
23. Is there an opportunity to initiate a regional-level mitigation (or compensation) of impacts?		
24. What is required for monitoring and impact management as follow-up?		

Note: Valued environmental components (VECs) are defined as fundamental elements of the physical, biological or socio-economic environment, including the air, water, soil, terrain, vegetation, wildlife, fish, birds and land use that may be affected by a proposed project.
Socio-economic and Health Survey | Assessment

Interviewer's Name:					Date:		
Q. 1 F	Q. 1 Respondent's Name:						
Q. 2 C	Cell # _			Q. 3 Age (yea	rs):		
Q. 4 E	Q. 4 Education Level						
C	Illite	rate		Primary		Middle	
C	∃ Seco	ndary		Higher Secondary		Graduate	
C] Post	Graduate		Deeni Uloom			
Q. 5 L	Languag	ges Spoken:					
i. Urd	u	ii. Punjabi		iii. English	iv. Oth	ier	
Q. 6	Prese	nt Residential Addres	s:				
Q. 7	Distri	ct:					
Q. 8	Marit	al Status:					
Q. 9	i. ii. iii. Occuj	Married Un-Married Divorced/ Separated pancy Status & Sourc	d/Wi es of	dowed Income:			
	i.	Govt. Servant					
	ii.	Private Service					
	iii.	Business					
		a) Office/comp	bany				
		b) Shop					
	iv.	Agriculture					
	v.	Livestock					
	vi.	Labor					
	vii.	Retired					
	viii.	Any other (Specify))				
Q. 10	Busin	ess Ownership (if off	ice/c	ompany holder or s	hop)		

		i.	Owner			ii.	Rent		
Q. 11	Distan	ce from	Main Road:					_(ft/m)	
Q. 12	Persona	al Incor	ne (Monthly a	average)					
□ R	s. 5,000)15,0	00		□ R	s. 16,00	025,00	0	
□ R	s. 26,00)1-35,00	00			s. 36,00	0-50,000		
□ R	s above	50,000)						
Q. 13	Month	ly Expe	enditure:						
	i.	Less tl	nan 2000				_		
	ii.	2001-5	5000				_		
	iii.	5001-8	3000				_		
	iv.	8001-1	11000				_		
	v.	11001	-14000				_		
	vi.	14001	and above				_		
Q. 14	Housir	ng Cono	lition:						
	i.	Pucca							
	ii.	Katcha	a						
	iii.	Hut							
	iv	Any o	ther (Specify)						
Q. 15	What i	is the ty	pe of the owr	ership of	your ho	ouse? S	Self-Owne	d	Rented
Q. 16	Source	e of Dri	inking Water:						
	i.	Public							
	ii.	Private	e						
	iii.	Any o	ther (Specify))					

Q. 17 Common Diseases:

a. Common cold	b. Diarrhea	c. Typhoid
d. Stomach Worms	e. TB	f. Malaria
g. Goiter	h. Dysentery	i. Hepatitis
j. Other (specify)		

- Q. 18 Total No. of Dependents:
- Q. 19 Age Group and Education Level of Dependents:

Age Group	Male	Education	Female	Education
0-4				
5-9				
10-19				
20-39				
40-59				
60+				

Q. 20 Educational Facilities Available:

				If yes t	hen reply
Sr.	Facilities	Yes	No	Govt.	Private
1	Primary School				
2	Middle School				
3	High School				
4	College				
5	Vocational Training Centers				
6	Deeni Madrassa				
7	Others				

Q. 21 Institutional Facilities Available:

				If yes t	hen reply	
Sr.	Facilities	Yes	No	Govt.	Private	Name
1	Hospital					
2	Dispensary					
3	Basic Health Unit					
4	Post Office					
5	Mosque					
6	Banks					
7	Others					

Q. 22 Means of Transport Available:

LOCAL	INTERCITY
1. Public Transport	1. Public Transport
2. Private Transport	2. Private Transport
3. Pedestrian	3. Pedestrian
4. Others	4. Others

Q. 23 Civic Facilities Available:

Sr. No	Facilities	Yes	No	Remarks if Any
1	Lined Drainage System	1	2	
2	Street Lights	1	2	
3	Grocery Shops	1	2	
4	Recreational / Games Facilities (clubs, grounds)	1	2	
5	Medical Stores	1	2	
6	Graveyards	1	2	
7	Electricity	1	2	
8	Telephone	1	2	
9	Public Water Supply, Sewerage	1	2	
10	Others	1	2	

Q. 24 During construction:

- □ Information about alternative traffic route
- □ Arrangements of utilities backup
- \Box Do nothing and wait for service to be restored
- Q. 25 Does any NGO exists: 1. Yes

2.1

2.No

Q. 26 If Yes:

Sr.No	Name	Status
		1. Local
1		2. National
		3. International
		1. Local
2		2. National
		3. International
		1. Local
3		2. National
		3. International

Q. 27 Do you have any livestock?

L /		Yes_		No	
	If yes,	how much?			
Q.28	Land u	se:			
	i.	Agriculture			
	ii.	Commercial			
	iii.	Residential			
	iv.	Any other			
Q.29	Do yo	u know about t	he subj	ect Project?	
	i.	Yes	ii.	No	
Q.30	In you	r opinion, shou	ld this	Project be	implemented at the proposed location?
	i.	Yes	ii.	No	
	If yes,	then reasons			If no, then reasons
				-	
Q.31	In your	copinion, what	will b	e the possib	le impacts of this Project on the locals?

Q.32 What are the major problems of your area?

Sr.	Types of Problems	Proposed Solutions
1		

2	
3	
4	
5	

Q.33 Are there any historical places/monuments exist?

1. Yes	2. No	

Q.34 If yes:

Sr.	Name	Number	Location (use	e codes)
			Inside $= 1$	Near $= 2$
1	Rock Carvings			
2	Historical Ruins			
3	Old Graveyard			
4	Others			

Q. 35 Capability of the respondent:

i.	High
ii.	Medium
iii.	Low

Q.36 Sources of water

- \Box tap water
- purchased water from a refilling station (where tap water is sold by a private company after it is reportedly re-treated)
- \Box purchased bottled water
- \Box water from filtration plants
- □ regularly collected rain water (in addition to other sources of water)

Q.37 Consistency of service throughout the day and year

- \Box less than 24-hour per day service
- \Box two to three days at a time
- \Box periods of several days without water service
- \Box low water pressure on most days.

Q.38 During interruptions of service or periods of low pressure,

- \Box possession of a household storage tank
- \Box drums or buckets
- \Box Do nothing and wait for water service to return

Q. 39 Storage and treatment practices within the home

- \Box closed containers, such as bottles or covered pitchers,
- open containers (exclusively or in addition to covered containers) uncovered buckets or bowls.
- Q.40 Treat water before drinking
- □ Yes

□ No

- Q. 41 Treatment method
 - \Box by adding chlorine or bleach
 - \Box boiling
 - \Box using a filter, such as coal, sand or cloth (2%).
 - □ by settling (referring to the time the water remained in a tank, drum, or other container).
- Q.42 Do you pay for water service?
 - \Box Yes \Box No

Q.43 Water costs (Rs/month) for water service

- $\Box \text{ LESS THAN 5000} \qquad \Box \text{ 5000} \qquad \Box \text{ 10000}$
- □ 15000 □ 20000 □

Q.44 Cost per month on bottled water or water from a refilling station or truck

Q.45 Water shortage in your area

□ Yes □ No

- Q.46 Does water shortage a
 - \Box A big problem
 - \Box Somewhat a problem
 - \Box No problem at all
- Q.47 Do you believe that tap water is safe to drink?

□ Yes □ No

Q.48 If no, what does make you believe that the water is unsafe for drinking

- □ appearance of the water (dirty, cloudy, has particles in it, or has a strange color)
- \Box it makes them feel ill
- \Box contains bugs or bacteria
- \Box has a bad smell or taste
- \Box contaminated with chemicals or pesticides
- \Box has too much chlorine

Survey Form for Industries Data

Sr#	Information required	Remarks / Evidence
		(documents, pictures)
1.	Digital mapping & coordinates of the project area and surrounding	
	within 10m ²	
2.	Total number of industries	
3.	Type of Industry/Business	
4.	List the primary products produced at this facility	
_		
5.	List raw materials and process additives used	
6	Does production very significantly by season	
0.	Does production vary significantly by season	
7.	List raw materials and process additives used	
8.	Complete the Wastewater Pollutants Checklist	
	 Identify sampling points 	
	 Sampling of effluents discharge from selected industries 	
	 Laboratory testing & analysis of specific parameters 	
9.	Treatment facility in the factory (if any) for pre-treatment of its WW	
	before discharge	
10.	Pictorial evidence of WW discharge by factories within project area	

11.	Characteristics and volume (parameters of WW generated) from each
	selected industry
12.	Status of discharged WW treatment
13.	Information on compliance of WW generated by industry with PEQS
	 List down industry specific PEQs to check the compliance
14.	Disposal of WW
	 Nearby Drain
	Canal
	• River
15.	Do you have, or have you ever applied for or been issued an Industrial
	User Pre-treatment Permit to discharge wastewater to the sewer
	collection system?
16.	Do you have, or have you ever applied for or been issued any other
	Environmental Permits?
17.	Do you have any underground storage tanks at your facility? If yes, list
	contents and volume of each tank?
18.	Do you have any above ground storage tanks at your facility? If yes, for
	each tank, list the contents, volume, whether the tank has any spill
	prevention or containment devices, such as dikes, and procedures for
	draining any containment devices.
19.	Number of WW discharge outlets along River Ravi
20.	Current water usage downstream of River Ravi
21.	Hydrological and hydraulic data of River Ravi

Annexure-EE

Composition of the ESIA Team

Composition of the ESIA Team

Name	Position on team	Organization
Ms. Samina Islam	Team Leader	Perseverance Social and
		Environmental Safeguards (PSES)
Dr. Asim Mahmood	Senior Environment	G3 Consulting Engineering (Pvt.)
	Specialist	Ltd.
Dr. Saamia Saif	Environment Specialist	Perseverance Social and
		Environmental Safeguards (PSES)
Mr. Kamran Nawaz	Social Specialist	Perseverance Social and
		Environmental Safeguards (PSES)
Mr. Maqsood Ahmad	Resettlement Specialist	Perseverance Social and
		Environmental Safeguards (PSES)
Ms. Rizwana Waraich	Poverty and Social Expert	Perseverance Social and
		Environmental Safeguards (PSES)
Mr. Zahid Iqbal	ESIA Social Expert	Perseverance Social and
		Environmental Safeguards (PSES)
Ms. Hajira Saif	Liaison/Coordination	Perseverance Social and
	Manager	Environmental Safeguards (PSES)
Ms. Abeeha Islam	Social Expert	Perseverance Social and
		Environmental Safeguards (PSES)
Dr. Wasim Ahmad Khan	Aqua Biologist	Perseverance Social and
		Environmental Safeguards (PSES)

Dr. Nawaz Chaudhary	Geologist	Perseverance Social and
		Environmental Safeguards (PSES)
Dr. Aleem Chaudhary	Ecologist	Perseverance Social and
		Environmental Safeguards (PSES)
Dr. Iftikhar Ahmad	Hydrologist	Perseverance Social and
		Environmental Safeguards (PSES)
Dr. Kausar J Cheema	Senior Environmentalist	Perseverance Social and
		Environmental Safeguards (PSES)
Ms. Sunaina Ashfaq	Jr. Environmentalist	Perseverance Social and
		Environmental Safeguards (PSES)
Ms. Munazza Khan	Jr. Environmentalist	Perseverance Social and
		Environmental Safeguards (PSES)
Mr. M. Shuaib Kabeer	Environmental Surveyor /	Perseverance Social and
	Data Collector	Environmental Safeguards (PSES)
Mr. S. Mustafain Haider	Environmental Surveyor /	Perseverance Social and
	Data Collector	Environmental Safeguards (PSES)
Mr. Shah Zaib	Environmental Surveyor /	Perseverance Social and
	Data Collector	Environmental Safeguards (PSES)
Mr. Saifullah	Environmental Surveyor /	Perseverance Social and
Mr. Saifullah	Environmental Surveyor / Data Collector	Perseverance Social and Environmental Safeguards (PSES)
Mr. Saifullah Mr. Usman Sheikh	Environmental Surveyor / Data Collector Environmental Surveyor /	Perseverance Social and Environmental Safeguards (PSES) Perseverance Social and
Mr. Saifullah Mr. Usman Sheikh	Environmental Surveyor / Data Collector Environmental Surveyor / Data Collector	Perseverance Social and Environmental Safeguards (PSES) Perseverance Social and Environmental Safeguards (PSES)
Mr. Saifullah Mr. Usman Sheikh Mr. Zain ul Abideen	Environmental Surveyor / Data Collector Environmental Surveyor / Data Collector Jr. Sociologist	Perseverance Social and Environmental Safeguards (PSES) Perseverance Social and Environmental Safeguards (PSES) Perseverance Social and
Mr. Saifullah Mr. Usman Sheikh Mr. Zain ul Abideen	Environmental Surveyor / Data Collector Environmental Surveyor / Data Collector Jr. Sociologist	Perseverance Social and Environmental Safeguards (PSES) Perseverance Social and Environmental Safeguards (PSES) Perseverance Social and Environmental Safeguards (PSES)
Mr. Saifullah Mr. Usman Sheikh Mr. Zain ul Abideen Mr. Rana Jamiullah	Environmental Surveyor / Data Collector Environmental Surveyor / Data Collector Jr. Sociologist Jr. Sociologist	Perseverance Social and Environmental Safeguards (PSES) Perseverance Social and Environmental Safeguards (PSES) Perseverance Social and Environmental Safeguards (PSES) Perseverance Social and
Mr. Saifullah Mr. Usman Sheikh Mr. Zain ul Abideen Mr. Rana Jamiullah	Environmental Surveyor / Data Collector Environmental Surveyor / Data Collector Jr. Sociologist Jr. Sociologist	Perseverance Social and Environmental Safeguards (PSES) Perseverance Social and Environmental Safeguards (PSES) Perseverance Social and Environmental Safeguards (PSES) Perseverance Social and Environmental Safeguards (PSES)
Mr. Saifullah Mr. Usman Sheikh Mr. Zain ul Abideen Mr. Rana Jamiullah Ms. Muqaddas Haidri	Environmental Surveyor / Data Collector Environmental Surveyor / Data Collector Jr. Sociologist Jr. Sociologist Jr. Sociologist	Perseverance Social and Environmental Safeguards (PSES) Perseverance Social and Environmental Safeguards (PSES) Perseverance Social and Environmental Safeguards (PSES) Perseverance Social and Environmental Safeguards (PSES) Perseverance Social and
Mr. Saifullah Mr. Usman Sheikh Mr. Zain ul Abideen Mr. Rana Jamiullah Ms. Muqaddas Haidri	Environmental Surveyor / Data Collector Environmental Surveyor / Data Collector Jr. Sociologist Jr. Sociologist Jr. Sociologist	Perseverance Social and Environmental Safeguards (PSES) Perseverance Social and Environmental Safeguards (PSES) Perseverance Social and Environmental Safeguards (PSES) Perseverance Social and Environmental Safeguards (PSES) Perseverance Social and Environmental Safeguards (PSES)
Mr. Saifullah Mr. Usman Sheikh Mr. Zain ul Abideen Mr. Rana Jamiullah Ms. Muqaddas Haidri Ms. Sara Noor	Environmental Surveyor / Data Collector Environmental Surveyor / Data Collector Jr. Sociologist Jr. Sociologist Jr. Sociologist Jr. Sociologist	Perseverance Social and Environmental Safeguards (PSES) Perseverance Social and
Mr. Saifullah Mr. Usman Sheikh Mr. Zain ul Abideen Mr. Rana Jamiullah Ms. Muqaddas Haidri Ms. Sara Noor	Environmental Surveyor / Data Collector Environmental Surveyor / Data Collector Jr. Sociologist Jr. Sociologist Jr. Sociologist Jr. Sociologist	Perseverance Social andEnvironmental Safeguards (PSES)Perseverance Social andEnvironmental Safeguards (PSES)
Mr. Saifullah Mr. Usman Sheikh Mr. Zain ul Abideen Mr. Rana Jamiullah Ms. Muqaddas Haidri Ms. Sara Noor Mr. Mohammad Shahzad	Environmental Surveyor / Data Collector Environmental Surveyor / Data Collector Jr. Sociologist Jr. Sociologist Jr. Sociologist Jr. Sociologist Jr. Sociologist	Perseverance Social and Environmental Safeguards (PSES) Perseverance Social and Environmental Safeguards (PSES)

Mr. Nadeem Bhutta	Jr. Sociologist	Perseverance Social and
		Environmental Safeguards (PSES)
Mr. Haleem Ahmad	Jr. Sociologist	Perseverance Social and
		Environmental Safeguards (PSES)
Ms. Shazia Rehman	Social Surveyor	Perseverance Social and
		Environmental Safeguards (PSES)
Mr. Nasir Qureshi	Assistant Social Surveyor	Perseverance Social and
		Environmental Safeguards (PSES)
Mr. Attiq-ur-Rehman	Assistant Social Surveyor	Perseverance Social and
		Environmental Safeguards (PSES)
Mr. Mohammad Umer Shah	Assistant Social Surveyor	Perseverance Social and
		Environmental Safeguards (PSES)
Mr. Adnan Ahmad	Assistant Social Surveyor	Perseverance Social and
		Environmental Safeguards (PSES)
Mr. Rana Sajawal	Assistant Social Surveyor	Perseverance Social and
		Environmental Safeguards (PSES)
Ms. Saima Shabbir	Assistant Social Surveyor	Perseverance Social and
		Environmental Safeguards (PSES)
Ms. Zuhra Qurat ul Ain	Assistant Social Surveyor	Perseverance Social and
		Environmental Safeguards (PSES)

Annexure-FF

REFERENCES

REFERENCES

- Environmental and Social Impact Assessment for Lahore Water and Wastewater Management Project (LWWMP), Inception Report (Final) Jxan-2019
- PC-1 of Lahore Water and Wastewater Management Project (LWWMP)-Construction of SWTP at BRBD Canal-June, 2019
- Final Feasibility Study Report of Lahore Water and Wastewater Management Project (LWWMP)-Feb. 2019
- (Japan International Cooperation Agency (JICA) Study in 2010 titled "Preparatory Study on Lahore Water Supply, Sewerage and Drainage Improvement Project")
- Malik, A. (2015). Geotechnical statistical evaluation of Lahore site data and deep excavation design
- Sheikh, M. I. (2010). Role of Environmental Geology for Urbanization of Lahore City Pakistan (Doctoral Dissertation, University of the Punjab, Lahore, Pakistan).
- http://www.gsp.gov.pk/
- Building Code of Pakistan (BCP 2007)
- Ahmad, T. I. (2013). The role of rural women in livestock management: socioeconomic evidences from diverse geographical locations of Punjab (Pakistan) (Doctoral dissertation, Université Toulouse le Mirail-Toulouse II)
- https://www.worldweatheronline.com
- https://wasa.punjab.gov.pk/
- Hassan, G. Z., Hassan, F. R., & Akhtar, S. (2016). Environmental Issues and concerns of Groundwater in Lahore. Proceedings of the Pakistan Academy of Sciences., Life and Environmental Science, 53(3), 163-178.
- Kanwal, S., Gabriel, H. F., Mahmood, K., Ali, R., Haidar, A., & Tehseen, T. (2015). Lahore's groundwater depletion-A review of the aquifer susceptibility to degradation and its consequences. University of Engineering and Technology Taxila. Technical Journal, 20(1), 26.
- Performance of ductile-iron pipe in soils". Journal (American Water Works Association). 60 (6): 645–655.

- Public Works April 15, 1995 Ductile iron mains; Water Supply and Treatment SECTION: Pg. pC34(4) Vol. V126
- Wildman, P. (1990). Methodological and social policy issues in social impact assessment. Environmental Impact Assessment Review, 10(1-2), 69-79.
- Social Indicators of Pakistan-2016, Pakistan Bureau of Statistics
- https://data.worldbank.org/country/pakistan
- Intergovernmental Panel on Climate Change (IPCC) Guidelines for National Greenhouse Gas Inventories, 2006
- World Bank Group, August (2017). ESIA and ESMP Baghdad Water Supply and Sewerage Improvement Project
- National Institute of Environmental Health Sciences (2002)
- International Commission on Non-Ionizing Radiation Protection (ICNIRP) (2001); International Agency for Research on Cancer (2002); U.S. National Institute of Health (2002); Advisory Group to the Radiation Protection Board of the UK (2001), and U.S. National Institute of Environmental Health Sciences (1999))
- U.S. National Institute of Environmental Health Sciences (2002)
- ICNIRP (1998): Guidelines for limiting exposure to time-varying electric, magnetic and electromagnetic fields (up to 300 GHz)
- McGhee, T. J., & Steel, E. W. (1991). Water supply and sewerage (Vol. 6): McGraw-Hill New York.
- Ashraf, U., Hameed, I., & Chaudhary, M. N. (2016). Solid waste management practices under public and private sector in Lahore, Pakistan. Bulletin of Environmental Studies, 1(4), 98-105
- Intergovernmental Panel on Climate Change (IPCC) Guidelines for National Greenhouse Gas Inventories, 2006
- IPCC Fifth Assessment Report (2013)